

Condition Rating	Corresponding Condition
D	Bushings are cracked or have large chips or flashover burns that compromise the safe creepage distance or cementing or fasteners are not secure and cannot be repaired. Bushings need replacement during next planned outage.
E	Bushings are damaged to the extent that there is very high risk of failure in service and an unplanned outage is required to replace bushings immediately.

Table 63: Criteria for Oil Leaks

Condition Rating	Corresponding Condition
A	No evidence of oil leakage, Oil levels are acceptable.
В	Minor oil leaks exist, but no moisture ingress likely.
С	Clear evidence of oil leaks, but rate of loss is not likely to cause any operational or environmental impacts if no repairs are made.
D	Significant oil leakage and probable moisture ingress indicate immediate need for a major reconditioning or replacement.
E	Major oil leakage and moisture ingress resulting in damage/degradation beyond repair.

A.8. Pad-Mounted Transformers

Table 64: Criteria for Service Age

Condition Rating	Corresponding Condition
А	0 to 10 years



Condition Rating	Corresponding Condition
В	11 to 20 years
С	21 to 30 years
D	31 to 40 years
E	41 years or older

Table 65: Criteria for Condition of Enclosure

Condition Rating	Corresponding Condition
A	Good condition as new
С	Poor condition, remedial action required
E	Immediate replacement required

Table 66: Criteria for Condition of Pad

Condition Rating	Corresponding Condition
А	Good condition as new
С	Poor condition, remedial action required
E	Civil structure degraded beyond repairs, unlevel, crumbling cement, trees and vegetation growth; Immediate replacement required



Table 67: Criteria for Oil Leaks

Condition Rating	Corresponding Condition
А	No evidence of oil leakage, Oil levels are acceptable.
В	Minor oil leaks exist, but no moisture ingress likely.
С	Clear evidence of oil leaks, but rate of loss is not likely to cause any operational or environmental impacts if no repairs are made.
D	Significant oil leakage and probable moisture ingress indicate immediate need for a major reconditioning or replacement.
E	Major oil leakage and moisture ingress resulting in damage/degradation beyond repair.

A.9. Overhead Load Break Switches

Table 68: Criteria for Service Age

Condition Rating	Corresponding Condition
A	0 to 10 years
В	11 to 20 years
С	21 to 30 years
D	31 to 40 years
E	41 years or older



Table 69: Criteria for Condition of Insulators

Condition Rating	Corresponding Condition
A	Insulators are not broken and are free of chips, radial cracks, flashover burns, copper splash and copper wash. Cementing and fasteners are secure
С	Insulators are not broken, however there are some major chips and cracks. Some evidence of flashover burns or copper splash or copper wash. Cementing and fasteners are secure
E	Insulators, cementing or fasteners are broken/damaged beyond repair

Table 70: Criteria for Condition of Housing

Condition Rating	Corresponding Condition
A	Housing is clean, free from corrosion, cracks, distortion, abrasion or obstruction.
С	Significant signs of wear with respect to the above listed deficiencies, but the deficiencies are not critical to the safe operation of the switch
E	Housing is damaged/degraded beyond repair, requiring immediate replacement

Table 71: Criteria for Condition of Operating Mechanism

Condition Rating	Corresponding Condition
A	Operating mechanism is in good condition and all parts are moving with adequate speed. No evidence of rust or friction in moving parts



Condition Rating	Corresponding Condition
С	Significant wear of operating mechanism based on the above listed characteristics, but it does not affect safe operation of the disconnect switch
E	Switch operating mechanism defective, damaged, or degraded, requiring immediate replacement

Table 72: Criteria for IR Scan

Condition Rating	Corresponding Condition
A	No hot spots detected; no deficiency identified for switch and no further action required
С	Intermediate temperature rises between 10 to 20°C; maintenance required at next available outage
E	Critical temperature rises larger than 30°C; immediate action is required to correct the issue

A.10. Station Transformers

Table 73: Gas Concentration (ppm) limits

Gas	O2/N2 Ratio <= 0.2				O2/N2 Ratio >0.2			
	Transforme	er Age in Y	'ears		Transformer Age in Years			
	Unknown	1-9	10-30	>30	Unknown	1-9	10-30	>30
H ₂	80	75		100	40	40		
CH4	90	45	90	110	20	20		



Gas	O2/N2 Ratio <= 0.2				O2/N2 Ratio >0.2			
	Transformer Age in Years				Transformer Age in Years			
	Unknown	1-9	10-30	>30	Unknown	1-9	10-30	>30
C ₂ H ₆	90	30	90	150	15	15		
C ₂ H ₄	50	20	50	90	50	25	60	
C ₂ H ₂	1	1	1		2	2		
со	900	900		500	500			
CO ₂	9000	5000 10000		5000	3500	5500		

Table 74: Gas Rate of Change Limits (ppm)

Gas	Maximum (ppm) variation between consecutive DGA samples			
	O2/N2 Ratio <= 0.2	O2/N2 Ratio >0.2		
H ₂	40	25		
CH4	30	10		
C ₂ H ₆	25	7		
C ₂ H ₄	20			
C ₂ H ₂	Any Increase			
со	250	175		



Gas	Maximum (ppm) consecutive DGA sc	variation between Imples		
	O2/N2 Ratio <= 0.2	02/N2 Ratio >0.2		
CO ₂	2500	1750		

Table 75: Criteria for DGA Results

Condition Rating	Corresponding Condition
А	All parameters within acceptable limits
В	1 parameter does not meet acceptability limits.
С	2 parameters do not meet acceptability limits.
D	3 parameters do not meet acceptability limits.
E	4 or more parameters do not meet acceptability limits.

Table 76: Criteria for Oil Quality Tests

Test	Station Transformer Voltage Class	Grade
	U ≤ 69 kV	
Acid Number	≤0.05	А
	0.05-0.20	С
	≥0.20	E



Test	Station Transformer Voltage Class	Grade
	U ≤ 69 kV	
IFT [mN/m]	≥30	А
	25-30	С
	≤25	E
Dielectric Strength [kV]	>23 (1mm gap) >40 (2 mm gap)	A
	≤40	E
Water Content [ppm]	<35	А
	≥35	E

Table 77: Criteria for Service Age

Condition Rating	Corresponding Condition
A	0 to 15 years
В	16 to 30 years
С	31 to 45 years
D	46 to 60 years
E	More than 60 years



Table 78: Criteria for Loading History

Condition Rating	Corresponding Condition
A	Peak Load less than 50% of its rating
В	Peak Load of 50% to 75% its rating
С	Peak Load 75% to 100% its rating
D	Peak Load 100% to 125% of its rating
E	Peak Load Greater then 125% of its rating

Table 79: Criteria for Main Tank Condition

Condition Rating	Corresponding Condition
A	No rust, corrosion, or moisture evident on main tank.
В	No rust or corrosion on main tank, but some evidence of moisture ingress or condensation.
С	Some rust and corrosion on main tank.
D	Significant corrosion on main tank – repairable.
E	Significant corrosion on main tank – degradation beyond repair.



Table 80: Criteria for Cooling Fan Equipment and Control

Condition Rating	Corresponding Condition
A	No rust or corrosion on body of radiators. Fan and pump enclosures are free of rust and corrosion and securely mounted in position. Pump bearings are in good condition and fan controls are operating per design.
В	Normal signs of wear with respect to the above characteristics.
С	One or two of the above characteristics are unacceptable.
D	More than two of the above characteristics are unacceptable. Fan and pump enclosures may be damaged/degraded beyond repair.
E	Fan and pump enclosures damaged/degraded beyond repair.

Table 81: Criteria for Oil Tank Corrosion

Condition Rating	Corresponding Condition
A	No rust, corrosion, or moisture evident on oil tank.
В	No rust or corrosion on oil tank, but some evidence of moisture ingress or condensation.
С	Some rust and corrosion on oil tank.
D	Significant corrosion on oil tank – repairable.
E	Significant corrosion on oil tank – degradation beyond repair.



Table 82: Criteria for Foundation Condition

Condition Rating	Corresponding Condition
A	Concrete foundation is level and free from cracks and spalling. Support steel and/or anchor bolts are tight and free from corrosion. No issues with settling.
В	Normal signs of wear with respect to the above characteristics.
С	One of the above characteristics is unacceptable.
D	Two of the above characteristics are unacceptable.
E	Foundation or supports are damaged/degraded beyond repair.

Table 83: Criteria for Grounding

Condition Rating	Corresponding Condition
A	Ground connections are tight and free of corrosion. Connections are made directly to tanks, radiators, cabinets and supports without any intervening paint or corrosion.
В	Normal signs of wear with respect to the ground connections.
С	One ground connection is visibly detached/missing.
D	Two ground connections are visibly detached/missing.
E	Ground connections are damaged/degraded beyond repair or more than two missing ground connections.



Table 84: Criteria for Oil Leaks

Condition Rating	Corresponding Condition
A	No oil leakage or water ingress at any of the bushing-metal interfaces or at gaskets, weld seals, flanges, valve fittings, gauges, monitors.
В	Minor oil leaks evident, but no moisture ingress is likely.
С	Clear evidence of oil leaks but rate of loss is not likely to cause any operational or environmental impacts.
D	Major oil leakage and probable moisture ingress. If left uncorrected it could cause operational and/or environmental problems.
E	Oil leaks or moisture ingress have resulted in complete failure or damage/degradation beyond repair.

Table 85: Criteria for Oil Level

Condition Rating	Corresponding Condition
A	Transformer oil level is acceptable with insignificant variation from the previous inspection.
В	Transformer oil level is acceptable with noticeable variation from the previous inspection.
С	Transformer oil level is acceptable, but considerable variation from the previous inspection.
D	Transformer oil level is unacceptable. Topped up during inspection.
E	Transformer oil level is unacceptable and could not be topped up; and/or oil level indicates unsafe transformer operation or hazardous rate of oil loss.



Table 86: Criteria for Turns Test Ratio

Condition Rating	Corresponding Condition
А	Maximum Deviation: 0-0.09%
В	0.10-0.29%
С	0.03-0.39%
D	0.40-0.49%
E	≥ 0.5%

Table 87: Criteria for DC Winding Resistance Testing

Condition Rating	Corresponding Condition
A	0-0.49%
В	0.50-2.49%
С	2.5-3.99%
D	4.0-4.99%
E	≥ 5%

Table 88: Criteria for Insulation Resistance

Condition Rating	Corresponding Condition
A	$IR \ge 5 G\Omega$
В	4.0 < IR ≤ 5.0 GΩ



2024 Asset Condition Assessment Technical Report Results and Recommendations

Condition Rating	Corresponding Condition
С	2.5 < IR ≤ 4.0 GΩ
D	0.5 < IR ≤ 2.5 GΩ
E	0 < IR ≤ 0.5 GΩ



APPENDIX H. ERTH Substation Inspection Report





MAINTENANCE INSPECTION REPORT

ERTH Power Corporation 143 Bell St Ingersoll, ON N5C 3K5

Re: Maintenance Inspection Report – Ref: H-23-001

Site: Semi-Annual Inspections (Spring 2023)

Date: June 14, 2023

Index

Introductory	2
Ingersoll Substation MSI	7
Beachville Substation MSI	8
Port Stanley Substation MSI	9
Tavistock Substation MSI	10
Aylmer Substation MSI	
Aylmer Substation MS2	12
Clinton Substation MSI	13
Goderich Substation MS2	14
Goderich Substation MS3	15
Goderich Substation MS4	16
Oil Reports	17



Introductory

Please find the enclosed report for the maintenance work and inspections completed May 16^{th} and 17^{th} 2023 for stations identified below.

Erth Corp cleaned, serviced and tested as required the main power system. A summary of the site findings is listed below for your review. All findings are referenced to the Ontario Electrical Safety Code (OESC) and the International Electrical Testing Association (NETA) where applicable.

All other equipment that ERTH Corp tested appears in satisfactory condition, suitable for continued service. Please contact us should you wish us to provide pricing and services for any or all of the recommended repairs listed in this report.

Oil and dissolved gas analysis:

A snap shot of the diagnostics from the oil and dissolved gas analysis can be found below with the formal report from AVO at the end of this report. The diagnostics, have been placed in order of priority. The bolded text are of areas of concern, and require further investigation and in some cases recommend online surveillance.

Clinton: Serial#: 301687	
DGA Diagnostics Roger's Ratio	Not Determined
Duval Triangles	Triangle 1: Thermal fault (t > 700°C) Diagnostic not applicable – Triangle 4 gas levels normal. Triangle 5: Thermal fault (t > 700°C)
Duval Pentagons	Pentagon 1: High energy discharge Pentagon 2: High energy discharge
Cellulose insulation	CO2/CO ratio = 26 (>20) -Indication of slow degradation of the paper due to low temperature (< 140 °C). Verify insulation condition with furans/methanol tests.
DGA Status	Status 3 - High gas levels and/or probable active gassing. Probably suspicious - perform fault identification and transformer assessment. Take appropriate action based on transformer assessment results and company policy.
Resampling Protocol	Surveillance
AVO Resampling Recommendation	Increase frequency to verify gassing rates. Consider online monitoring and comprehensive engineering assessment.

Recommendation:

- Increase sampling frequency and consider online monitoring.
- Consult a transformer specialist, to discuss appropriate measures. We would suggest Vankooy Transformer Consulting, whom specializes with local Ontario Based Utilities





Goderich MS4	
DGA Diagnostics Roger's	Diagnostic not applicable - Gas levels normal.
Ratio	
Duval Triangles	Diagnostic not applicable – Triangle 1 gas levels normal.
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Diagnostic not applicable – Triangle 5 gas levels normal.
Duval Pentagons	Diagnostic not applicable - Gas levels normal.
Cellulose insulation	CO2/CO ratio = 42 (>20) -Indication of slow degradation of the paper due
	to low temperature (< 140 °C). Verify insulation
	condition with furans/methanol tests.
DGA Status	Status 3 - High gas levels and/or probable active gassing.
	Probably suspicious - perform fault identification and transformer
	assessment. Take appropriate action based on transformer assessment
	results and company policy.
Resampling Protocol	Surveillance
AVO Resampling	Increase frequency to verify gassing rates. Consider online monitoring
Recommendation	and comprehensive engineering assessment.
Dielectric Breakdown ASTM D-1816:	Below limit for in-service oil (40 kV min @ 2mm).

- Increase sampling frequency and consider online monitoring.
- Consult a transformer specialist, to discuss appropriate measures. We would suggest Vankooy Transformer Consulting, whom specializes with local Ontario Based Utilities

Beachville:	
DGA Diagnostics Roger's Ratio	Thermal > 700 °C
Duval Triangles	Triangle 1: Thermal fault (t > 700°C)
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Triangle 5: Thermal fault (t > 700°C)
Duval Pentagons	Pentagon 1: Thermal fault (t > 700°C)
	Pentagon 2: Thermal fault in oil only
Cellulose insulation	CO2/CO ratio = 9 (3< ratio <= 20) - No indication of a fault involving paper
DGA Status	Status 3 - High gas levels and/or probable active gassing.
	Probably suspicious - perform fault identification and transformer
	assessment. Take appropriate action based on transformer assessment
	results and company policy.
Resampling Protocol	Surveillance
AVO Resampling	Increase frequency to verify gassing rates.
Recommendation	Consider online monitoring and comprehensive engineering assessment.

Recommendation:

- Increase sampling frequency and consider online monitoring.
- Consult a transformer specialist, to discuss appropriate measures. We would suggest Vankooy Transformer Consulting, whom specializes with local Ontario Based Utilities



Ingersoll:	
DGA Diagnostics Roger's	Diagnostic not applicable - Gas levels normal.
Ratio	
Duval Triangles	Diagnostic not applicable – Triangle 1 gas levels normal.
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Diagnostic not applicable – Triangle 5 gas levels normal.
Duval Pentagons	Diagnostic not applicable - Gas levels normal.
Cellulose insulation	CO2/CO ratio = 4 (3< ratio <= 20) - No indication of a fault involving paper
DGA Status	Status 3 - High gas levels and/or probable active gassing.
	Probably suspicious - perform fault identification and transformer
	assessment. Take appropriate action based on transformer assessment
	results and company policy.
Resampling Protocol	Surveillance
AVO Resampling	Increase frequency to verify gassing rates.
Recommendation	Consider online monitoring and comprehensive engineering assessment.
Dielectric Breakdown ASTM D-1816:	Below limit for in-service oil (40 kV min @ 2mm).

- Increase sampling frequency and consider online monitoring.
- Consult a transformer specialist, to discuss appropriate measures. We would suggest Vankooy Transformer Consulting, whom specializes with local Ontario Based Utilities

Port Stanley	
DGA Diagnostics Roger's	Diagnostic not applicable - Gas levels normal.
Ralio	
Duval Triangles	Diagnostic not applicable – Triangle 1 gas levels normal.
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Diagnostic not applicable – Triangle 5 gas levels normal.
Duval Pentagons	Diagnostic not applicable - Gas levels normal.
Cellulose insulation	CO2/CO ratio = 10 (3< ratio <= 20) - No indication of a fault involving paper
DGA Status	Status 3 - High gas levels and/or probable active gassing.
	Probably suspicious - perform fault identification and transformer
	assessment. Take appropriate action based on transformer assessment
	results and company policy.
Resampling Protocol	Surveillance
AVO Resampling	Increase frequency to verify gassing rates. Consider online monitoring
Recommendation	and comprehensive engineering assessment.
Dielectric Breakdown ASTM D-1816:	Below limit for in-service oil (40 kV min @ 2mm).

Recommendation:

- Increase sampling frequency and consider online monitoring.
- Consult a transformer specialist, to discuss appropriate measures. We would suggest Vankooy Transformer Consulting, whom specializes with local Ontario Based Utilities

Tavistock	
DGA Diagnostics Roger's	Unit normal.
Duval Triangles	Pentagon 1: Stray Gassing (t < 200°C)
	Pentagon 2: Stray Gassing (t< 200°C)
Duval Pentagons	Diagnostic not applicable - Gas levels normal.
Cellulose insulation	CO and CO2 levels are normal. No indication of a fault involving paper.
DGA Status	Status 2 - Elevated gas levels and/or possible gassing.
	Possibly suspicious - warrants additional investigation. Increase
	surveillance and DGA frequency.
Resampling Protocol	Surveillance
AVO Resampling	Resample within 3 months.
Recommendation	

Recommendation:

- Increase sampling frequency to quarterly and consider online monitoring.
- Consult a transformer specialist, to discuss appropriate measures. We would suggest Vankooy Transformer Consulting, whom specializes with local Ontario Based Utilities



AYLMER				
DGA Diagnostics Roger's	Diagnostic not applicable - Gas levels normal.			
Ratio				
Duval Triangles	Diagnostic not applicable – Triangle 1 gas levels normal.			
	Diagnostic not applicable – Triangle 4 gas levels normal.			
	Diagnostic not applicable – Triangle 5 gas levels normal.			
Duval Pentagons	Diagnostic not applicable - Gas levels normal.			
Cellulose insulation	CO2/CO ratio = 10 (3< ratio <= 20) - No indication of a fault involving paper			
DGA Status	Status 2 - Elevated gas levels and/or possible gassing.			
	Possibly suspicious - warrants additional investigation. Increase			
	surveillance and DGA frequency.			
Resampling Protocol	Surveillance			
AVO Resampling	Routine Screening			
Recommendation				
Dielectric Breakdown ASTM D-1816:	Resample within 3 months.			
Dielectric Breakdown ASTM D-1816:	Below limit for in-service oil (40 kV min @ 2mm).			

- Increase sampling frequency to quarterly and consider online monitoring.
- Consult a transformer specialist, to discuss appropriate measures. We would suggest Vankooy Transformer Consulting, whom specializes with local Ontario Based Utilities

AYLMER - MCBRIEN	
DGA Diagnostics Roger's	Diagnostic not applicable - Gas levels normal.
Ratio	
Duval Triangles	Diagnostic not applicable – Triangle 1 gas levels normal.
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Diagnostic not applicable – Triangle 5 gas levels normal.
Duval Pentagons	Diagnostic not applicable - Gas levels normal.
Cellulose insulation	CO and CO2 levels are normal. No indication of a fault involving paper.
DGA Status	Status 1 - Normal gas levels and no Indication of gassing. Continue routine
	DGA and normal transformer operation.
Resampling Protocol	Surveillance
AVO Resampling	Routine Screening
Recommendation	
Dielectric Breakdown ASTM D-1816:	Resample within 1 year.
Dielectric Breakdown ASTM D-1816:	Below limit for in-service oil (40 kV min @ 2mm).
De se un un de tie un	

Recommendation:

- Routine maintenance.

Goderich MS3	
DGA Diagnostics Roger's	Diagnostic not applicable - Gas levels normal.
Ratio	
Duval Triangles	Diagnostic not applicable – Triangle 1 gas levels normal.
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Diagnostic not applicable – Triangle 5 gas levels normal.
Duval Pentagons	Diagnostic not applicable - Gas levels normal.
Cellulose insulation	CO and CO2 levels are normal. No indication of a fault involving paper.
DGA Status	Status 1 - Normal gas levels and no Indication of gassing.
	Continue routine DGA and normal transformer operation.
Resampling Protocol	Routine Surveillance
AVO Resampling	Resample within 1 year.
Recommendation	
Dielectric Breakdown ASTM D-1816:	Below limit for in-service oil (40 kV min @ 2mm).

Recommendation:

- Routine maintenance.





Clinton - Serial#: 062108	
DGA Diagnostics Roger's	Diagnostic not applicable - Gas levels normal.
Ratio	
Duval Triangles	Diagnostic not applicable – Triangle 1 gas levels normal.
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Diagnostic not applicable – Triangle 5 gas levels normal.
Duval Pentagons	Diagnostic not applicable - Gas levels normal.
Cellulose insulation	CO and CO2 levels are normal. No indication of a fault involving paper.
DGA Status	Status 1 - Normal gas levels and no Indication of gassing. Continue routine DGA
	and normal transformer operation.
Resampling Protocol	Surveillance
AVO Resampling	Routine Screening
Recommendation	
Dielectric Breakdown ASTM D-1816:	Resample within 1 year.

- Routine maintenance.



Ingersoll Substation MSI

Site: Substation # MS1 Address: 110 Mill Street, Ingersoll

Findings:

- Leaves were cleaned up within the transformer station.
- Battery bank still has a positive ground fault indicator.





Beachville Substation MSI

<u>Site: Substation # MS1</u> <u>Address: 434839 Zorra Line, Beachville</u>

Findings:

- Vines are growing along / through the South-West corner and side of the fence.
- The service for the heater in the main incoming switch still needs to be completed.
- The transformer and switch should be painted.







Port Stanley Substation MSI

Site: Substation # MSI Address: 288 Carlow Road, Port Stanley

Findings:

• The fan controller no longer has 120/240V since the station building was taken out of service. Temperature of the transformer should be monitored and kept below 65 °C. A new service could be installed on the pole in the station if required.





Tavistock Substation MSI

Site: Substation # MS1 Address: 17 Decew Street West, Tavistock

Findings:

• Power has never been routed to the fan controller. Temperature of the transformer should be monitored to see if it is necessary to install power.





Aylmer Substation MSI

Site: Substation # MS1 Address: 118 Myrtle Street, Aylmer

Findings:

• A cedar tree is growing through the North-West corner of the fence.





Aylmer Substation MS2

Site: Substation # MS2 Address: 209 Caverly Road, Aylmer

Findings:

- Both transformers have one fan that is seized and not operational. Each transformer still has 3 functioning fans. All fan nameplate data was recorded in the event replacements are requested.
- Weed spray is needed soon.







Clinton Substation MSI

Site: Substation # MS1 Address: 17 Park Lane, Clinton

Findings:

• The breaker was found off for the fan controller. When testing the fans, it was found that the fans turn on in auto or manual switch positions. The breaker was turned off prior to leaving the station.



Goderich Substation MS2

Site: Substation # MS2 Address: 211 Britannia Road East, Goderich

Findings:

- Weeds were pulled and removed from the station.
- The fan controller and timer were both found in the off position. The operation of the fans was verified and the controls were left in the off position prior to leaving the station.
- Emergency light unit at the main entrance does not work and requires a new battery.





Goderich Substation MS3

<u>Site: Substation # MS3</u> <u>Address: 436 Mooney Street, Goderich</u>

Findings:

• A "DO NO OPERATE POWER FUSES" sign is required on the tower switch.

OESC Rule # 36-006 (3) - Suitable warning signs shall be erected in a conspicuous place adjacent to fuses and shall warn operators not to replace fuses while the supply circuit is energized.

• A single line diagram is required on the metal enclosed switchgear.

OESC Rule # 36-006 (5a) - A permanent, legible, single-line diagram of the switchgear shall be provided in a conspicuous location within sight of the switchgear, and this diagram shall clearly identify interlocks, isolation means, and all possible sources of voltage to the installation under normal or emergency conditions, including all equipment contained in each cubicle, and the marking on the switchgear shall cross reference the diagram;

• Conservator shows slightly less than 25°C while temperature gauge is at 25°C. Some oil should be added during the next outage.





ERTH Power – 2023 Substation Maintenance Report



Goderich Substation MS4

<u>Site: Substation # MS4</u> <u>Address: 77 Lee Street, Goderich</u>

Findings:

- All leaves within the station were bagged and taken away.
- The fan controller and timer were both found in the off position. The operation of the fans was verified and the controls left in the off position prior to leaving the station.





Oil Reports



AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 005 000 0007 005 000 000

TEST REPORT 01-7647787-701058-00

DIAGNOSTIC SERVICES		905-632-8697 + 905-632-8698 Page 1 WWW.AVODIAGNOSTICS.COM					Page 1 of 2	
ERTH (Holdings) Inc		Serial#:	301687 Mfr: FERRANT PACKARD		FERRANTI PACKARD	Control#:	7647787	
		Location:	CLINTON		kV:	27.6	Order#:	701058
		Equipment:	RMER	kVA:	5000	Account:	110229	
INGERSOLL, . N5C2N9 C	A	Compartment: MAIN(BOTTOM)			Year Mf'd:	1971	Received:	06/06/2023
ATTN: MARC GALECKAS	6	Breathing:	- /	Svringe ID:	8001815	Reported:	06/28/2023	
PO#: POH007255		Bank:	Phase: 3		Bottle ID:			
Project ID: H-23-001		Fluid: MIN	USGal: 60)7	Sampled By:	CC		
Customer ID: MS1								
		Lab Control Number	:	7647787	7590311	7535757	7505531	7425759
		Date Sampled	1: 05	5/17/2023 0	9/20/2022	04/06/2022	10/21/2021	02/10/202 ⁻
		Order Number		701058	686680	674258	666239	647030
		Oil Temp	:	45	40	45	45	45
Dissolved Gas Analysis ((DGA)	O2/N2 Ratio	:	0.05	0.06	0.07	0.07	0.04
ASTM	- /	Transformer Age (vrs)	:	52	51	51	50	50
D-3612 ¹		Hvdrogen (H2) (uL/L)	:	101	85	84	85	80
		Methane (CH4) (uL/L)	:	10	9	9	10	1
		Ethane (C2H6) (uL/L)	:	3	3	3	3	
		Ethvlene (C2H4) (µL/L)	:	121	107	114	119	116
		Acetylene (C2H2) (µL/L)	:	<1	<1	<1	<1	<′
	Carb	on Monoxide (CO) (µL/L)		601	555	638	687	759
	Car	bon Dioxide (CO2) (µL/L)		15810	14705	16222	15971	1640
		Nitrogen (N2) (uL/L)		64201	55251	68634	70234	76472
		Oxvgen (O2) (µL/L)		3257	3056	4508	4602	3439
				ingranding IEEE	E Std CE7 404 20	40		
		Dissolved Gas P	analysis D		- 510 057.104-20			
	Absolu	Diute Gas Levels (μL/L) Gas Level Deltas(μL/L) Gas Generation Rates (μl (2 most recent samples) (3-6 most recent samples with			Generation Rates (µL t recent samples with	/L per yr) in 4-24 mos.)		
Gas	Level	Diagnostic	Delta	Delta Diagnostic		Rate	Diagnost	ic
Hydrogen (H2)	101	Elevated (> 100)	16	Normal Variation	(<= 40)	10	No active gassing (<=	20)
Methane (CH4)	10	Normal (<= 110)	1	Normal Variation	(<= 30)	0	No active gassing (<=	10)
Ethane (C2H6)	3	Normal (<= 150)	0	Normal Variation	(<= 25)	0	No active gassing (<=	9)
Ethylene (C2H4)	121	Elevated (> 90)	14	Normal Variation	(<= 20)	1	No active gassing (<=	7)
Acetylene (C2H2)	<1	Normal (<= 1)	0	Normal Variation	(<= 0)	0	No active gassing (<=	0)
Carbon Monoxide (CO)	601	Normal (<= 900)	46	Normal Variation	(<= 250)	-61	No active gassing (<=	100)
Carbon Dioxide (CO2)	15810	High (> 14000)	1105	Normal Variation	(<= 2500)	-320	No active gassing (<=	1000)
DGA Diagnostics	Roger's Ratio	 s Not Determined io 						
Duva	l Triangles	gles Triangle 1: Thermal fault (t > 700°C) Diagnostic not applicable – Triangle 4 gas levels normal. Triangle 5: Thermal fault (t > 700°C)						
Duval I	Pentagons	Pentagon 1: High energy discharge Pentagon 2: High energy discharge						
Cellulose	insulation	CO2/CO ratio = 26 (>20) condition with furans/meth	-Indication nanol tests.	of slow degradatic	on of the paper du	e to low temp	perature (< 140 °C). Ve	erify insulatior
D	GA Status	Status 3 - High gas levels transformer assessment.	and/or pro Take appr	bable active gassi	ng. Probably sus ed on transforme	picious - perf	orm fault identification a	and olicy.
Becomplin	a Protocol	Surveillance						

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , μg/m, μL/L = ppm, μg/L = ppb, mN/m = dynes/cm, mm²/s = cSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AVO			TEST REPORT 01-7647787-701058-00 Page 2 of 2					
DIAGNOSTIC SERVICES	5			WWW.AVODIAG	NOSTICS.COM			Tage 2 01 2
ERTH (Holdings) Inc			Serial#: 3	01687		Mfr: FERRANTI PACKARD		7647787
			Location: (CLINTON			Order#	701058
		E	quipment: T	FRANSFORMER k		k VA: 5000	Account	110229
INGERSOLL, . N5C2NS	9 CA	Con	npartment: N	/AIN(BOTTOM)	Year	Mf'd: 1971	Received	06/06/2023
ATTN: MARC GALECH	KAS		Breathing: S	SEAL	Syring	e ID: 8001815	Reported	06/28/2023
PO#: POH007255			Bank: F	hase: 3	Bottl	e ID:		
Project ID: H-23-001			Fluid: MIN L	JSGal: 607	Sampleo	By: CC		
Customer ID: MS1				1				
		Lab Con	trol Number:	7647787	7590311	7535757	7505531	7425759
		Da	te Sampled:	05/17/2023	09/20/2022	04/06/2022	10/21/2021	02/10/2021
		Or	der Number:	701058	686680	674258	666239	647030
			Oil Temp:	45	40	45	45	45
AVC	O Resampling	Increase freq	uency to verif	y gassing rates. Cor	nsider online monito	ring and comprehe	nsive engineering as	sessment.
Reco	ommendation							
Comment:	200)							
General OII Quality (G	Moioturo i		(ma/ka)	21	20	22	20	11
ASTM D-1555	Interfected T	noin	(mg/kg): (mN/m);	21	3Z 25 42	22	30 25 01	11
ASTM D-971		ension	(mn/m): (ma KOU/a):	30.02	30.42	30.10	0.005	30.21
ASTM D 45001		ibei		0.030	0.022	0.024	0.025	0.020
ASTM D-1500	Viewel Ex		(ASTIVI).		LI.J			
A311WI D-1524	VISUALEX	am.	(Relative).					
ASTM D-15241	Sodimont F	vam	(Polativo):					
ASTM D-18161 Di	oloctric Broak	-vani.		60 (23 C)	73 (24 C)	A1 (22 C)	14 (23°C)	59 (24°C)
ASTM D-40521	Donsity @	15°C	(a/mL):	0.8033	0.8033	0.80/	0 80/1	0.8013
GOO Diagnostics	Density @	Mo	isturo in Oil:	Accentable for in-se	arvice oil (35 ma/ka	may)	0.0041	0.0010
PFR IFFF C57 106-20	15	Interfa	cial Tension:	on: Acceptable for in-service oil (25 mN/m min)				
(most recent sample)		Δ	cid Number	iber: Acceptable for in-service oil (0.2 mg KOH/g max)				
	C	Color Numbe	r and Visual	isual: Diagnostic not applicable. Diagnostic not applicable				
	Dielectric E	Breakdown A	STM D-1816:	Acceptable for in-se	ervice oil (40 kV min	@ 2mm).		
Comment:						<u> </u>		

End of Test Report

Authorized By:

and

JANET KAROLAT SUPV CHEMIST

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698

TEST REPORT 01-7647789-701058-00

Page 1 of 2

DIAGNOSTIC SERVICES	WWW.AVODIAGNOSTICS.COM						
ERTH (Holdings) Inc	Serial#: 225151		Mfr:		Control#: 7647789		
	Location: BE	ACHVILLE		kV: 27.6	Order	#: 701058	
	Equipment: TR	ANSFORMER	k	VA: 3000	Accoun	t: 110229	
INGERSOLL, . N5C2N9 CA	Compartment: MA	IN(BOTTOM)	Year M	f'd: 1976	Received	d: 06/06/2023	
ATTN: MARC GALECKAS	Breathing: SEAL		Syringe ID: 8003346		Reported	d: 06/28/2023	
PO#: POH007255	Bank: Phase: 3		Bottle ID:				
Project ID: H-23-001	Fluid: MIN USGal: 574		Sampled By: CC				
Customer ID: MS1							
	Lab Control Number:	7647789	7590319	7535750	7515375	7425750	
	Date Sampled:	05/16/2023	09/29/2022	04/05/2022	11/30/2021	02/11/2021	
	Order Number:	701058	686680	674258	668835	647030	
	Oil Temp:	40		38	30	20	
Dissolved Gas Analysis (DGA)	O2/N2 Ratio:	0.2	0.21	0.2	0.2	0.21	
ASTM	Transformer Age (yrs):	47	46	46	45	45	
D-3612 ¹	Hydrogen (H2) (µL/L):	4	5	4	4	4	
	Methane (CH4) (µL/L):	12	11	11	12	13	
	Ethane (C2H6) (ul /l.):	5	Δ	Δ	5	5	

Methane (CH4) (µL/L):	12	11	11	12	13
Ethane (C2H6) (µL/L):	5	4	4	5	5
Ethylene (C2H4) (µL/L):	72	67	64	69	71
Acetylene (C2H2) (µL/L):	<1	<1	<1	<1	<1
Carbon Monoxide (CO) (µL/L):	952	908	829	931	977
Carbon Dioxide (CO2) (µL/L):	8943	8885	7752	8790	8349
Nitrogen (N2) (µL/L):	67950	63595	64025	69111	71385
Oxygen (O2) (μL/L):	13857	13422	12604	13895	14827

Dissolved Gas Analysis Diagnostics – IEEE Std C57.104-2019

	Absolu	Gas Levels (µL/L) Gas Level Deltas(µL/L) (2 most recent samples)		Gas Generation Rates (μL/L per yr) (3-6 most recent samples within 4-24 mos.)				
Gas	Level	Diagnostic	Delta	Diagnostic	Rate	Diagnostic		
Hydrogen (H2)	4	Normal (<= 40)	-1		0	No active gassing (<= 10)		
Methane (CH4)	12	Normal (<= 20)	1	Normal Variation (<= 10)	0	No active gassing (<= 3)		
Ethane (C2H6)	5	Normal (<= 15)	1	Normal Variation (<= 7)	0	No active gassing (<= 2)		
Ethylene (C2H4)	72	Elevated (> 60)	5	Normal Variation (<= 20)	3	No active gassing (<= 5)		
Acetylene (C2H2)	<1	Normal (<= 2)	0	Normal Variation (<= 0)	0	No active gassing (<= 0)		
Carbon Monoxide (CO)	952	High (> 600)	44	Normal Variation (<= 175)	37	No active gassing (<= 80)		
Carbon Dioxide (CO2)	8943	High (> 8000)	58	Normal Variation (<= 1750)	386	No active gassing (<= 800)		
DGA Diagnostics	Roger's	Thermal > 700 °C						
	Ratio	tio						
Duval	Triangles	Triangle 1: Thermal fault (t > 700°C)						
		Diagnostic not applicable – Triangle 4 gas levels normal.						
Duval Pentagons Pentagon 1: Thermal fault (t > 700°C) Pentagon 2: Thermal fault in oil only								
Cellulose	insulation	ation CO2/CO ratio = 9 (3< ratio <= 20) - No indication of a fault involving paper						
D	DGA Status Status 3 - High gas levels and/or probable active gassing. Probably suspicious - perform fault identification and transformer assessment. Take appropriate action based on transformer assessment results and company policy.					orm fault identification and results and company policy.		
Resampling	ing Protocol Surveillance							
AVO R	AVO Resampling Increase frequency to verify gassing rates. Consider online monitoring and comprehensive engineering assessment.					ensive engineering assessment.		

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , μg/m, μL/L = ppm, μg/L = ppb, mN/m = dynes/cm, mm²/s = cSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.
DIAGNOSTIC SER	RVICES	919 FRAS	AVO DIAGNOS ER DR. UNIT 13 + E 905-632-8697 + WWW.AVODIAG	+ L7L 4X8	01-764	TEST REPORT 17789-701058-00 Page 2 of 2	
ERTH (Holdings) Ir	C	Serial#: 2	25151		Mfr:	Contro	l#: 7647789
		Location: E	BEACHVILLE		kV: 27.6	Orde	r#: 701058
		Equipment: 7	RANSFORMER		kVA: 3000	Accou	nt: 110229
INGERSOLL, . N50	C2N9 CA	Compartment: N	MAIN(BOTTOM)	Year	Mf'd: 1976	Receive	;d: 06/06/2023
ATTN: MARC GAL	TTN: MARC GALECKAS Breathing: \$ 0#: POH007255 Bank: F		SEAL	Syring	e ID: 8003346	Reporte	: 06/28/2023
PO#: POH007255			Phase: 3	Bottl	e ID:		
Project ID: H-23-0	01	Fluid: MIN L	JSGal: 574	Sampleo	By: CC		
Customer ID: MS1							
	Lab	Control Number:	7647789	7590319	7535750	7515375	7425750
		Date Sampled:	05/16/2023	09/29/2022	04/05/2022	11/30/2021	02/11/2021
		Order Number:	701058	686680	674258	668835	647030
		Oil Temp:	40		38	30	20
Comment:							
General Oil Qualit	y (GOQ)						
ASTM D-15331	Moisture in Oil	(mg/kg):	3	5	4	2	3
ASTM D-9711	Interfacial Tension	(mN/m):	37.62	38.02	38.19	38.27	38.75
ASTM D-9741	Acid Number	(mg KOH/g):	0.016	0.008	0.014	0.010	0.010
ASTM D-1500¹	Color Number	(ASTM):	L1.5	L1.5	L1.0	L1.0	1.5
ASTM D-15241	Visual Exam.	(Relative):	PASS	PASS	PASS	PASS	PASS
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT
ASTM D-15241	Sediment Exam.	(Relative):	ND	ND	ND	ND	ND
ASTM D-18161	Dielectric Breakdown 2 m	nm (kV °C):	47 (23 C)	50 (23 C)	68 (22 C)	44 (23°C)	64 (23°C)
ASTM D-40521	Density @15°C	(g/mL):	0.859	0.8586	0.8597	0.8589	0.8594
GOQ Diagnostics		Moisture in Oil:	Acceptable for in-se	ervice oil (35 mg/kg	max).		
PER IEEE C57.106	6-2015 Inte	erfacial Tension:	Acceptable for in-se	ervice oil (25 mN/m	min).		
(most recent sampl	e)	Acid Number:	Acceptable for in-se	ervice oil (0.2 mg K0	DH/g max).		
	Color Nu	mber and Visual:	Diagnostic not appli	icable. Diagnostic n	ot applicable.		
	Dielectric Breakdow	n ASTM D-1816:	Acceptable for in-se	ervice oil (40 kV min	@ 2mm).		
Comment:							

End of Test Report

F.Karolt

JANET KAROLAT SUPV CHEMIST

Authorized By:

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AVO DIAGNOSTIC SERVICES		919 FRA	AVO I SER DR. U 905-6 WWW	Diagnos Init 13 + E 32-8697 + .Avodiag	TIC SERVICES BURLINGTON, ON + L7 • 905-632-8698 ©NOSTICS.COM	7L 4X8	T 01-76477	EST REPORT 88-701058-00 Page 1 of 2
ERTH (Holdings) Inc		Serial#:	026500100	01	Mf	r: FERRANTI	Control#:	7647788
		Location:	INGERSO	LL	k'	/: 27.6	Order#:	701058
		Equipment:	TRANSFO	RMER	kVA	A: 5000	Account:	110229
INGERSOLL, . N5C2N9 CA	Ą	Compartment:	MAIN(BOT	TOM)	Year Mf	d: 1985	Received:	06/06/2023
ATTN: MARC GALECKAS		Breathing:	SEAL	,	Syringe II) : 8005730	Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle II	D:		
Project ID: H-23-001		Fluid: MIN	Liters: 343	37	Sampled B	y: CC		
Customer ID: MS1								
		Lab Control Numbe	r:	7647788	7590318	7535753	7515374	7425760
		Date Sampled	i: 05	5/16/2023	09/28/2022	04/07/2022	11/30/2021	02/11/2021
		Order Numbe	r:	701058	686680	674258	668835	647030
Dissolved Gas Analysis (Oli Temp O2/N2 Patic): 	0.01	0.01	0.01	0.01	0.01
ASTM	DGA)	Transformer Age (vrs).).	38	37	37	36	36
D-3612 ¹		Hydrogen (H2) (uL/L):	85	78	79	76	78
		Methane (CH4) (µL/L):	40	42	40	41	45
		Ethane (C2H6) (µL/L):	12	12	12	12	12
		Ethylene (C2H4) (µL/L):	18	18	18	19	20
		Acetylene (C2H2) (µL/L):	<1	<1	<1	<1	<1
	Carb	on Monoxide (CO) (µL/L):	1137	1184	1162	1179	1274
	Car	bon Dioxide (CO2) (μL/L):	4696	5106	4617	8014	4706
		Nitrogen (N2) (µL/L):	71651	70984	75612	78398	79655
		Oxygen (O2) (µL/L):	620	670	1101	856	893
		Dissolved Gas	Analysis D	iagnostics	s – IEEE Std C57.104-2	2019		
	Absolu	ite Gas Levels (μL/L)		Gas Leve	el Deltas(µL/L)	Gas C	Generation Rates (μL	/L per yr)
			-	(2 most re	ecent samples)	(3-6 most	t recent samples with	in 4-24 mos.)
Gas	Level	Diagnostic	Delta		Diagnostic	Rate	Diagnost	ic
Hydrogen (H2)	85	Normal (<= 100)	7	Normal V	ariation (<= 40)	6	No active gassing (<=	20)
Methane (CH4)	40	Normal (<= 110)	-2			0	No active gassing (<=	10)
Ethane (C2H6)	12	Normal (<= 150)	0	Normal V	ariation (<= 25)	0	No active gassing (<=	9)
Ethylene (C2H4)	18	Normal (<= 90)	0	Normal V	ariation (<= 20)	-1	No active gassing (<=	7)
Acetylene (C2H2)	<1	Normal (<= 1)	0	Normal V	ariation (<= 0)	0	No active gassing (<=	0)
Carbon Monoxide (CO)	1137	High (> 1100)	-47			-23	No active gassing (<=	100)
Carbon Dioxide (CO2)	4696	Normal (<= 10000)	-410			-1751	No active gassing (<=	1000)
DGA Diagnostics	Roger's Ratio	Diagnostic not applicable	- Gas level	s normal.				
Duval	Triangles	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable	– Triangle – Triangle – Triangle	1 gas leve 4 gas leve 5 gas leve	ls normal. ls normal. ls normal.			
Duval F	entagons	Diagnostic not applicable	- Gas level	s normal.				
Cellulose	insulation	<u>CO2/CO ratio =</u> 4 (3< rati	<u>o <= 20)</u> - N	<u>No indi</u> catio	on of a fault involving pa	aper		
D	GA Status	Status 3 - High gas levels transformer assessment.	and/or pro	bable activ	ve gassing. Probably su ion based on transform	spicious - perfo er assessment	orm fault identification a	and policy.
Resampling	g Protocol	Surveillance						
AVO Re Recomr	esampling nendation	Increase frequency to ver	ify gassing	rates. Co	nsider online monitorino	g and comprehe	ensive engineering ass	essment.

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , μg/m, μL/L = ppm, μg/L = ppb, mN/m = dynes/cm, mm²/s = cSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Avoid the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Assumes no responsibility and makes no warrantly or representation, expressed to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

DIAGNOSTIC SERV) IICES	919 FRAS	AVO DIAGNOST ER DR. UNIT 13 + B 905-632-8697 + WWW.AVODIAG	TIC SERVICES URLINGTON, ON + 905-632-8698 NOSTICS.COM	- L7L 4X8	T 01-76477	EST REPORT 788-701058-00 Page 2 of 2
ERTH (Holdings) Inc	2	Serial#: 0	265001001		Mfr: FERRANTI PACKARD	Control#:	7647788
		Location:	NGERSOLL		kV: 27.6	Order#:	701058
		Equipment: 7	RANSFORMER	1	VA: 5000	Account	110229
INGERSOLL, . N5C	2N9 CA	Compartment: N	AIN(BOTTOM)	Year I	Mf'd: 1985	Received:	06/06/2023
ATTN: MARC GALE	ECKAS	Breathing: S	SEAL	Syring	e ID: 8005730	Reported:	06/28/2023
PO#: POH007255		Bank: F	hase: 3	Bottle	e ID:		
Project ID: H-23-00	1	Fluid: MIN L	.iters: 3437	Sampled	By: CC		
Customer ID: MS1				-	-		
	Lab	Control Number:	7647788	7590318	7535753	7515374	7425760
		Date Sampled:	05/16/2023	09/28/2022	04/07/2022	11/30/2021	02/11/2021
		Order Number:	701058	686680	674258	668835	647030
		Oil Temp:	42	35	32	30	20
Comment:							
General Oil Quality	(GOQ)						
ASTM D-15331	Moisture in Oil	(mg/kg):	5	9	5	13	3
ASTM D-9711	Interfacial Tension	(mN/m):	41.86	41.67	40.78	41.47	41.81
ASTM D-9741	Acid Number	(mg KOH/g):	0.011	0.003	0.008	0.005	0.005
ASTM D-15001	Color Number	(ASTM):	L1.0	L1.0	L1.0	L1.0	L1.0
ASTM D-15241	Visual Exam.	(Relative):	PASS	PASS	PASS	PASS	PASS
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT
ASTM D-15241	Sediment Exam.	(Relative):	ND	ND	ND	ND	ND
ASTM D-18161	Dielectric Breakdown 2 m	nm (kV °C):	27 (23 C)	60 (23 C)	71 (22 C)	67 (23°C)	59 (23°C)
ASTM D-40521	Density @15°C	(g/mL):	0.8628	0.8623	0.8632	0.8626	0.8639
GOQ Diagnostics		Moisture in Oil:	Acceptable for in-se	ervice oil (35 mg/kg	max).		
PER IEEE C57.106-	2015 Inte	erfacial Tension:	Acceptable for in-se	ervice oil (25 mN/m i	min).		
(most recent sample	e)	Acid Number:	Acceptable for in-se	ervice oil (0.2 mg KC)H/g max).		
	Color Nur	nber and Visual:	Diagnostic not appli	cable. Diagnostic n	ot applicable.		
	Dielectric Breakdow	n ASTM D-1816:	Below limit for in-se	rvice oil (40 kV min	@ 2mm).		

Comment:

End of Test Report

F.Karoly

Authorized By:

JANET KAROLAT SUPV CHEMIST

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.



AVO DIAGNOSTIC SERVICES

919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698 WWW.AVODIAGNOSTICS.COM

Serial#: A3S6029

Control#: 7647786

Mfr: WESTINGHOUSE

Page 1 of 2

		Location: Equipment:	GODERIC TRANSFC	H MS 3 RMER	k) kV/	/: 27.6 A: 5000	Order#: Account:	701058 110229
INGERSOLL, . N5C2N9 CA	4	Compartment:	MAIN(BOT	ГТОМ)	Year Mf	1: 1968	Received:	06/06/2023
ATTN: MARC GALECKAS		Breathing:	CONS		Syringe I): 8006754	Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle II	Bottle ID:		
Project ID: H-23-001		Fluid: MIN	USGal: 85	50	Sampled B	/: CC		
Customer ID: T1								- (00
		Lab Control Number	r:	7647786	7590313	7535759	7505532	7425752
		Date Sampled	1: Ut	701059	09/20/2022	04/06/2022	10/21/2021	02/10/2021
		Order Number Oil Temr	r:	701058	080080	074258 30	000239 35	647030
Dissolved Gas Analysis (O2/N2 Ratio).)'	0.45	0.46	0.48	0.45	0.45
ASTM	DON,	Transformer Age (vrs)):	55	54	54	53	53
D-3612 ¹		Hvdrogen (H2) (uL/L)):	4	5	4	7	4
		Methane (CH4) (µL/L)):	2	2	2	2	2
		Ethane (C2H6) (µL/L)):	<1	<1	<1	<1	<1
		Ethylene (C2H4) (µL/L)):	10	11	9	11	11
		Acetylene (C2H2) (µL/L)):	<1	<1	<1	<1	<1
	Carb	on Monoxide (CO) (µL/L)):	108	134	111	155	142
	Car	bon Dioxide (CO2) (µL/L)):	1232	1306	1260	1391	1372
		Nitrogen (N2) (µL/L)):	58056	55719	58892	64216	68745
		Oxygen (O2) (µL/L)):	26356	25430	28038	29012	30903
		Dissolved Gas A	Analysis D	iagnostics	s – IEEE Std C57.104-2	2019		
	Absolu	ıte Gas Levels (μL/L)		Gas Leve (2 most re	el Deltas(µL/L) ecent samples)	Gas C (3-6 most	Generation Rates (μL t recent samples with	/L per yr) in 4-24 mos.)
Gas	Level	Diagnostic	Delta		Diagnostic	Rate	Diagnost	ic
Hydrogen (H2)	4	Normal (<= 40)	-1			-2	No active gassing (<=	10)
Methane (CH4)	2	Normal (<= 20)	0	Normal Va	ariation (<= 10)	0	No active gassing (<=	3)
Ethane (C2H6)	0	Normal (<= 15)	0	Normal Va	ariation (<= 7)	0	No active gassing (<=	2)
Ethylene (C2H4)	10	Normal (<= 60)	-1			0	No active gassing (<=	5)
Acetylene (C2H2)	<1	Normal (<= 2)	0	Normal Va	ariation (<= 0)	0	No active gassing (<=	0)
Carbon Monoxide (CO)	108	Normal (<= 500)	-26			-23	No active gassing (<=	80)
Carbon Dioxide (CO2)	1232	Normal (<= 5500)	-74			-83	No active gassing (<=	800)
DGA Diagnostics	Roger's Ratio	Diagnostic not applicable	- Gas leve	ls normal.				
Duval	Triangles	Diagnostic not applicable	– Triangle	1 das leve	ls normal			
Buru	mangioo	Diagnostic not applicable	- Triangle	4 das leve	ls normal.			
		Diagnostic not applicable	- Triangle	5 das leve	ls normal.			
Duval F	Pentagons	Diagnostic not applicable	- Gas leve	ls normal				
Cellulose	insulation	CO and CO2 levels are n	ormal No i	ndication o	of a fault involving pape			
D	GA Status	Status 1 - Normal gas lev	els and no	Indication	of gassing. Continue ro	utine DGA and	normal transformer op	eration.
Resampling	g Protocol	Routine Screening						
AVO Re	esampling	Resample within 1 year.						
Recomm	nendation							
Comment:								
General Oil Quality (GOQ)							
Notations: 1. Analysis is ISO/IEC 17025:20 test is conducted by AVO Diagnostic Servit for these results; accreditation status does Accreditation applies to current analysis on by this laboratory are the same as all such	17 accredited, AN ces Laboratory oth not apply to these ly. The analyses, material in the en	IAB Accredited Certificate Number L2303 her than Primary Lab. 6. AVO Diagnostic e results. 8. Imported Equipment 10. mg/k opinions or interpretations contained in th vironment from which the sample was take	2. This test is co Services Laborato g, μg/g, μg/mL, μ is report are base	nducted by a sub ory has received uL/L = ppm, µg/L d upon material a is relate only to th	contracted laboratory. 3. Subcontract ISO Standard 17025 accreditation fo _ = ppb, mN/m = dynes/cm, mm²/s = and information supplied by the client e sample or samples tested Anv int	ed laboratory has recei this test. 7. Imported S St AVO Diagnostic Servic erroretations or opinions	ived ISO Standard 17025 accreditati Sample: AVO Diagnostic Services ac ces does not imply that the contents expressed represent the best judgm	on for this test. 5. This cepts no responsibility of the sample received
Services. AVO Diagnostic Services assume upon for any reason whatsoever. This test	es no responsibilit report shall not b	y and makes no warranty or representation e reproduced except in full, without writter	n, expressed or in approval of the l	mplied as to the caboratory.	condition, productivity or proper opera	tion of any equipment of	or other property for which this repor	may be used or relied

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698

TEST REPORT 01-7647786-701058-00

Page 2 of 2

DIAGNOSTIC SE	ERVICES	WWW.AVODIAGNOSTICS.COM					
ERTH (Holdings) I	Inc	Serial#:	A3S6029		Mfr: WESTINGHOUS	E Control#:	7647786
		Location:	GODERICH MS 3		kV: 27.6	Order#:	701058
		Equipment:	TRANSFORMER		kVA: 5000	Account:	110229
INGERSOLL, . N5	C2N9 CA	Compartment:	MAIN(BOTTOM)	Year	Mf'd: 1968	Received:	06/06/2023
ATTN: MARC GA	LECKAS	Breathing:	CONS	Syring	je ID: 8006754	Reported:	06/28/2023
PO#: POH007255	i	Bank:	Phase: 3	Bott	le ID:		
Project ID: H-23-0	001	Fluid: MIN	USGal: 850	Sample	d By: CC		
Customer ID: T1							
	Lab C	Control Number	r: 7647786	7590313	7535759	7505532	7425752
		Date Sampled	l: 05/17/2023	09/20/2022	04/06/2022	10/21/2021	02/10/2021
		Order Number	r: 701058	686680	674258	666239	647030
		Oil Temp	25	40	30	35	18
ASTM D-15331	Moisture in Oil	(mg/kg)): 7	13	7	13	4
ASTM D-9711	Interfacial Tension	(mN/m)	36.94	36.28	36.9	37.16	37.16
ASTM D-9741	Acid Number	(mg KOH/g	0.014	0.017	0.019	0.016	0.010
ASTM D-15001	Color Number	(ASTM)): L1.5	L1.5	L1.5	L1.5	L2.0
ASTM D-15241	Visual Exam.	(Relative)): PASS	PASS	PASS	PASS	PASS
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT C	LR&BRIGHT	CLR&BRIGHT
ASTM D-15241	Sediment Exam.	(Relative)): ND	ND	ND	ND	ND
ASTM D-18161	Dielectric Breakdown 2 m	m (kV °C)): 26 (23 C)	39 (23 C)	67 (22 C)	43 (23°C)	73 (23°C)
ASTM D-40521	Density @15°C	(g/mL)): 0.8604	0.8593	0.8608	0.8607	0.8568
GOQ Diagnostics	6	Moisture in Oi	I: Acceptable for in-se	ervice oil (35 mg/kg	max).		
PER IEEE C57.10	6-2015 Inte	erfacial Tensior	I: Acceptable for in-se	ervice oil (25 mN/m	min).		
(most recent samp	ole)	Acid Number	r: Acceptable for in-se	ervice oil (0.2 mg K	OH/g max).		
	Color Nun	nber and Visua	I: Diagnostic not appl	icable. Diagnostic r	not applicable.		
	Dielectric Breakdow	n ASTM D-1816	Below limit for in-se	ervice oil (40 kV mir	ı @ 2mm).		
Comment:							

End of Test Report

F.Karold

Authorized By:

JANET KAROLAT SUPV CHEMIST

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8

TEST REPORT 01-7647790-701058-00

DIAGNOSTIC SERVICES			905-6 WWW	32-8697 + 905 AVODIAGNOS	5-632-8698 STICS.COM			Page 1 of 2
ERTH (Holdings) Inc		Serial#:	G135721		Mfr:	PIONEER ELECTRIC	Control#:	7647790
		Location:	TAVISTOC	СК	kV:	27.6	Order#:	701058
		Equipment:	TRANSFO	RMER	kVA:	5000	Account:	110229
INGERSOLL, . N5C2N9 C	4	Compartment:	MAIN(BOT	TOM)	Year Mf'd: 2005		Received:	06/06/2023
ATTN: MARC GALECKAS	5	Breathing:	FB	,	Syringe ID: 8004950		Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle ID:			
Project ID: H-23-001		Fluid: MIN	Liters: 372	20	Sampled By:	CC		
Customer ID:								
		Lab Control Number	r:	7647790	7590317	7535749	7505535	7425757
		Date Sampled	I: 05	5/16/2023	09/20/2022	04/05/2022	10/03/2021	02/10/2021
		Order Number	r:	701058	686680	674258	666239	647030
		Oil Temp):	30	35	20	35	6
Dissolved Gas Analysis (DGA)	O2/N2 Ratio	:	0.24	0.25	2.47	0.26	0.26
ASTM		Transformer Age (yrs)):	18	17	17	16	16
D-3612 ¹		Hydrogen (H2) (µL/L)):	48	43	40	51	47
		Methane (CH4) (µL/L)):	8	8	7	8	9
		Ethane (C2H6) (µL/L)):	6	6	6	6	6
		Ethylene (C2H4) (µL/L)):	3	3	3	3	3
		Acetylene (C2H2) (µL/L)):	<1	<1	<1	<1	<1
	Carb	on Monoxide (CO) (µL/L)):	416	377	333	423	379
	Car	bon Dioxide (CO2) (µL/L)):	2858	2841	2514	2971	2588
		Nitrogen (N2) (µL/L)):	64043	58905	5508	68749	64918
		Oxygen (O2) (µL/L)):	15078	14693	13578	17598	16559
		Dissolved Gas A	Analysis D	iagnostics – IF	EEE Std C57 104-20	19		
				lagnootioo ii				
	Absolu	ite Gas Levels (μL/L)		Gas Level De (2 most recen	eltas(μL/L) nt samples)	Gas ((3-6 most	Generation Rates(µL/ t recent samples withi	/L per yr) in 4-24 mos.)
Gas	Absolu Level	ite Gas Levels (μL/L) Diagnostic	Delta	Gas Level De (2 most recen	eltas(μL/L) ht samples) iagnostic	Gas ((3-6 most	Generation Rates (µL t recent samples withi Diagnost	/L per yr) in 4-24 mos.) ic
Gas Hydrogen (H2)	Absolu Level 48	te Gas Levels (μL/L) Diagnostic Elevated (> 40)	Delta 5	Gas Level De (2 most recen D Normal Variati	eltas(μL/L) nt samples) niagnostic	Gas ((3-6 most Rate -1	Generation Rates (µL) t recent samples withi Diagnost No active gassing (<=	/L per yr) in 4-24 mos.) ic 10)
Gas Hydrogen (H2) Methane (CH4)	Absolu Level 48 8	te Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20)	Delta 5	Gas Level De (2 most recen D Normal Variati	eltas(μL/L) nt samples) hiagnostic hion (<= 25) hion (<= 10)	Gas ((3-6 most Rate -1	Generation Rates (µL/ t recent samples withi Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6)	Absolu Level 48 8 6	te Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15)	Delta 5 0	Gas Level De (2 most recen D Normal Variati Normal Variati	eltas(μL/L) it samples) iagnostic ion (<= 25) ion (<= 10) ion (<= 7)	Gas ((3-6 most Rate -1 0	Generation Rates (µL/ t recent samples withi Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4)	Absolu Level 48 6 3	te Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60)	Delta 5 0 0	Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati	eltas(μL/L) it samples) iagnostic ion (<= 25) ion (<= 10) ion (<= 7) ion (<= 20)	Gas ((3-6 most Rate -1 0 0	Generation Rates (µL) t recent samples within Diagnost No active gassing (<= No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2)	Absolu Level 48 8 6 3 <1	tte Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 2)	Delta 5 0 0 0 0	Gas Level De (2 most recen Normal Variati Normal Variati Normal Variati Normal Variati	eltas(μL/L) it samples) iagnostic ion (<= 25) ion (<= 10) ion (<= 7) ion (<= 20) ion (<= 0)	Gas ((3-6 most Rate -1 0 0 0	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO)	Absolu Level 48 8 6 3 <1 416	te Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 2) Normal (<= 500)	Delta 5 0 0 0 0 39	Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati	eltas(μL/L) it samples) iagnostic ion (<= 25) ion (<= 10) ion (<= 7) ion (<= 20) ion (<= 0) ion (<= 175)	Gas ((3-6 most Rate -1 0 0 0 0 0	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2)	Absolu Level 48 6 3 <1 416 2858	tte Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 2) Normal (<= 500) Normal (<= 5500)	Delta 5 0 0 0 0 0 39 17	Gas Level De (2 most recen Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati	Pltas(μL/L) it samples) iagnostic ion (<= 25) ion (<= 10) ion (<= 7) ion (<= 20) ion (<= 0) ion (<= 175) ion (<= 1750)	Gas ((3-6 most Rate -1 0 0 0 0 0 0	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics	Absolu Level 48 8 6 3 41 416 2858 Roger's Ratio	tte Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 2) Normal (<= 500) Normal (<= 5500) Unit normal.	Delta 5 0 0 0 0 0 39 17	Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati	Pltas(μL/L) nt samples) iagnostic iion (<= 25) iion (<= 10) iion (<= 7) iion (<= 20) iion (<= 0) iion (<= 175) iion (<= 1750)	Gas ((3-6 most Rate -1 0 0 0 0 0 0 1	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 5) 0) 80) 800)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval	Absolu Level 48 8 6 3 3 <1 416 2858 Roger's Ratio	tte Gas Levels (µL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 500) Normal (<= 5500) Unit normal. Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable	Delta 5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati	Plas(μL/L) it samples) iagnostic ion (<= 25)	Gas ((3-6 most Rate -1 0 0 0 0 0 0	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval	Absolu Level 48 8 6 3 3 <1 416 2858 Roger's Ratio Triangles	tte Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 2) Normal (<= 5500) Unit normal. Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Pentagon 1: Stray Gassin Pentagon 2: Stray Gassin	Delta 5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Gas Level De (2 most recen Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Sormal Variati	Plas(μL/L) it samples) iagnostic ion (<= 25)	Gas ((3-6 most Rate -1 0 0 0 0 0	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval Duval Cuval	Absolu Level 48 8 6 3 <1 416 2858 Roger's Ratio Triangles Pentagons insulation	te Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 500) Normal (<= 5500) Unit normal. Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Pentagon 1: Stray Gassin Pentagon 2: Stray Gassin CO and CO2 levels are n	Delta 5 0 17 - <th>Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Sormal Variati</th> <th>Plas(µL/L) isamples) iagnostic ion (<= 25) ion (<= 10) ion (<= 7) ion (<= 20) ion (<= 0) ion (<= 175) ion (<= 1750)</th> <th>Gas ((3-6 most Rate -1 0 0 0 0 0 0</th> <th>Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=</th> <th>/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800)</th>	Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Sormal Variati	Plas(µL/L) isamples) iagnostic ion (<= 25) ion (<= 10) ion (<= 7) ion (<= 20) ion (<= 0) ion (<= 175) ion (<= 1750)	Gas ((3-6 most Rate -1 0 0 0 0 0 0	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval Duval F Cellulose	Absolu Level 48 8 6 3 <1 416 2858 Roger's Ratio Triangles Pentagons insulation GA Status	te Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 500) Normal (<= 5500) Unit normal. Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Pentagon 1: Stray Gassin Pentagon 2: Stray Gassin CO and CO2 levels are no Status 2 - Elevated gas le surveillance and DGA free	Delta 5 0 - Triangle - <t< th=""><th>Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Sormal Variati Normal Variati Normal Variati Sormal Variati Normal Variati Normal Variati</th><th>Plas(μL/L) is samples) iagnostic ion (<= 25) ion (<= 10) ion (<= 20) ion (<= 0) ion (<= 175) ion (<= 1750)</th><th>Gas ((3-6 most Rate -1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</th><th>Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=</th><th>/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800) 800) 800)</th></t<>	Gas Level De (2 most recen D Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Sormal Variati Normal Variati Normal Variati Sormal Variati Normal Variati Normal Variati	Plas(μL/L) is samples) iagnostic ion (<= 25) ion (<= 10) ion (<= 20) ion (<= 0) ion (<= 175) ion (<= 1750)	Gas ((3-6 most Rate -1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Generation Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800) 800) 800)
Gas Hydrogen (H2) Methane (CH4) Ethane (C2H6) Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval Duval Cellulose D	Absolu Level 48 8 6 3 <1 416 2858 Roger's Ratio Triangles Pentagons insulation GA Status g Protocol	te Gas Levels (μL/L) Diagnostic Elevated (> 40) Normal (<= 20) Normal (<= 15) Normal (<= 60) Normal (<= 2) Normal (<= 5500) Normal (<= 5500) Unit normal. Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Pentagon 1: Stray Gassin Pentagon 2: Stray Gassin CO and CO2 levels are no Status 2 - Elevated gas les surveillance	Delta 5 0 0 0 0 0 0 0 39 17 - Triangle - Triangle - Triangle g (t < 200°C ormal. No in evels and/or guency.	Gas Level De (2 most recen Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Normal Variati Sas levels no 5 gas levels no	Plas(µL/L) isamples) iagnostic ion (<= 25) ion (<= 10) ion (<= 20) ion (<= 0) ion (<= 175) ion (<= 1750)	Gas ((3-6 most -1 -1 0 0 0 0 0 0 0 0 0 0	Seneration Rates (µL/ t recent samples within Diagnost No active gassing (<= No active gassing (<=	/L per yr) in 4-24 mos.) ic 10) 3) 2) 5) 0) 80) 800) 800)

Notations: 1. Analysis is ISO/IEC 17025/2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

ERTH (Holdings) Inc Serial#: G13572 Location: TAVIST Equipment: TRANS INGERSOLL, . N5C2N9 CA Compartment: MAIN(B ATTN: MARC GALECKAS Breathing: FB PO#: POH007255 Bank: Phase: Project ID: H-23-001 Fluid: MIN Liters: Customer ID: Lab Control Number: Date Sampled:	21 TOCK FORMER SOTTOM)	l Voor l	Mfr: PIONEER ELECTRIC kV: 27.6	Control	#: 7647790	
Location: TAVIST Equipment: TRANS INGERSOLL, . N5C2N9 CA ATTN: MARC GALECKAS PO#: POH007255 Bank: Phase: Project ID: H-23-001 Fluid: MIN Liters: Customer ID: Lab Control Number: Date Sampled:	OCK FORMER SOTTOM)	l Voar l	kV: 27.6			
Equipment: TRANS INGERSOLL, . N5C2N9 CA Compartment: MAIN(B ATTN: MARC GALECKAS Breathing: FB PO#: POH007255 Bank: Phase: Project ID: H-23-001 Fluid: MIN Liters: Customer ID: Lab Control Number: Date Sampled: Date Sampled:	FORMER OTTOM)	l Voar I		Order	#: 701058	
INGERSOLL, . N5C2N9 CA ATTN: MARC GALECKAS PO#: POH007255 Project ID: H-23-001 Customer ID: Lab Control Number: Date Sampled:	OTTOM)	Voarl	KVA: 5000	Accour	it: 110229	
ATTN: MARC GALECKAS Breathing: FB PO#: POH007255 Bank: Phase: Project ID: H-23-001 Fluid: MIN Liters: Customer ID: Lab Control Number: Date Sampled:		Ieali	Mf'd: 2005	Receive	d: 06/06/2023	
PO#: POH007255 Bank: Phase: Project ID: H-23-001 Fluid: MIN Liters: Customer ID: Lab Control Number: Date Sampled:		Syring	e ID: 8004950	Reporte	d: 06/28/2023	
Project ID: H-23-001 Fluid: MIN Liters: Customer ID: Lab Control Number: Date Sampled:	3	Bottl	e ID:			
Customer ID: Lab Control Number: Date Sampled:	3720	Sampled	By: CC			
Lab Control Number: Date Sampled:		-	-			
Date Sampled:	7647790	7590317	7535749	7505535	7425757	
	05/16/2023	09/20/2022	04/05/2022	10/03/2021	02/10/2021	
Order Number:	701058	686680	674258	666239	647030	
Oil Temp:	30	35	20	35	6	
Recommendation						
Comment:						
General Oil Quality (GOQ)						
ASTM D-1533 ¹ Moisture in Oil (mg/kg):	4	8	2	7	2	
ASTM D-971 ¹ Interfacial Tension (mN/m):	31.93	31.3	32.4	31.83	31.46	
ASTM D-974 ¹ Acid Number (mg KOH/g):	0.014	0.008	0.008	0.013	0.010	
ASTM D-1500 ¹ Color Number (ASTM):	L0.5	L0.5	L0.5	L0.5	L0.5	
ASTM D-1524 ¹ Visual Exam. (Relative):	PASS	FAIL	PASS	PASS	PASS	
CL	R&BRIGHT	H2O	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	
ASTM D-1524 ¹ Sediment Exam. (Relative):	TRACE	ND	ND	ND	ND	
ASTM D-1816 ¹ Dielectric Breakdown 2 mm (kV °C):	52 (23 C)	50 (23 C)	62 (22 C)	48 (23°C)	58 (23°C)	
ASTM D-4052 ¹ Density @15°C (g/mL):	0.8865	0.886	0.887	0.8872	0.8851	
GOQ Diagnostics Moisture in Oil: Accept	otable for in-se	rvice oil (35 mg/kg	max).			
PER IEEE C57.106-2015 Interfacial Tension: Accept	otable for in-se	rvice oil (25 mN/m i	min).			
(most recent sample) Acid Number: Accep	otable for in-se	rvice oil (0.2 mg KC)H/g max).			
Color Number and Visual: Diagn	ostic not appli	I: Diagnostic not applicable. Diagnostic not applicable				
Dielectric Breakdown ASTM D-1816: Accept	· ·	cable. Diagnostic n	ot applicable.			

Comment:

End of Test Report

F.Kankt

Authorized By:

JANET KAROLAT SUPV CHEMIST

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.



AVO DIAGNOSTIC SERVICES

919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698 WWW.AVODIAGNOSTICS.COM

Page 1 of 2

ERTH (Holdings) Inc		Serial#:	A3S6467		Mfr:	WESTINGH	OUSE Control#:	7647795
		Location:	GODERIC	H MS 4	kV:	27.6	Order#:	701058
		Equipment:	TRANSFC	RMER	kVA:	5000	Account:	110229
INGERSOLL, . N5C2N9 CA	A Contraction of the second se	Compartment:	MAIN(BOT	TOM)	Year Mf'd:	1979	Received:	06/06/2023
ATTN: MARC GALECKAS		Breathing:	FB		Syringe ID:	8001933	Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle ID:			
Project ID: H-23-001		Fluid: MIN	IMPGal: 7	10	Sampled By:	CC		
Customer ID: T1								
		Lab Control Number	r:	7647795	7590308	7535748	7505534	7425755
		Date Sampled	1: 05	704050	09/20/2022	04/06/2022	10/21/2021	02/10/2021
		Order Number		701058	686680	674258	666239	647030
Dissolved Cas Analysis (Oil Temp		40	0.02	45	52	40
DISSOIVED Gas Analysis (DGA)			0.01	0.03	0.02	0.02	0.01
ASTWI D 26121		Hudrogon (H2) (ul /l.)		44	43	43	42	42
D-3012		Mothene (CH4) (µL/L)		30	21	22	22	17
		Ethano (C2H6) (µL/L)		34 8	7	52	50	30
		Ethylene (C2H4) (µL/L)		8	7	6	5	6
		Acetylene (C2H2) (μ L/L)		<1	<1	<1	<1	<1
	Carb	n Monoxide (CO) (uL/L): 549		482	526	630	631	
	Car	bon Dioxide (CO2) (µL/L)	μμιμίας μεγείας μεγάλαστας		22223	22533	24390	23843
	- Cui	Nitrogen (N2) (µL/L)		73947	62005	69062	78983	78444
		Oxvgen (O2) (µL/L)	:	986	1584	1067	1192	780
		Dissolved Gas A	Analysis D	iagnostics -	IEEE Std C57.104-20	19		
	Absolu	ite Gas Levels (μL/L)		Gas Level D	Deltas(μL/L)	Gas G	eneration Rates (μL	/L per yr)
				(2 most rece	ent samples)	(3-6 most	recent samples with	n 4-24 mos.)
Gas	Level	Diagnostic	Delta		Diagnostic	Rate	Diagnost	ic
Hydrogen (H2)	30	Normal (<= 100)	13	Normal Vari	ation (<= 40)	5	No active gassing (<=	20)
Methane (CH4)	34	Normal (<= 110)	3	Normal Vari	ation (<= 30)	-1	No active gassing (<=	10)
Ethane (C2H6)	8	Normal (<= 150)	1	Normal Vari	ation (<= 25)	1	No active gassing (<=	9)
Ethylene (C2H4)	8	Normal (<= 90)	1	Normal Vari	ation (<= 20)	2	No active gassing (<=	7)
Acetylene (C2H2)	<1	Normal (<= 1)	0	Normal Vari	ation (<= 0)	0	No active gassing (<=	0)
Carbon Monoxide (CO)	549	Normal (<= 900)	67	Normal Vari	ation (<= 250)	-48	No active gassing (<=	100)
Carbon Dioxide (CO2)	23237	High (> 14000)	1014	Normal Vari	ation (<= 2500)	-620	No active gassing (<=	1000)
DGA Diagnostics	Roger's	Diagnostic not applicable	- Gas level	s normal.				
	Ratio							
Duval	Triangles							
	manyles	Diagnostic not applicable	– Triangle	1 gas levels	normal.			
	mangles	Diagnostic not applicable Diagnostic not applicable	 Triangle Triangle 	1 gas levels 4 gas levels	normal. normal.			
	Inaligies	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable	– Triangle – Triangle – Triangle	1 gas levels 4 gas levels 5 gas levels	normal. normal. normal.			
Duval F	Pentagons	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable	– Triangle – Triangle – Triangle <u>- Gas leve</u> l	1 gas levels 4 gas levels 5 gas levels s normal.	normal. normal. normal.			
Duval F Cellulose	Pentagons	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20)	– Triangle – Triangle <u>– Triangle - Gas level</u> -Indication	1 gas levels 4 gas levels 5 gas levels s normal. of slow degra	normal. normal. normal. adation of the paper due	e to low temp	erature (< 140 °C). Ve	erify insulation
Duval F Cellulose	Pentagons	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth	 Triangle Triangle Triangle Gas level Indication nanol tests. 	1 gas levels 4 gas levels 5 gas levels ls normal. of slow degra	normal. normal. normal. adation of the paper due	e to low temp	erature (< 140 °C). Ve	orify insulation
Duval F Cellulose	Pentagons insulation GA Status	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels	 Triangle Triangle Triangle Gas level Indication nanol tests and/or pro 	1 gas levels 4 gas levels 5 gas levels s normal. of slow degra	normal. normal. normal. adation of the paper due gassing. Probably susp	e to low temp icious - perfo	erature (< 140 °C). Ve prm fault identification a	erify insulation
Duval F Cellulose D ⁱ	Pentagons insulation GA Status	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment.	 Triangle Triangle Triangle Gas level Indication nanol tests and/or pro Take appr 	1 gas levels 4 gas levels 5 gas levels ls normal. of slow degra bable active opriate action	normal. normal. adation of the paper due gassing. Probably susp n based on transformer	e to low temp icious - perfc assessment	erature (< 140 °C). Ve orm fault identification a results and company p	erify insulation and policy.
Duval F Cellulose Du Resampling	Pentagons insulation GA Status g Protocol	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment. Surveillance	 Triangle Triangle Triangle Gas level Indication nanol tests and/or pro Take appr 	1 gas levels 4 gas levels 5 gas levels ls normal. of slow degra bable active opriate action	normal. normal. adation of the paper due gassing. Probably susp n based on transformer	e to low temp icious - perfc assessment	erature (< 140 °C). Ve orm fault identification a results and company p	erify insulation and policy.
Duval F Cellulose Duval F Resampling	Pentagons insulation GA Status g Protocol	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment. Surveillance	 Triangle Triangle Triangle Gas level Indication nanol tests. and/or pro Take appr 	1 gas levels 4 gas levels 5 gas levels Is normal. of slow degra bable active opriate action	normal. normal. normal. adation of the paper due gassing. Probably susp n based on transformer	e to low temp icious - perfo assessment	erature (< 140 °C). Ve orm fault identification a results and company p	erify insulation and policy.
Duval F Cellulose Duval F Resampling AVO Re Recomp	Pentagons insulation GA Status g Protocol esampling nendation	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment. Surveillance Increase frequency to ver	 Triangle Triangle Triangle Gas level Indication nanol tests and/or pro Take appr ify gassing 	1 gas levels 4 gas levels 5 gas levels ls normal. of slow degra obable active opriate action rates. Consi	normal. normal. normal. adation of the paper due gassing. Probably susp n based on transformer ider online monitoring a	e to low temp icious - perfo assessment nd comprehe	erature (< 140 °C). Ve orm fault identification a results and company p ensive engineering ass	erify insulation and policy. essment.
Duval F Cellulose Duval F Resampling AVO Re Recomm	Pentagons insulation GA Status g Protocol esampling nendation	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment. Surveillance Increase frequency to ver	 Triangle Triangle Triangle Gas level Indication nanol tests and/or pro Take appr ify gassing 	1 gas levels 4 gas levels 5 gas levels ls normal. of slow degra bable active opriate action rates. Consi	normal. normal. normal. adation of the paper due gassing. Probably susp n based on transformer ider online monitoring a	e to low temp nicious - perfo assessment nd comprehe	erature (< 140 °C). Ve orm fault identification a results and company p ensive engineering ass	erify insulation and policy. essment.
Duval F Cellulose Duval F Cellulose Duval F Resampling AVO Re Recomm Notations: 1. Analysis is ISO/IEC 17025:20 test is conducted by AVO Diagnostic Servic	Pentagons insulation GA Status g Protocol esampling nendation	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment. Surveillance Increase frequency to ver	 Triangle Triangle Triangle Gas level Indication nanol tests. and/or pro Take appr ify gassing 2. This test is co Pervices Laborator 	1 gas levels 4 gas levels 5 gas levels 5 gas levels ls normal. of slow degra bable active opriate action rates. Consi nducted by a subcon	normal. normal. normal. adation of the paper due gassing. Probably susp n based on transformer ider online monitoring a	e to low temp icious - perfo assessment nd comprehe	erature (< 140 °C). Ve orm fault identification a results and company p ensive engineering ass red ISO Standard 17025 accreditatik ample: AVO Diagnostic Services ac	erify insulation and policy. essment.
Duval F Cellulose Duval F Cellulose Du Resampling AVO Re Recomr Notations: 1. Analysis is ISO/IEC 17025:20 test is conducted by AVO Diagnostic Servi for these results; accreditation status does Accreditation applies to current analysis on	Pentagons insulation GA Status g Protocol esampling nendation 17 accredited, AN res Laboratory of the say to t	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment. Surveillance Increase frequency to ver	 Triangle Triangle Triangle Gas level Indication nanol tests. and/or pro Take appr ify gassing 2. This test is co Services Laborations, s report are base 	1 gas levels 4 gas levels 5 gas levels 5 gas levels Is normal. of slow degra bable active opriate action rates. Consi nducted by a subcon ry has received ISO uL/L = ppm, µg/L = p	normal. normal. normal. adation of the paper due gassing. Probably susp n based on transformer ider online monitoring a "standard 17025 accreditation for th opp, mV/m = dynes/cm, mm7s = cSt information supplied by the client. Av	e to low temp icious - perfo assessment nd comprehe laboratory has receiv s test. 7. Imported S	erature (< 140 °C). Ve orm fault identification a results and company p ensive engineering ass red ISO Standard 17025 accreditati ample: AVO Diagnostic Services ac es does not imply that the contents	erify insulation and policy. essment.
Duval F Cellulose Duval F Cellulose Du Resampling AVO Re Recomm Notations: 1. Analysis is ISO/IEC 17025:20 test is conducted by AVO Diagnostic Service set is conducted by AVO Diagnostic Services assum by this laboratory are the same as all such Services. AVO Diagnostic Services assum pron for any reason whaterourge This trad	Pentagons insulation GA Status g Protocol esampling nendation 17 accredited, AN res Laboratory of 17 accredited, AN res Laboratory of 17 accredited and the responsibility of these y. The analyses, y. The analyses, y. The analyses, y. The analyses, and the analyses paterial in the emission of the analyses of the analyses of the analy	Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 42 (>20) condition with furans/meth Status 3 - High gas levels transformer assessment. Surveillance Increase frequency to ver	 Triangle Triangle Triangle Gas level Indication nanol tests. and/or pro Take appr ify gassing 2. This test is co services Laboration angorreal of the logger of the logger 	1 gas levels 1 gas levels 5 gas levels 5 gas levels is normal. of slow degra bable active opriate action rates. Consi nducted by a subcon oy has received ISO 1/L = pom, up/L = p d upon material and abneatory	normal. normal. normal. adation of the paper due gassing. Probably susp n based on transformer ider online monitoring a standar 17025 accreditation for thi Standard 17025 accreditation for thi standard 17025 accreditation for thi maple or samples tested. Any interpr itition, productivity or proper operation	e to low temp vicious - perfo assessment nd comprehe laboratory has receiv s test. 7. Imported S O Diagnostic Servic relations or opinions of any equipment o	erature (< 140 °C). Ve orm fault identification a results and company p ensive engineering ass red ISO Standard 17025 accreditati ample: AVO Diagnostic Services ac es des not imply that the contents expressed represent the best judgm r other property for which this report	erify insulation and policy. essment. on for this test. 5. This cepts no responsibility of the sample received ent of AVO Diagnostic may be used or relied

DIAGNOSTIC SE	RVICES	919 FRAS	AVO DIAGNOST SER DR. UNIT 13 + B 905-632-8697 + WWW.AVODIAGI	TIC SERVICES URLINGTON, ON · 905-632-8698 NOSTICS.COM	+ L7L 4X8	T 01-76477	EST REPORT '95-701058-00 Page 2 of 2
FRTH (Holdings)	nc	Serial#: /	43\$6467		Mfr: WESTINGH	OUSE Control#:	7647795
		Location: (GODERICH MS 4		kV: 27.6	Order#:	701058
		Equipment:	RANSFORMER		kVA: 5000	Account:	110229
INGERSOLL. N5	C2N9 CA	Compartment:	MAIN(BOTTOM)	Year	Mf'd: 1979	Received:	06/06/2023
ATTN: MARC GA	LECKAS	Breathing:	-B	Syring	e ID: 8001933	Reported:	06/28/2023
PO#: POH007255		Bank: I	Phase: 3	Bottl	e ID:		
Project ID: H-23-0	01	Fluid: MIN I	MPGal: 710	Sampleo	By: CC		
Customer ID: T1				•	-		
	Lab C	control Number:	7647795	7590308	7535748	7505534	7425755
		Date Sampled:	05/17/2023	09/20/2022	04/06/2022	10/21/2021	02/10/2021
		Order Number:	701058	686680	674258	666239	647030
		Oil Temp:	40		45	52	40
Comment:							
General Oil Quali	ty (GOQ)						
ASTM D-15331	Moisture in Oil	(mg/kg):	5	9	2	10	3
ASTM D-9711	Interfacial Tension	(mN/m):	39.49	37.87	38.8	39.88	39.77
ASTM D-9741	Acid Number	(mg KOH/g):	0.027	0.018	0.025	0.021	0.018
ASTM D-1500 ¹	Color Number	(ASTM):	L1.0	L1.0	L1.0	L1.0	1.0
ASTM D-1524 ¹	Visual Exam.	(Relative):	FAIL	PASS	PASS	PASS	PASS
			H2O	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT
ASTM D-1524 ¹	Sediment Exam.	(Relative):	ND	ND	ND	ND	ND
ASTM D-1816 ¹	Dielectric Breakdown 2 m	m (kV °C):	52 (23 C)	40 (23 C)	60 (22 C)	43 (23°C)	55 (23°C)
ASTM D-40521	Density @15°C	(g/mL):	0.8582	0.858	0.8589	0.8588	0.8582
GOQ Diagnostics		Moisture in Oil:	Acceptable for in-se	ervice oil (35 mg/kg	max).		
PER IEEE C57.10	6-2015 Inte	rfacial Tension:	Acceptable for in-se	ervice oil (25 mN/m	min).		
(most recent samp	le)	Acid Number:	Acceptable for in-se	ervice oil (0.2 mg K0	DH/g max).		
	Color Nun	nber and Visual:	Diagnostic not appli	cable. Diagnostic n	ot applicable.		
	Dielectric Breakdow	n ASTM D-1816:	Acceptable for in-se	ervice oil (40 kV min	@ 2mm).		
Comment:							

End of Test Report

F.Kankt

JANET KAROLAT SUPV CHEMIST

Authorized By:

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Avoid the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Assumes no responsibility and makes no warrantly or representation, expressed to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698

TEST REPORT 01-7647792-701058-00

DIAGNOSTIC SERVICES	WWW.AVODIAGNOSTICS.COM						ruge rorz	
ERTH (Holdings) Inc		Serial#:	307425		Mfr:	FERRANTI PACKARD	Control#:	7647792
		Location:	PORT STA	ANLEY	kV:	27.6	Order#:	701058
		Equipment:	TRANSFO	RMER	kVA:	5000	Account:	110229
INGERSOLL, . N5C2N9 C/	4	Compartment:	MAIN(BOT	TOM)	Year Mf'd:	1979	Received:	06/06/2023
ATTN: MARC GALECKAS	5	Breathing:	SEAL		Syringe ID:	8000826	Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle ID:			
Project ID: H-23-001		Fluid: MIN	USGal: 66	5	Sampled By:	CC		
Customer ID: MS1								
		Lab Control Number	"	7647792	7590316	7535754	7505536	7425756
		Date Sampled	1: 05	5/16/2023	09/29/2022	04/05/2022	10/28/2021	02/11/2021
		Order Number	-	/01058	686680	674258	666239	647030
Disselved Cas Analysis (Oil Temp	<u></u>	40	40	38	40	28
DISSOIVED Gas Analysis (DGA)	UZ/NZ Ralic	·-	0.01	0.02	0.01	0.05	0.01
D_3612 ¹		Hydrogen (H2) (ul /l	/- 	44 31	43	43 27	42	42
0-0012		Methane (CH4) (µL/L)		27	20	26	28	30
		Ethane (C2H6) (µL/L)		8	7	7	8	8
		Ethylene (C2H4) (µL/L)):	21	21	21	21	23
		Acetylene (C2H2) (µL/L)):	<1	<1	<1	<1	<1
	Carb	on Monoxide (CO) (µL/L)):	1483	1435	1386	1438	1612
	Car	bon Dioxide (CO2) (µL/L)):	14782	14558	14425	14898	15314
		Nitrogen (N2) (µL/L)):	74826	70694	72365	78241	82350
		Oxygen (O2) (µL/L)):	541	1134	1045	3816	655
		Dissolved Gas /	Analysis Di	iagnostics ·	- IEEE Std C57.104-20	19		
	Absolu	ite Gas Levels (μL/L)	Gas Level Deltas(µL/L) (2 most recent samples)			Gas Generation Rates (µL/L per yr) (3-6 most recent samples within 4-24 mos		
Gas	Level	Diagnostic	Delta		Diagnostic	Rate	Diagnost	ic
Hydrogen (H2)	31	Normal (<= 100)	5	Normal Var	iation (<= 40)	2	No active gassing (<=	20)
Methane (CH4)	27	Normal (<= 110)	0	Normal Var	iation (<= 30)	0	No active gassing (<=	10)
Ethane (C2H6)	0							
	0	Normal (<= 150)	1	Normal Var	iation (<= 25)	0	No active gassing (<=	9)
Ethylene (C2H4)	21	Normal (<= 150) Normal (<= 90)	1 0	Normal Var Normal Var	iation (<= 25) iation (<= 20)	0	No active gassing (<= No active gassing (<=	9) 7)
Ethylene (C2H4) Acetylene (C2H2)	21 <1	Normal (<= 150) Normal (<= 90) Normal (<= 1)	0	Normal Var Normal Var Normal Var	iation (<= 25) iation (<= 20) iation (<= 0)	0	No active gassing (<= No active gassing (<= No active gassing (<=	9) 7) 0)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO)	21 <1 1483	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100)	1 0 0 48	Normal Var Normal Var Normal Var Normal Var	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250)	0 0 0 39	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	9) 7) 0) 100)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2)	21 <1 1483 14782	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) High (> 14000)	1 0 0 48 224	Normal Var Normal Var Normal Var Normal Var Normal Var	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500)	0 0 0 39 -19	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	9) 7) 0) 100) 1000)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics	21 <1 1483 14782 Roger's Ratio	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) High (> 14000) Diagnostic not applicable	1 0 48 224 - Gas level	Normal Var Normal Var Normal Var Normal Var Normal Var s normal.	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500)	0 0 0 39 -19	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	9) 7) 0) 100) 1000)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval	21 <1 1483 14782 Roger's Ratio Triangles	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) High (> 14000) Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable	1 0 48 224 - Gas level - Triangle - Triangle 4 - Triangle 5	Normal Var Normal Var Normal Var Normal Var s normal. 1 gas levels 4 gas levels 5 gas levels	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500) normal. normal. normal.	0 0 39 -19	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	9) 7) 0) 100) 1000)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval	21 <1 1483 14782 Roger's Ratio Triangles	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) High (> 14000) Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable	1 0 48 224 - Gas level - Triangle - Triangle - Triangle -	Normal Var Normal Var Normal Var Normal Var s normal. 1 gas levels 4 gas levels 5 gas levels s normal.	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500) normal. normal. normal.	0 0 39 -19	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	9) 7) 0) 100) 1000)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval Duval F Cellulose	21 21 1483 14782 Roger's Ratio Triangles Pentagons insulation	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 10 (3< ra	1 0 0 48 224 - Gas level - Triangle - Triangle - Triangle - Gas level tio <= 20) -	Normal Var Normal Var Normal Var Normal Var Normal Var s normal. 1 gas levels 4 gas levels 5 gas levels 5 gas levels s normal. No indicatio	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500) normal. normal. normal.	0 0 39 -19	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<=	9) 7) 0) 100) 1000)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval Duval F Cellulose	21 21 21 21 21 21 21 21 21 21 21 21 21 2	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) High (> 14000) Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 10 (3< ra Status 3 - High gas levels transformer assessment.	1 0 0 48 224 - Gas level - Triangle - Triangle - Gas level tio <= 20) - and/or pro Take appro	Normal Var Normal Var Normal Var Normal Var Normal Var s normal. 1 gas levels 4 gas levels 5 gas levels 5 gas levels 5 gas levels bable active opriate active	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500) normal. normal. normal. or of a fault involving pa gassing. Probably susp n based on transformer	per bicious - performance	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= orm fault identification a results and company p	9) 7) 0) 100) 1000)
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval Duval Cellulose D Resampling	21 21 1483 14782 Roger's Ratio Triangles Pentagons insulation GA Status g Protocol	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) High (> 14000) Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 10 (3< ra Status 3 - High gas levels transformer assessment. Surveillance	1 0 0 48 224 - Gas level - Triangle - Triangle - Triangle - Triangle - Gas level tio <= 20) - and/or pro Take appro	Normal Var Normal Var Normal Var Normal Var Normal Var s normal. 1 gas levels 4 gas levels 5 gas levels 5 gas levels s normal. No indicatio bable active opriate actio	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500) normal. normal. normal. ormal. ormal. ormal. photo a fault involving pa gassing. Probably susp in based on transformer	per bicious - perfor assessment	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= orm fault identification a results and company p	9) 7) 0) 100) 1000) and policy.
Ethylene (C2H4) Acetylene (C2H2) Carbon Monoxide (CO) Carbon Dioxide (CO2) DGA Diagnostics Duval Duval Cellulose D Resampling AVO Ro	21 21 1483 14782 Roger's Ratio Triangles Pentagons insulation GA Status g Protocol esampling	Normal (<= 150) Normal (<= 90) Normal (<= 1) High (> 1100) High (> 14000) Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable CO2/CO ratio = 10 (3< ra Status 3 - High gas levels transformer assessment. Surveillance Increase frequency to ver	1 0 0 48 224 - Gas level - Triangle - Triangle - Triangle - Triangle - Gas level tio <= 20) - and/or pro Take appro	Normal Var Normal Var Normal Var Normal Var Normal Var s normal. 1 gas levels 4 gas levels 5 gas levels 5 gas levels 5 gas levels 5 gas levels bable active opriate actio rates. Cons	iation (<= 25) iation (<= 20) iation (<= 0) iation (<= 250) iation (<= 2500) normal. normal. normal. ormal. on of a fault involving pa gassing. Probably susp in based on transformer sider online monitoring a	per bicious - perfor assessment	No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= No active gassing (<= orm fault identification a results and company p	9) 7) 0) 100) 1000) and bolicy. essment.

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , μg/m, μL/L = ppm, μg/L = ppb, mN/m = dynes/cm, mm²/s = cSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

DIAGNOSTIC SER	W ICES	919 FRAS	AVO DIAGNOS ER DR. UNIT 13 + E 905-632-8697 + WWW.AVODIAG	TIC SERVICES BURLINGTON, ON - 905-632-8698 NOSTICS.COM	TEST REPORT 01-7647792-701058-00 Page 2 of 2		
ERTH (Holdings) In	IC	Serial#: 3	807425		Mfr: FERRANTI	Control#:	7647792
		Location: F	PORT STANLEY		kV : 27.6	Order#:	701058
		Equipment: 7			kVA: 5000	Account	110229
INGERSOLL. N50	C2N9 CA	Compartment: N		Year	Mf'd: 1979	Received:	06/06/2023
ATTN: MARC GAL	ECKAS	Breathing: S	SEAL	Syring	e ID: 8000826	Reported:	06/28/2023
PO#: POH007255		Bank: F	Phase: 3	Bottl	e ID:	•	
Project ID: H-23-00	01	Fluid: MIN U	JSGal: 665	Sampleo	By: CC		
Customer ID: MS1				-	-		
	Lab	Control Number:	7647792	7590316	7535754	7505536	7425756
		Date Sampled:	05/16/2023	09/29/2022	04/05/2022	10/28/2021	02/11/2021
		Order Number:	701058	686680	674258	666239	647030
		Oil Temp:	40	40	38	40	28
Comment:							
General Oil Qualit	y (GOQ)						
ASTM D-15331	Moisture in Oil	(mg/kg):	15	12	9	17	5
ASTM D-9711	Interfacial Tension	(mN/m):	36.13	36.49	36.58	36.12	36.97
ASTM D-9741	Acid Number	(mg KOH/g):	0.045	0.026	0.047	0.040	0.039
ASTM D-15001	Color Number	(ASTM):	L1.5	L1.5	L1.5	L1.5	1.5
ASTM D-15241	Visual Exam.	(Relative):	PASS	PASS	PASS	PASS	PASS
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT
ASTM D-15241	Sediment Exam.	(Relative):	ND	ND	ND	ND	ND
ASTM D-1816 ¹	Dielectric Breakdown 2 m	nm (kV °C):	21 (23 C)	39 (23 C)	45 (22 C)	53 (23°C)	65 (23°C)
ASTM D-40521	Density @15°C	(g/mL):	0.8595	0.859	0.8601	0.8602	0.8593
GOQ Diagnostics		Moisture in Oil:	Acceptable for in-se	ervice oil (35 mg/kg	max).		
PER IEEE C57.106	-2015 Int	erfacial Tension:	Acceptable for in-se	ervice oil (25 mN/m	min).		
(most recent sampl	e)	Acid Number:	Acceptable for in-se	ervice oil (0.2 mg KC	DH/g max).		
	Color Nu	nber and Visual:	Diagnostic not appl	icable. Diagnostic n	ot applicable.		
	Dielectric Breakdow	n ASTM D-1816:	Below limit for in-se	ervice oil (40 kV min	@ 2mm).		

Comment:

End of Test Report

F.Karoly

Authorized By:

JANET KAROLAT SUPV CHEMIST

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698 WWW.AVODIAGNOSTICS.COM

TEST REPORT 01-7647793-701058-00

DIAGNOSTIC SERVICES		905-632-8697 + 905-632-8698 WWW.AVODIAGNOSTICS.COM						Page 1 of 2
ERTH (Holdings) Inc		Serial#:	T29931		Mfr:	PIONEER FI FCTRIC	Control#:	7647793
		Location:	AYLMER -	- MCBRIEN	kV:	27.6	Order#:	701058
		Equipment:	TRANSFC	RMER	kVA:	3000	Account:	110229
INGERSOLL, . N5C2N9 C	A	Compartment:	MAIN(BOT	ГТОМ)	Year Mf'd:	1967	Received:	06/06/2023
ATTN: MARC GALECKAS	6	Breathing:	FB	- /	Syringe ID:	8006681	Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle ID:			
Project ID: H-23-001		Fluid: MIN	USGal: 73	39	Sampled By:	CC		
Customer ID: MS2 TX1								
		Lab Control Numbe	r:	7647793	7590309	7535751	7505537	7425758
		Date Sampleo	d: 05	5/16/2023	09/29/2022	04/05/2022	08/04/2021	02/11/2021
		Order Numbe	r:	701058	686680	674258	666239	647030
		Oil Tem	o:	30	25	15	30	11
Dissolved Gas Analysis ((DGA)	O2/N2 Ratio	p:	0.49	0.48	0.5	0.47	0.48
ASTM		Transformer Age (yrs):	56	55	55	54	54
D-3612 ¹		Hydrogen (H2) (µL/L):	2	4	2	6	3
		Methane (CH4) (µL/L):	1	1	1	2	1
		Ethane (C2H6) (µL/L):	<1	<1	<1	<1	<1
		Ethylene (C2H4) (µL/L):	2	3	2	3	3
		Acetylene (C2H2) (µL/L):	<1	<1	<1	<1	<1
	Carb	oon Monoxide (CO) (µL/L):	84	78	72	124	96
	Car	bon Dioxide (CO2) (μL/L):	913	974	893	1105	984
		Nitrogen (N2) (µL/L):	61749	55331	57653	63819	71242
		Oxygen (O2) (µL/L):	30540	26652	28970	29975	33964
		Dissolved Gas	Analysis D	iagnostics –	IEEE Std C57.104-20	19		
	Absolu	ute Gas Levels (µL/L)		Gas Level D	Deltas(µL/L)	Gas	Generation Rates (µL	/L per yr)
		. , , , , , , , , , , , , , , , , , , ,		(2 most rece	ent samples)	(3-6 mos	t recent samples with	in 4-24 mos.)
Gas	Level	Diagnostic	Delta		Diagnostic	Rate	Diagnost	ic
Hydrogen (H2)	2	Normal (<= 40)	-2			-2	No active gassing (<=	10)
Methane (CH4)	1	Normal (<= 20)	0	Normal Vari	ation (<= 10)	-1	No active gassing (<=	3)
Ethane (C2H6)	0	Normal (<= 15)	0	Normal Vari	ation (<= 7)	0	No active gassing (<=	2)
Ethylene (C2H4)	2	Normal (<= 60)	-1			0	No active gassing (<=	5)
Acetylene (C2H2)	<1	Normal (<= 2)	0	Normal Vari	ation (<= 0)	0	No active gassing (<=	0)
Carbon Monoxide (CO)	84	Normal (<= 500)	6	Normal Vari	ation (<= 175)	-20	No active gassing (<=	80)
Carbon Dioxide (CO2)	913	Normal (<= 5500)	-61			-90	No active gassing (<=	800)
DGA Diagnostics	Roger's Ratio	Diagnostic not applicable	- Gas level	ls normal.				
Duval Triangles		Diagnostic not applicable Diagnostic not applicable Diagnostic not applicable	– Triangle – Triangle – Triangle	1 gas levels 4 gas levels 5 gas levels	normal. normal. normal.			
Duval I	Pentagons	Diagnostic not applicable	- Gas leve	ls normal.				
Cellulose	insulation	CO and CO2 levels are n	ormal. No i	ndication of a	fault involving paper.			
D	GA Status	Status 1 - Normal gas lev	els and no	Indication of	gassing. Continue rout	ine DGA and	l normal transformer op	peration.
Resamplin	g Protocol	Routine Screening						
AVO R	esampling mendation	Resample within 1 year.						
Ittoooliii								

Comment:

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , μg/m, μL/L = ppm, μg/L = ppb, mN/m = dynes/cm, mm²/s = cSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698 WWW.AVODIAGNOSTICS.COM

TEST REPORT 01-7647793-701058-00

Page 2 of 2

ERTH (Holdings) Ir	nc	Serial#:	T29931		Mfr: PIONEER ELECTRIC	Contro	l#: 7647793
		Location:	AYLMER - MCBRIEN	I	kV: 27.6	Orde	r #: 701058
		Equipment:	TRANSFORMER		kVA: 3000	Accou	n t: 110229
INGERSOLL, . N50	C2N9 CA	Compartment:	MAIN(BOTTOM)	Year	Mf'd: 1967	Receive	: 06/06/2023
ATTN: MARC GAL	ECKAS	Breathing:	FB	Syring	ge ID: 8006681	Reporte	: 06/28/2023
PO#: POH007255		Bank:	Phase: 3	Bott	le ID:		
Project ID: H-23-0	01	Fluid: MIN	USGal: 739	Sample	d By: CC		
Customer ID: MS2	2 TX1						
	Lab	Control Number	: 7647793	7590309	7535751	7505537	7425758
		Date Sampled	: 05/16/2023	09/29/2022	04/05/2022	08/04/2021	02/11/2021
		Order Number	701058	686680	674258	666239	647030
		Oil Temp	: 30	25	15	30	11
General Oil Qualit	y (GOQ)						
ASTM D-15331	Moisture in Oil	(mg/kg)	: 14	18	10	18	5
ASTM D-9711	Interfacial Tension	(mN/m)	: 36.66	42.84	37.23	36.7	37.03
ASTM D-9741	Acid Number	(mg KOH/g)	: 0.018	0.018	0.024	0.018	0.016
ASTM D-15001	Color Number	(ASTM)	: L1.0	L1.0	L1.0	L1.0	1.5
ASTM D-15241	Visual Exam.	(Relative)	: PASS	PASS	PASS	PASS	PASS
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT
ASTM D-15241	Sediment Exam.	(Relative)	: ND	ND	ND	ND	ND
ASTM D-18161	Dielectric Breakdown 2 m	nm (kV °C)	: 28 (23 C)	45 (24 C)	43 (22 C)	51 (23°C)	56 (24°C)
ASTM D-40521	Density @15°C	(g/mL)	: 0.8544	0.8539	0.8249	0.8551	0.8553
GOQ Diagnostics		Moisture in Oil	: Acceptable for in-se	ervice oil (35 mg/kg	max).		
PER IEEE C57.106	6-2015 Inte	erfacial Tension	: Acceptable for in-se	ervice oil (25 mN/m	min).		
(most recent sampl	e)	Acid Number	: Acceptable for in-se	ervice oil (0.2 mg K	OH/g max).		
	Color Nu	mber and Visua	: Diagnostic not appl	icable. Diagnostic r	not applicable.		
	Dielectric Breakdow	n ASTM D-1816	Below limit for in-se	ervice oil (40 kV mir	n @ 2mm).		
Comment:							

End of Test Report

F.Kand

JANET KAROLAT SUPV CHEMIST

Authorized By:

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic. Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698

TEST REPORT 01-7647797-701058-00

-4 - 4 0

DIAGNOSTIC SERVICES			www	AVODIAG	SNOSTICS.COM			Page 1 of 2
ERTH (Holdings) Inc		Serial#:	2305405		Mfr	FERRANTI	Control#:	7647797
		Location:	AYLMER		kV	27.6	Order#:	701058
		Equipment:	TRANSFC	RMER	kVA:	3000	Account:	110229
INGERSOLL, . N5C2N9 CA	A	Compartment:	MAIN(BOT	ГТОМ)	Year Mf'd:	1992	Received:	06/06/2023
ATTN: MARC GALECKAS		Breathing:	SEAL	- /	Syringe ID:	8007673	Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle ID:			
Project ID: H-23-001		Fluid: MIN	USGal: 40)9	Sampled By:	CC		
Customer ID:								
		Lab Control Numbe	r:	7647797	7590315	7535758	7505538	7425749
		Date Sampled	l: 05	5/16/2023	09/29/2022	04/05/2022	08/04/2021	02/11/2021
		Order Numbe	r:	701058	686680	674258	666239	647030
		Oil Temp) :	45	45	38	45	28
Dissolved Gas Analysis (DGA)	O2/N2 Ratio):	0.02	0.01	0.03	0.02	0.02
ASTM		Transformer Age (yrs):	31	30	30	29	29
D-3612 ¹		Hydrogen (H2) (µL/L):	8	9	8	10	8
		Methane (CH4) (µL/L):	49	46	44	48	47
		Ethane (C2H6) (µL/L):	13	12	12	12	12
		Ethylene (C2H4) (µL/L):	82	79	75	81	81
		Acetylene (C2H2) (µL/L):	<1	<1	<1	<1	<1
	Carb	on Monoxide (CO) (µL/L):	922	852	825	941	869
	Car	bon Dioxide (CO2) (µL/L):	9327	9169	7850	9475	7495
		Nitrogen (N2) (µL/L):	77605	66926	73014	75451	73094
		Oxygen (O2) (µL/L):	1659	852	2538	1420	1255
		Dissolved Gas	Analysis D	iagnostics	s – IEEE Std C57.104-20)19		
	Absolu	ute Gas Levels (uL/L)		Gas Leve	el Deltas(uL/L)	Gas (Generation Rates (uL	/L per vr)
	1.00010			(2 most re	ecent samples)	(3-6 most	recent samples with	in 4-24 mos.)
Gas	Level	Diagnostic	Delta		Diagnostic	Rate	Diagnost	ic
Hydrogen (H2)	8	Normal (<= 100)	-1			-1	No active gassing (<=	20)
Methane (CH4)	49	Normal (<= 110)	3	Normal V	ariation (<= 30)	1	No active gassing (<=	10)
Ethane (C2H6)	13	Normal (<= 150)	1	Normal V	ariation (<= 25)	1	No active gassing (<=	9)
Ethylene (C2H4)	82	Normal (<= 90)	3	Normal V	ariation (<= 20)	1	No active gassing (<=	7)
Acetylene (C2H2)	<1	Normal (<= 1)	0	Normal V	ariation (<= 0)	0	No active gassing (<=	0)
Carbon Monoxide (CO)	922	Elevated (> 900)	70	Normal V	ariation (<= 250)	-7	No active gassing (<=	100)
Carbon Dioxide (CO2)	9327	Normal (<= 10000)	158	Normal V	ariation (<= 2500)	98	No active gassing (<=	1000)
DGA Diagnostics	Roger's Ratio	Diagnostic not applicable	- Gas leve	ls normal.				
	Talanal	Diamaghteriat	Tuiter 1	4	I			
Duval	Irlangles	Diagnostic not applicable	- I riangle	1 gas leve	ls normal.			
		Diagnostic not applicable	- I riangle	4 gas leve	ls normal.			
		Diagnostic not applicable	- I riangle	5 gas leve	ls normal.			
Duval F	entagons	Diagnostic not applicable	- Gas leve	ls normal.				
Cellulose	CO2/CO ratio = 10 (3< ra	tio <= 20) -	No indicat	tion of a fault involving pa	aper			
D	GA Status	Status 2 - Elevated gas le	evels and/o	r possible g	gassing. Possibly suspici	ous - warrant	s additional investigatio	on. Increase
		surveillance and DGA fre	quency.					
Resampling	g Protocol	Surveillance						
AVO Re Recomr	esampling nendation	Resample within 3 month	S.					
1								

test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no respons for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg, µg/g, µg/mL, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = cSt Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

Δ		919 FRA	AVO DIAGNOS SER DR. UNIT 13 + E	TIC SERVICES BURLINGTON, ON ·	+ L7L 4X8	T 01-76477	TEST REPORT 01-7647797-701058-00	
DIAGNOSTIC SER	VICES	905-632-8697 + WWW.AVODIAG	905-632-8698 NOSTICS.COM			Page 2 of 2		
ERTH (Holdings) In	с	Serial#:	2305405		Mfr: FERRANTI PACKARD	Control#:	7647797	
		Location:	AYLMER		kV: 27.6	Order#:	701058	
		Equipment:	TRANSFORMER		kVA: 3000	Account:	110229	
INGERSOLL, . N5C	2N9 CA	Compartment:	MAIN(BOTTOM)	Year	Mf'd: 1992	Received:	06/06/2023	
ATTN: MARC GAL	ECKAS	Breathing:	SEAL	Syring	e ID: 8007673	Reported:	06/28/2023	
PO#: POH007255		Bank:	Phase: 3	Bottl	le ID:			
Project ID: H-23-00)1	Fluid: MIN	USGal: 409	Sampleo	d By: CC			
Customer ID:			_					
	Lab (Control Number	r: 7647797	7590315	7535758	7505538	7425749	
		Date Sampled	l: 05/16/2023	09/29/2022	04/05/2022	08/04/2021	02/11/2021	
		Order Number	r: 701058	686680	674258	666239	647030	
		Oil Temp	. 45	45	38	45	28	
Comment:								
General Oil Quality	(GOQ)							
ASTM D-1533 ¹	Moisture in Oil	(mg/kg)	5	6	4	9	2	
ASTM D-9711	Interfacial Tension	(mN/m)	31.07	31.09	31.32	30.46	31.45	
ASTM D-9741	Acid Number	(mg KOH/g)	0.044	0.029	0.042	0.035	0.034	
ASTM D-1500¹	Color Number	(ASTM)	L3.0	L3.0	L2.5	L2.5	3.0	
ASTM D-15241	Visual Exam.	(Relative)	PASS	PASS	PASS	PASS	PASS	
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	
ASTM D-1524 ¹	Sediment Exam.	(Relative)	ND	TRACE	ND	ND	ND	
ASTM D-1816¹	Dielectric Breakdown 2 m	m (kV °C)): 26 (23 C)	71 (24 C)	55 (22 C)	47 (23°C)	55 (24°C)	
ASTM D-40521	Density @15°C	(g/mL)	0.8631	0.8622	0.8638	0.8635	0.8633	
GOQ Diagnostics		Moisture in Oi	I: Acceptable for in-se	ervice oil (35 mg/kg	max).			
PER IEEE C57.106	-2015 Inte	erfacial Tension	Acceptable for in-se	ervice oil (25 mN/m	min).			
(most recent sample	e)	Acid Number	Acceptable for in-se	ervice oil (0.2 mg K0	OH/g max).			
	Color Nur	nber and Visua	I: Diagnostic not appl	icable. Diagnostic n	ot applicable.			
	Dielectric Breakdow	n ASTM D-1816	Below limit for in-se	ervice oil (40 kV min	@ 2mm).			
Comment:								

End of Test Report

F.Karold

Authorized By:

JANET KAROLAT SUPV CHEMIST

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.



AVO DIAGNOSTIC SERVICES

919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698 WWW AVODIAGNOSTICS COM

Page 1 of 2

DIAGNOSTIC SERVICES			VVVVVV	.AVODIAG	NOSTICS.COM			•
ERTH (Holdings) Inc		Serial#:	062108		M	fr: NORTHERN	Control#:	7647796
		Location:	CLINTON	ON	k	V: 27.6	Order#:	701058
		Equipment:	TRANSFC	RMER	kV	A: 5000	Account:	110229
INGERSOLL, . N5C2N9 CA	4	Compartment:	MAIN(BOTTOM)		Year Mf	d: 2007	Received:	06/06/2023
ATTN: MARC GALECKAS	i	Breathing:	SEAL		Syringe I	D: 8006869	Reported:	06/28/2023
PO#: POH007255		Bank:	Phase: 3		Bottle I	D:		
Project ID: H-23-001 Fluid: MIN		Liters: 324	47	Sampled B	y: CC			
Customer ID: REPLACEM	ENT							
		Lab Control Number	r:	7647796	7590310	7535755	7505533	7425753
		Date Sampled	I: 05	5/17/2023	09/20/2022	04/06/2022	10/21/2021	02/10/2021
		Order Number		701058	686680	674258	666239	647030
		Oil Temp	:	19	30	15	15	
Dissolved Gas Analysis (DGA)	O2/N2 Ratio	:	0.37	0.39	0.43	0.4	0.46
ASTM		Transformer Age (yrs)):	16	15	15	14	14
D-3612 ¹		Hydrogen (H2) (µL/L)): [3	<2	<2	3	<2
		Methane (CH4) (µL/L)):	2	2	2	2	2
		Ethane (C2H6) (µL/L)):	<1	<1	<1	<1	<1
		Ethylene (C2H4) (µL/L)):	32	30	27	31	26
	Carl	Acetylene (C2H2) (µL/L)): [<1 054	<1	<1	<1	[`>
	Carb	ion Monoxide (CO) (µL/L)		254	211	170	223	120
	Car	Nitrogen (N2) (µL/L)		61252	F3553	940 57024	1272	690
				22662	21072	2/270	26020	28861
		Oxygen (Oz) (µE/E		22002	21072	24210	20320	20001
		Dissolved Gas /	Analysis D	iagnostics	s – IEEE Std C57.104-	2019		
	Absolu	ute Gas Levels (µL/L)		Gas Leve	l Deltas(μL/L)	Gas G	Generation Rates (μL	/L per yr)
				(2 most re	ecent samples)	(3-6 most	recent samples with	in 4-24 mos.)
Gas	Level	Diagnostic	Delta		Diagnostic	Rate	Diagnost	ic
Hydrogen (H2)	3	Normal (<= 40)	1	Normal Va	ariation (<= 25)	0	No active gassing (<=	10)
Methane (CH4)	2	Normal (<= 20)	0	Normal Va	ariation (<= 10)	0	No active gassing (<=	3)
Ethane (C2H6)	0	Normal (<= 15)	0	Normal Va	ariation (<= 7)	0	No active gassing (<=	2)
Ethylene (C2H4)	32	Normal (<= 60)	2	Normal Va	ariation (<= 20)	1	No active gassing (<=	5)
Acetylene (C2H2)	<1	Normal (<= 2)	0	Normal Va	ariation (<= 0)	0	No active gassing (<=	0)
Carbon Monoxide (CO)	254	Normal (<= 500)	43	Normal Va	ariation (<= 175)	28	No active gassing (<=	80)
Carbon Dioxide (CO2)	1126	Normal (<= 5500)	-34			-38	No active gassing (<=	800)
DGA Diagnostics	Roger's Ratio	Diagnostic not applicable	- Gas level	ls normal.				
Dural	Trianalaa	Dia mandia matana dia dala	Trianala	4	I			
Duvai	Triangles	Diagnostic not applicable	- Triangle	1 gas level	is normal.			
		Diagnostic not applicable	- Triangle	4 gas level	is normal.			
Duvel E	Pontogono				is normal.			
	inculation		- Gas level	ndigation o	f a fault involving page	r		
Cellulose		Co and Coz levels are in	olo and no			Liting DCA and	normal transformer on	oration
Bosampling	Brotocol	Poutino Scrooning		Indication	or gassing. Continue re	Juline DGA and		
		Posamplo within 1 year						
AVU R	pendetion	rxesample within i year.						
Comment:	inerroation	1						
General Oil Quality (GOQ)							
Notations: 1. Analysis is ISO/IEC 17025:20 test is conducted by AVO Diagnostic Service	17 accredited, AN ces Laboratory ot	IAB Accredited Certificate Number L2303 her than Primary Lab. 6. AVO Diagnostic	2. This test is co Services Laborate	nducted by a sub ory has received I	contracted laboratory. 3. Subcontra ISO Standard 17025 accreditation for	cted laboratory has receiv or this test. 7. Imported S	ved ISO Standard 17025 accreditati ample: AVO Diagnostic Services ac	on for this test. 5. This cepts no responsibility
for these results; accreditation status does Accreditation applies to current analysis on by this laboratory are the same as all such	not apply to these ly. The analyses, material in the en-	e results. 8. Imported Equipment 10. mg/k opinions or interpretations contained in th vironment from which the sample was take	g , µg/g, µg/mL, µ s report are base en. Our test result	uL/L = ppm, µg/L ed upon material a ts relate only to th	. = ppb, mN/m = dynes/cm, mm²/s = and information supplied by the clien le sample or samples tested. Any in	cSt t. AVO Diagnostic Servic terpretations or opinions	es does not imply that the contents expressed represent the best judan	of the sample received
Services. AVO Diagnostic Services assume upon for any reason whatsoever. This test	es no responsibilit report shall not b	y and makes no warranty or representatio e reproduced except in full, without writter	n, expressed or in approval of the l	mplied as to the c aboratory.	condition, productivity or proper oper	ation of any equipment o	r other property for which this report	may be used or relied

AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698

TEST REPORT 01-7647796-701058-00

Page 2 of 2

DIAGNOSTIC S	ERVICES		WWW.AVODIAG	WWW.AVODIAGNOSTICS.COM				
ERTH (Holdings)	Inc	Serial#:	062108		Mfr: NORTHERN	Control	I#: 7647796	
		Location:	CLINTON ON		kV: 27.6	Order	#: 701058	
		Equipment:	TRANSFORMER		kVA: 5000	Accour	nt: 110229	
INGERSOLL, . N	5C2N9 CA	Compartment:	MAIN(BOTTOM)	Year	Mf'd: 2007	Receive	d: 06/06/2023	
ATTN: MARC GA	ALECKAS	Breathing:	SEAL	Syring	e ID: 8006869	Reporte	d: 06/28/2023	
PO#: POH007255	5	Bank:	Phase: 3	Bottl	e ID:			
Project ID: H-23-	001	Fluid: MIN	Liters: 3247	Sampleo	By: CC			
Customer ID: RE	PLACEMENT							
	Lab (Control Numbe	r: 7647796	7590310	7535755	7505533	7425753	
		Date Sampled	d: 05/17/2023	09/20/2022	04/06/2022	10/21/2021	02/10/2021	
		Order Numbe	r: 701058	686680	674258	666239	647030	
		Oil Tem	b: 19	30	15	15		
ASTM D-15331	Moisture in Oil	(mg/kg): 5	6	3	17	2	
ASTM D-9711	Interfacial Tension	(mN/m): 35.11	34.83	35.46	35.68	35.69	
ASTM D-9741	Acid Number	(mg KOH/g): 0.032	0.031	0.027	0.021	0.021	
ASTM D-15001	Color Number	(ASTM): L1.5	L1.5	L1.0	L1.0	1.5	
ASTM D-1524 ¹	Visual Exam.	(Relative): PASS	PASS	PASS	PASS	PASS	
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	
ASTM D-1524 ¹	Sediment Exam.	(Relative): ND	TRACE	ND	ND	ND	
ASTM D-1816 ¹	Dielectric Breakdown 2 m	m (kV °C): 62 (23 C)	50 (23 C)	54 (22 C)	69 (23°C)	44 (24°C)	
ASTM D-40521	Density @15°C	(g/mL): 0.8858	0.8853	0.8861	0.8864	0.8829	
GOQ Diagnostic	S	Moisture in Oi	I: Acceptable for in-se	ervice oil (35 mg/kg	max).			
PER IEEE C57.10	06-2015 Inte	erfacial Tension	1: Acceptable for in-se	ervice oil (25 mN/m	min).			
(most recent sam	ple)	Acid Numbe	r: Acceptable for in-se	ervice oil (0.2 mg K0	DH/g max).			
	Color Nur	nber and Visua	I: Diagnostic not appl	cable. Diagnostic n	ot applicable.			
	Dielectric Breakdow	n ASTM D-181	6: Acceptable for in-se	ervice oil (40 kV min	@ 2mm).			
Comment:								

End of Test Report

F.Kankt

Authorized By:

JANET KAROLAT SUPV CHEMIST

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.



APPENDIX I. ERTH Substation Maintenance Report





MAINTENANCE INSPECTION REPORT

ERTH Power Corporation 143 Bell St Ingersoll, ON N5C 3K5

Re: Maintenance Inspection Report – Ref: H-23-001

- Site: Beechville
- Date: October 22, 2023

Index

Introductory	2
Beachville Substation MSI	3
Appendix A - Oil Report	5
Appendix B - Test Report	6



Introductory

Please find the enclosed report for the maintenance work completed October 22, 2023 for the Beechville MSI station identified below.

Erth Corp cleaned, serviced and tested as required the main power system. A summary of the site findings is listed below for your review. All findings are referenced to the Ontario Electrical Safety Code (OESC) and the International Electrical Testing Association (NETA) where applicable.

All other equipment that ERTH Corp tested appears in satisfactory condition, suitable for continued service. Please contact us should you wish us to provide pricing and services for any or all of the recommended repairs listed in this report.

Oil and dissolved gas analysis:

A snap shot of the diagnostics from the oil and dissolved gas analysis can be found below with the formal report from AVO in Appendix A.

Beechville (Existing Oil):	
DGA Diagnostics Roger's	Thermal > 700 °C
Ratio	
Duval Triangles	Triangle 1: Thermal fault (t > 700°C)
	Diagnostic not applicable – Triangle 4 gas levels normal.
	Triangle 5: Thermal fault (t > 700°C)
Duval Pentagons	Pentagon 1: Thermal fault (t > 700°C)
	Pentagon 2: Thermal fault in oil only
Cellulose insulation	CO2/CO ratio = 9 (3< ratio <= 20) - No indication of a fault involving paper
DGA Status	Status 3 - High gas levels and/or probable active gassing.
	Probably suspicious - perform fault identification and transformer
	assessment. Take appropriate action based on transformer assessment
	results and company policy.
Resampling Protocol	Surveillance
AVO Resampling	Increase frequency to verify gassing rates.
Recommendation	Consider online monitoring and comprehensive engineering assessment.

Recommendation:

- Increase sampling frequency and consider online monitoring.
- Next Oil Sample schedule for March 2024

Test Reports:

All equipment tested are in align with NETA recommendations. The test reports can be found in Appendix B.



Beachville Substation MSI

<u>Site: Substation # MSI</u> <u>Address: 434839 Zorra Line, Beachville</u>

Spring Inspection Comments/Follow up:

- Vines are growing along / through the South-West corner and side of the fence.
 - Vines cut back.
- The service for the heater in the main incoming switch still needs to be completed.
 - Heater replaced, in good working order.
- The transformer and switch should be painted.
 - Transformer and switch painted.





ERTH Power – 2023 Substation Maintenance Report



October Maintenance Comments:

- Maintenance was conducted during night time shutdown.
- Transformer and switch painted between spring maintenance and fall. The paint job is satisfactory, showing not signs of early rusting.
- Transformer showed signs of condensation inside high voltage hood. We recommend installing an anti-condensate material, or a cell heater to help reduce condensation.



- Transformer and switch with new paint.



- Transformer hood, showing signs of condensation.

ERTH Power – 2023 Substation Maintenance Report



Appendix A - Oil Report



AV0
DIAGNOSTIC SERVICES

AVO DIAGNOSTIC SERVICES 919 FRASER DR. UNIT 13 + BURLINGTON, ON + L7L 4X8 905-632-8697 + 905-632-8698

TEST REPORT 01-7647789-701058-00

Page 1 of 2

DIAGNOSTIC SERVICES			Fage 1012			
ERTH (Holdings) Inc	Serial#: 225	5151	N	/lfr:	Control	#: 7647789
	Location: BE	ACHVILLE		kV: 27.6	Order	#: 701058
	Equipment: TR	ANSFORMER	k	VA: 3000	Accoun	t: 110229
INGERSOLL, . N5C2N9 CA	Compartment: MA	IN(BOTTOM)	Year M	f'd: 1976	Received	d: 06/06/2023
ATTN: MARC GALECKAS	Breathing: SE	AL	Syringe	ID: 8003346	Reported	d: 06/28/2023
PO#: POH007255	Bank: Pha	ase: 3	Bottle	ID:		
Project ID: H-23-001	Fluid: MIN US	Gal: 574	Sampled	Sampled By: CC		
Customer ID: MS1						
	Lab Control Number:	7647789	7590319	7535750	7515375	7425750
	Date Sampled:	05/16/2023	09/29/2022	04/05/2022	11/30/2021	02/11/2021
	Order Number:	701058	686680	674258	668835	647030
	Oil Temp:	40		38	30	20
Dissolved Gas Analysis (DGA)	O2/N2 Ratio:	0.2	0.21	0.2	0.2	0.21
ASTM	Transformer Age (yrs):	47	46	46	45	45
D-3612 ¹	Hydrogen (H2) (µL/L):	4	5	4	4	4
	Methane (CH4) (µL/L):	12	11	11	12	13
	Ethane (C2H6) (ul /l.):	5	Δ	Δ	5	5

Methane (CH4) (µL/L):	12	11	11	12	13
Ethane (C2H6) (µL/L):	5	4	4	5	5
Ethylene (C2H4) (µL/L):	72	67	64	69	71
Acetylene (C2H2) (µL/L):	<1	<1	<1	<1	<1
Carbon Monoxide (CO) (µL/L):	952	908	829	931	977
Carbon Dioxide (CO2) (µL/L):	8943	8885	7752	8790	8349
Nitrogen (N2) (µL/L):	67950	63595	64025	69111	71385
Oxygen (O2) (μL/L):	13857	13422	12604	13895	14827

Dissolved Gas Analysis Diagnostics – IEEE Std C57.104-2019

	Absolu	ute Gas Levels (μL/L)	Gas Level Deltas(µL/L) (2 most recent samples) (;		Gas ((3-6 most	Generation Rates (μL/L per yr) t recent samples within 4-24 mos.)		
Gas	Level	Diagnostic	Delta	Diagnostic	Rate	Diagnostic		
Hydrogen (H2)	4	Normal (<= 40)	-1		0	No active gassing (<= 10)		
Methane (CH4)	12	Normal (<= 20)	1	Normal Variation (<= 10)	0	No active gassing (<= 3)		
Ethane (C2H6)	5	Normal (<= 15)	1	Normal Variation (<= 7)	0	No active gassing (<= 2)		
Ethylene (C2H4)	72	Elevated (> 60)	5	Normal Variation (<= 20)	3	No active gassing (<= 5)		
Acetylene (C2H2)	<1	Normal (<= 2)	0	Normal Variation (<= 0)	0	No active gassing (<= 0)		
Carbon Monoxide (CO)	952	High (> 600)	44	Normal Variation (<= 175)	37	No active gassing (<= 80)		
Carbon Dioxide (CO2)	8943	High (> 8000)	58	Normal Variation (<= 1750)	386	No active gassing (<= 800)		
DGA Diagnostics	Roger's	Thermal > 700 °C						
	Ratio							
Duval	Triangles	Triangle 1: Thermal fault (t > 700°C)						
		Diagnostic not applicable – Triangle 4 gas levels normal.						
Duval F	Pentagons	Pentagon 1: Thermal faul Pentagon 2: Thermal faul	Pentagon 1: Thermal fault (t > 700°C) Pentagon 2: Thermal fault in oil only					
Cellulose	insulation	CO2/CO ratio = 9 (3< rati	o <= 20) - N	No indication of a fault involving paper	r			
D	GA Status	Status 3 - High gas levels transformer assessment.	and/or pro	bable active gassing. Probably suspic opriate action based on transformer a	cious - perfe	orm fault identification and results and company policy.		
Resampling	g Protocol	Surveillance						
AVO Resampling Increase frequency to verify gassing rates. Consider online monitoring and comprehensive engineering asso					ensive engineering assessment.			

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , μg/m, μL/L = ppm, μg/L = ppb, mN/m = dynes/cm, mm²/s = cSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. AVO Diagnostic Services assumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

DIAGNOSTIC SER	RVICES	919 FRAS	AVO DIAGNOS ER DR. UNIT 13 + E 905-632-8697 + WWW.AVODIAG	TIC SERVICES BURLINGTON, ON 905-632-8698 NOSTICS.COM	+ L7L 4X8	01-764	TEST REPORT 17789-701058-00 Page 2 of 2
ERTH (Holdings) Ir	C	Serial#: 2	25151		Mfr:	Contro	l#: 7647789
		Location: E	BEACHVILLE		kV: 27.6	Orde	r#: 701058
		Equipment: 7	RANSFORMER		kVA: 3000	Accou	nt: 110229
INGERSOLL, . N50	C2N9 CA	Compartment: N	MAIN(BOTTOM)	Year	Mf'd: 1976	Receive	;d: 06/06/2023
ATTN: MARC GAL	ECKAS	Breathing: S	SEAL	Syring	e ID: 8003346	Reporte	: 06/28/2023
PO#: POH007255		Bank: F	Phase: 3	Bottl	e ID:		
Project ID: H-23-0	01	Fluid: MIN L	JSGal: 574	Sampleo	By: CC		
Customer ID: MS1							
	Lab	Control Number:	7647789	7590319	7535750	7515375	7425750
		Date Sampled:	05/16/2023	09/29/2022	04/05/2022	11/30/2021	02/11/2021
		Order Number:	701058	686680	674258	668835	647030
		Oil Temp:	40		38	30	20
Comment:							
General Oil Qualit	y (GOQ)						
ASTM D-15331	Moisture in Oil	(mg/kg):	3	5	4	2	3
ASTM D-9711	Interfacial Tension	(mN/m):	37.62	38.02	38.19	38.27	38.75
ASTM D-9741	Acid Number	(mg KOH/g):	0.016	0.008	0.014	0.010	0.010
ASTM D-1500¹	Color Number	(ASTM):	L1.5	L1.5	L1.0	L1.0	1.5
ASTM D-15241	Visual Exam.	(Relative):	PASS	PASS	PASS	PASS	PASS
			CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT	CLR&BRIGHT
ASTM D-15241	Sediment Exam.	(Relative):	ND	ND	ND	ND	ND
ASTM D-18161	Dielectric Breakdown 2 m	nm (kV °C):	47 (23 C)	50 (23 C)	68 (22 C)	44 (23°C)	64 (23°C)
ASTM D-40521	Density @15°C	(g/mL):	0.859	0.8586	0.8597	0.8589	0.8594
GOQ Diagnostics		Moisture in Oil:	Acceptable for in-se	ervice oil (35 mg/kg	max).		
PER IEEE C57.106	6-2015 Inte	erfacial Tension:	Acceptable for in-se	ervice oil (25 mN/m	min).		
(most recent sampl	e)	Acid Number:	Acceptable for in-se	ervice oil (0.2 mg K0	DH/g max).		
	Color Nu	mber and Visual:	Diagnostic not appli	icable. Diagnostic n	ot applicable.		
	Dielectric Breakdow	n ASTM D-1816:	Acceptable for in-se	ervice oil (40 kV min	@ 2mm).		
Comment:							

End of Test Report

F.Karolt

JANET KAROLAT SUPV CHEMIST

Authorized By:

Notations: 1. Analysis is ISO/IEC 17025:2017 accredited, ANAB Accredited Certificate Number L2303 2. This test is conducted by a subcontracted laboratory. 3. Subcontracted laboratory has received ISO Standard 17025 accreditation for this test. 5. This test is conducted by AVO Diagnostic Services Laboratory other than Primary Lab. 6. AVO Diagnostic Services Laboratory has received ISO Standard 17025 accreditation for this test. 7. Imported Sample: AVO Diagnostic Services accepts no responsibility for these results; accreditation status does not apply to these results. 8. Imported Equipment 10. mg/kg , µg/m, µL/L = ppm, µg/L = ppb, mN/m = dynes/cm, mm²/s = CSt

Accreditation applies to current analysis only. The analyses, opinions or interpretations contained in this report are based upon material and information supplied by the client. AVO Diagnostic Services does not imply that the contents of the sample received by this laboratory are the same as all such material in the environment from which the sample was taken. Our test results relate only to the sample or samples tested. Any interpretations or opinions expressed represent the best judgment of AVO Diagnostic Services. Asyumes no responsibility and makes no warrantly or representation, expressed or implied as to the condition, productivity or proper operation of any equipment or other property for which this report may be used or relied upon for any reason whatsoever. This test report shall not be reproduced except in full, without written approval of the laboratory.

Appendix B - Test Report





HIGH VOLTAGE SWITCH DATA SHEET (Pg. 1 of 2)

CORPORATION		Syst	em ID 27.6kV	Device	BID TB1-L
Customer Customer Address Site Site Address	ERTH POWER 143 BELL ST INGERSO BEECHVILLE MS1 BEECHVILLE MS1	DLL	Date Job #	October 22, 202 H-23-001	23
Nameplate Data					
Switch Mounting Switch Type Manufacturer	Metal Enclosed X Load Break X S&C	Pole Air Break	Tower BIL Rating	Other	kV
Date Of Manufacture Serial #	2/95 N/A		Feeder ID Feeds To	TB1-L MAIN POWER X	(FMR
Catalog # Nom. / Max. Voltage Comments	CDT-27691692 27.6 / 29.0) <u>kV</u> (Interrupting Rating Continuous Ampacity	40000 600	A A
Lightning Arrestors Class Composition Manufacturer Catalog #	Distribution Ceramic GE 9L12PPA024S	Intermediate Polymer	X X Max. / MCOV Rating	Station	/ 19.5 kV
Comments					
Primary Fuse Holder Data Manufacturer Type Nom. / Max. Voltage Holder Max. Fuse Link Holder Catalog #	ta S&C SMU40 25.0 / 29.0 100E N/A	Prim	ary Fuse Link Data Manufacturer Type Link Size TCC # Link Catalog #	a S&C 100E SMU40 100E 153-2 N/A	A
Primary Fuse Link Spare Spare Primary Fuses Spare Location Comments	es / Location Yes X	No	# of Spares	3	
Interlock Key Interlock Interlock Type Devices Interlocked Manufacturer Comments	Yes X Elec. H.V. Switch UTILITY LOCK	No Mech L Breaker Ti	itility Lock X ans. Encl. Key Interloci	Other	
Load Side Conductor	Data				
Conductor Type Conductor Material Tape Shield Concentric Neutral Insulation Voltage Insulation Type Comments	Cable X Aluminum X Aluminum Aluminum X 28KV XLPE 90	Bus Bar Copper Copper Copper	Conductor Size / Di Conductors per Pha Bond Size / Di # of Bond Coducto # of Neutral Conducto Neutral Size / Di	m. 2/0 se 1 m. 2/0 prs 2 N/A m.	/ Phase
Recorded Rv.	MARC GALECKAS CH	IAD CARON, MARCO	KEUBER		



HIGH VOLTAGE SWITCH TEST SHEET (Pg. 2 of 2)

CORPORATION			System ID	27.6	kV	Device ID		TB1-I	_
Visual Inspection / Mechar	ical Tests								
Nameplate Condition	Satisfactory X	Not Satisfa	actory N	J/A	Corr	ments			
Insulator Condition	Satisfactory X	Not Satisfa	actory N	J/A	Corr	ments			
Ground Connections	Satisfactory X	Not Satisfa	actory N	J/A	Con	ments			
Lightning Arrestors	Satisfactory X	Not Satisfa	actory N	J/A	Corr	ments			
Arc Suppressors	Satisfactory X	Not Satisfa	actory N	J/A	Con	ments			
Key Interlock Operation	Satisfactory	Not Satisfa	actory N	J/A X	Corr	ments			
Ground Straps & Materials	Satisfactory	Not Satisfa	actory N	J/A X	Com	ments			
Switch Condition / Operation									
Switch Operation As Left	Satisfactory X	Not Satisfa	actory N	J/A	Con	iments			
Contact Surface Condition	Satisfactory X	Not Satisfa	actory N	J/A	Con	ments			
Simultaneous Closure	Satisfactory X	Not Satisfa	actory N	J/A	Com	ments			
Electrical Tests									
Earth Resistance (3-Point Tes	st)		Arc Suppress	or Con	tact Resi	istance			
Earth Resistance in Ohms.			Arc Suppress	sor Conta	act Resista	ance in Ohm	6.		
			Phase A		0.3		Ω		
Earth Resistance	ΝΑ Ω	_	Phase B		0.4		Ω		
			Phase C		0.4		Ω		
Switch Insulation Resistance			Switch / Fuse	Contac	t Resist	ance			
Resistance in Meg-Ohms after 1	minute.		Resistance in	micro-Oh	ims after f	1 minute.			
Test Voltage 1 kV	2 kV 5 kV	10 kV	Test Current	1	0A				
PhaseA	Phase B	Phase C		Pha	se A	Phase B		Phas	e C
Phase to GND MΩ	MΩ	MΩ	Contacts	150	μΩ	147	Ωμ	153	μΩ
			Fuse	866	μΩ	694	μΩ	901	μΩ
			Overall	N/A	μΩ	N/A	μΩ	N/A	μΩ
Load Side Conductor Insulati	on Resistance								
Resistance in Meg-Ohms @		after 1 minut	e Ph	nase A to	Ground				MΩ
			Ph	nase B to	Ground				MΩ
			Ph	ase C to	Ground				MΩ
Lightning Arrestor Insulation	Resistance								
Resistance in Meg-Ohms @		after 1 minut	e Pr	nase A to	Ground				MΩ
			Ph	nase B to	Ground				MΩ
			Ph	nase C to	Ground				MΩ

Comments / Observations

Test Instrument(s)	Manufacturer / Model	Megger	Ductor		
	Serial #	MIT1025	DLRO-10		

Tested By: MARC GALECKAS, CHAD CARON, MARCO KEUBER



HIGH VOLTAGE SWITCH DATA SHEET (Pg. 1 of 2)

CORPORATION		System	1D 4.160k	/	Device ID	BEA1F1
Customer	ERTH POWER		Date	Octobe	r 22. 2023	
Customer Address	143 BELL ST INGERSOLL		Job #	H-23-00)1	
Site	BEECHVILLE MS1					
Site Address	BEECHVILLE MS1					
Nameplate Data						
Switch Mounting	Metal Enclosed X	Pole	Tower		Other	
Switch Type	Load Break X	Air Break			Other	
Manufacturer	S&C		BIL Rating	95		kV
Date Of Manufacture	06/17	;	Feeder ID	BEA1F	1	
Serial #	173774		Feeds To	BE42 S	OLID DISCO	NNECT
Catalog #		Ir	terrupting Rating	36400		Α
Nom. / Max. Voltage	14.4 / 17.0	kV Con	tinuous Ampacity	600		Α
Comments						
Lightning Arrestors			٦	.		
Class	Distribution	Intermediate	_	Stati	on	
Composition		Polymer			,	1.37
Manufacturer		IVIa	IX. / MCOV Rating		1	KV
Catalog #	NA					
Protective Device Dat						
Primary Euco Holdor Da	to	Primon	Euso Link Dat			
Manufacturer	58.C	Filinary	Manufacturer	1 580		
Type	SMU20		Type	SMU20		
Nom / Max Voltage		kV	Link Size	200F		Δ
Holder Max. Fuse Link	200E		TCC #	153-2		
Holder Catalog #	N/A		Link Catalog #	N/A		
Primary Fuse Link Spare	es / Location		0			
Spare Primary Fuses	Yes X	No	# of Spares	3		
Spare Location						
Comments	DOOR					
Interlock						
Koulstarlaak						
Devices Interlock Type	Elec. Med	kor Trop		Oth		
Manufacturer				. #		
Comments	UTIENT LOCK		Rey Interiock	. #		
Load Side Conductor	Data					
Conductor Type	Cable X Bus Bar	C	onductor Size / Dir	m. 2/0		
Conductor Material	Aluminum X Copper	C	onductors per Pha	se 1		/ Phase
Tape Shield	Aluminum Copper		Bond Size / Dir	m. 2/0		
Concentric Neutral	Aluminum Copper		# of Bond Coducto	ors 2		
Insulation Voltage	28KV	# o	f Neutral Conducto	rs N/A		
Insulation Type	XLPE 90		Neutral Size / Dir	n		
Comments						
Described						
Recorded By:	MARC GALECKAS, CHAD CAR	ON, MARCO KE	UBER			



HIGH VOLTAGE SWITCH TEST SHEET (Pg. 2 of 2)

CORPORATION			System ID			Device II	C	BEA1	-1
Visual Inspection / Mechai	nical Tests								
Nameplate Condition	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Insulator Condition	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Ground Connections	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Lightning Arrestors	Satisfactory	Not Satisf	actory N	J/A X	Con	nments			
Arc Suppressors	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Key Interlock Operation	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Ground Straps & Materials	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Switch Condition / Operation									
Switch Operation As Left	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Contact Surface Condition	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Simultaneous Closure	Satisfactory X	Not Satisf	actory N	J/A	Con	nments			
Electrical Tests									
Earth Resistance (3-Point Te	st)		Arc Suppress	or Co	ntact Res	istance			
Earth Resistance in Ohms.			Arc Suppres	sor Cor	ntact Resist	ance in Ohm	s.		
			Phase A		NA		Ω	:	
Earth Resistance	NA	Ω	Phase B		NA		Ω	:	
			Phase C		NA		Ω	:	
Switch Insulation Resistance	•		Switch / Fuse	Conta	act Resist	ance			
Resistance in Meg-Ohms after 1	minute.		Resistance in	micro-C	Ohms after	1 minute.			
Test Voltage 1 kV	2 kV 5 kV	10 kV	Test Current		10A				
Phase A	Phase B	Phase C		PI	nase A	Phase B		Phas	еC
Phase to GND 9000 MC	Ω 11200 ΜΩ	10400 MΩ	Contacts	109	θ μΩ	101	μΩ	111	μΩ
			Fuse	370	6 μΩ	390	μΩ	409	μΩ
			Overall	N//	Α μΩ	N/A	μΩ	N/A	μΩ
Load Side Conductor Insulat	ion Resistance								
Resistance in Meg-Ohms @		DC after 1 minut	te Pr	nase A	to Ground				MΩ
			Pł	nase B	to Ground				MΩ
			Pr	nase C	to Ground				MΩ
Lightning Arrestor Insulation	Resistance								
Resistance in Meg-Ohms @		DC after 1 minut	te Pr	nase A	to Ground				MΩ
			Pł	nase B	to Ground				MΩ
			Pł	nase C	to Ground				MΩ

Comments / Observations DAMP WELL TESTING

Test Instrument(s)	Manufacturer / Model	Megger	Ductor		
	Serial #	MIT1025	DLRO-10		

Tested By: MARC GALECKAS, CHAD CARON, MARCO KEUBER



TRANSFORMER DATA SHEET (Pg. 1 of 4)

System ID 27.6kV 38M44 Device ID MAIN POWER TX

	JRPORATION				System ID	27.0KV_30	IV144 L		MAIN	FOWER	
	Custome	r ERTH POWER				Date	October	22, 2023			
	Customer Addres	143 BELL ST INGE	RSOLL			Job #	H-23-001	, I			
	Site	BEECHVILLE MS1				000 //					
	Site Addres	BEECHVILLE MS1									
Namep	olate Data										
	Transformer Class	S Unit Padmount	X Padr	nount	Station			Other			
Т	ransformer Cooling) ONAN	X	ONAF	LNAN	DF	۲Y	Other			
Bushir	ng Configuration	Dead Front	Тор	- Тор 🛛 🗙	Top - Side	Side - Si	de	Other			
									r		
	Manufacture	PORTER			Co	re & Windings	8700		kg	lb	X
D	ate of Manufacture	e <u>1976</u>			Ta	anks & Fittings	6260		kg	lb) X
	Serial	[‡] 22515-1			C	oolant Volume	574		L	Gal	X
KVA	/ Prov. KVA Rating	3000		KVA	C	coolant Weight	4940		kg	lb	X
	Primary Voltage	e <u>276000</u>		V		Total Weight	19900		kg	Ib	X
	Primary Ampacit	/ 66.1		Α	Ten	nperature Rise	65		°C	X °F	
	Secondary Voltage	e 4160/2400		V		HV BIL Rating	200		kV		
S	econdary Ampacit	/ <u>NA</u>		Α		LV BIL Rating	75		kV		
H	V Winding Materia	NA			Perce	ent Impedance	5.65	% ONAN	X	ONAF	
L	V Winding Materia	NA NA			Tan	nper Resistant	t	YES	X	NO	'
С	SA Specification(s) <u>NA</u>			Trans	sformer Colour	GREY				
	Comment	S									
Visual	Inspection										
N	amentate Condition	Satisfactory X	Not	Satisfacto	ny N	/A	Comments				
Far	n / Pump Operation	Satisfactory	Not	Satisfacto	ny N		Comments				
G	round Connection	Satisfactory X	Not	Satisfacto	ny N	/A	Comments				
Liai	uid Levels In Tank	s Satisfactory X	Not	Satisfacto	rv N	/A	Comments				
	Interlock Operation	n Satisfactory	Not	Satisfacto	rv N		Comments				
Temp	. Gauge Operation	Satisfactory X	Not	Satisfacto	rv N	/A	Comments				
	0		1								
Co	olant Temperature	e 35	°C	X °F	Ma	ax. Coolant Te	mperature	50	°C	X °F	:
	Comment	6									
0:1.0											
OII Con	servator				0				. [. —
	Oil Conservato	or Yes			Conse	ervator volume			L.	Gai	
	Silica Gel Breathe	er Yes		Denter	Bre				L	Gai	·
	Silica Gel Color		ad	Replace	ed	N/A					
	Comment										
Tap Cha	anger Data		T		Vector Diag	gram:					
Р	osition /	Tap Voltages (V)	As	As	[▲ ^{H2}	x2	Xo		٦	
De	signation		Found	Left				\searrow	_		
1/A	105.00%	27600	v	v				/	33		
2/8	102.50%	20910	X	X		Н1	нз	Xı		1	
3/6	07 50%	20220					DeltaW	ye3			
4/D	97.50%	20030			Di.	m () / a at - ::		Casa: da	V/c - '		٦
3/E	95.00%				Prima	ry vector 2	(Secondary	vect	or X	
	Comments	•									
	Tested By	MARC GALECKAS	, CHAD C	ARON, MA		R					

TRANSFORMER DATA SHEET (Pg. 2 of 4)

			Curatam ID	07.01.)/ 0014/		
CORPORATION			System ID	27.6KV_38M44		MAIN POWER IX
Neutral Grounding Rea	sistor (NGR)					
NGR Present	Yes No					
Manufacturer				NGR Serial #		
NGR Voltage		V	Max	kimum Current		Α
NGR Resistance		Ω		NGR Location		
Comments						
Transformer Lightning	g Arrestors					
Class	Distribution	Interm	ediate X		Station	
Composition	Ceramic	Po	olymer X			
Manufacturer	GE		Max.	MCOV Rating	24.0 /	19.5 kV
Catalog #	9L12PPA024S			0_		
Comments						
Interlock						
Key Interlock	Yes	No				
Interlock Type	Elec.	Mech.	Utility Lo	ck		
Devices Interlocked	H.V. Switch	Breaker	Trans. Er	ncl.	Other	
Manufacturer				Key Interlock #		
Comments						
Fans						
# of Fans				Fan Voltage		
Fan Size				Frame Size		
Horsepower						
Comments						
Transformer Load Side	e Conductor Data					
Conductor Type	Cable	Bus Bar	Cond	uctor Size / Dim.		
Conductor Material	Aluminum	Copper	Cond	uctors per Phase		/ Phase
Tape Shield	Aluminum	Copper	1	Bond Size / Dim.		
Concentric Neutral	Aluminum	Copper	# of E	Sond Conductors		
Insulation Voltage			# of Ne	utral Conductors		
Insulation Type			Ne	eutral Size / Dim.		
Comments						

Tested By: MARC GALECKAS, CHAD CARON, MARCO KEUBER

ERTH



TRANSFORMER TEST SHEET (Pg. 3 of 4)

System ID 27.6kV_38M44 Device ID MAIN POWER TX

Electric	al Tests																
Turn Ra	tio Test	Test Vo	ltage: A	utoma	tic	X	Oth	ier	v	_							
Tap F	Position /	Tap Voltage	Calc	ulated		Н	То	Н		H 2	То	Н		Н	То	Н	
Desi	gnation	V	Ra	atio		Х	То	Х		X 2	То	Х		Х	То	Х	
1 / A	105.00%	27600															
2 / B	102.50%	26910					11.2	212			11.2	11			11.2	13	
3 / C	100.00%	26220															
4 / D	97.50%	25530															
5 / E	95.00%	24840															
						Excita Currre	tion ent	Perce Devia	ent tion	Excita Currr	tion ent	Perc Devia	ent ation	Excit Curi	ation rent	Percer Deviati	nt on
		Tap Posi	tion As F	ound	2	3.200) mA	0.14	10 %	3.100	mA	0.1	20 %	2.7	00 mA	0.150) %
		Tap Posi	tion As L	eft			mA		%		mA		%		mA		%
Primary	Winding F	Resistance						Secon	dary	v Windiı	ng Re	sistai	nce				
Re	sistance in o	hms at	5 A	after 1	min	ute	_	R	esista	ance in m	illi-ohr	ns at	5	Α	after	1 minut	е
H0 - H1		Ω	H1 - H2		1.3	87 Ω		X0 - X	1	10.122	mΩ	2	X1 - X	2	19.7	81 mΩ	
H0 - H2		Ω	H2 - H3		1.3	72 Ω		X0 - X	2	10.056	mΩ	2	X2 - X	3	19.8	57 mΩ	
H0 - H3		Ω	H3 - H1		1.3	74 Ω		X0 - X	3	10.064	mΩ	2	X3 - X	.1	19.9	10 mΩ	
	Stabiliz	ation Time >			Mir	nute			St	tabilizatio	on Tim	e >			Minu	ite	
					•							•					
Capacit	ance Test		1														
	-		Low -	Ground	1 _	Low	- Gua	ard	UST	(High - L	.ow)	Hig	jh - Gua	ard _	High	- Groun	d_
	Capacitance	in pico-farads			pF			pF			pF			pF			pF
	Uncorr	ected D.F. (%)			%			%			%			<u>%</u>			%
	Correcte				70			%			%			70			70
	Temp. Cor	rection Factor															
Lightnin	ng Arrestor	r Insulation F	Resistand	ce													
R	esistance in	meg-ohms @		V	DC	after 1 i	minute	Э		Phase A	to Gr	ound				Ν	NΩ
										Phase E	to Gr	ound				Ν	NΩ
		TE	STED WIT	H TRA	NS	FORME	R			Phase C	to Gr	ound				Ν	NΩ
Second	ary Condu	ctor Insulatio	on Resis	tance													
R	esistance in	meg-ohms @		V	DC	after 1 i	ninute	е									
	Phas	e A to Ground					MΩ]	F	Phase A	to Pha	ise B				Ν	IΩ
	Phas	e B to Ground					MΩ	-	F	Phase B	to Pha	se C				N	NΩ
	Phas	e C to Ground					MΩ	-	F	Phase C	to Pha	ise A				Ν	lΩ
Comme	ents / Obs	ervations															_

Test Instrument(s)	Manufacturer / Model	Ratio	Winding	Cap Bridge	Megger	
	Serial #	TR-MARK III 250	WR-14	CB-100	MIT1025	
Tested By: N	IARC GALECKAS, CHA	D CARON, MARC	O KEUBER			

CORPORATION

ERTH

TRANSFORMER TEST SHEET (Pg. 4 of 4)

System ID 27.6kV_38M44 Device ID MAIN POWER TX

Dielectric Absorption Test (Insulation Resistance)

	High to L	ow & Gnd	Low to H	igh & Gnd	High & Lo	ow to Gnd
Time	Uncorrected	Corrected	Uncorrected	Corrected	Uncorrected	Corrected
15 sec	2100 MΩ	5250 MΩ	7190 MΩ	17975 MΩ	4000 MΩ	10000 MΩ
30 sec	3000 MΩ	7500 MΩ	9000 MΩ	22500 MΩ	4620 MΩ	11550 MΩ
45 sec	3160 MΩ	7900 MΩ	12330 MΩ	30825 MΩ	5100 MΩ	12750 MΩ
1 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
2 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
3 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
4 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
5 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
6 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
7 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
8 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
9 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
10 min	3400 MΩ	8500 MΩ	13570 MΩ	33925 MΩ	5790 MΩ	14475 MΩ
Test Voltage	10000	V	1000	V	1000	V
Multiplier		1		1		1
Polarization Index	1.	00	1.	.00	1.	.00
TCC 2.50		Insulat	ion Resistance F	Readings Correcte	d to 20 °C	

Insulation Resistance

Core Ground Insulation Resistance Resistance in meg-ohms after 1 minute. Resistance in meg-ohms after 1 minute. V 8500 10000 Core Ground Accessible High to Low & Ground ΜΩ @ Yes No 33925 ΜΩ @ ٧ Test Voltage Low to High & Ground 1000 ٧ 14475 1000 V High & Low to Ground ΜΩ @ Core Ground Resistance MΩ



Test Instrument(s)	Manufacturer / Model	Ratio	Winding	Cap Bridge	Megger	
	Serial #	TR-MARK III 250	WR-14	CB-100	MIT1025	
Commenter						

Comments:

Tested By: MARC GALECKAS, CHAD CARON, MARCO KEUBER

$\mathbf{F}\mathbf{K}$ $\mathbf{I}\mathbf{H}$			INS	ULATION RES	SISTANC
			7	EST SHEET (Pg. 1 of 1
CORPORATION		System ID	4160V	Device ID	BEA1F1
Customer	ERTH POWER		Date	22-Oct-23	
Customer Address	143 BELL ST INGERSOLL		Job #	H-23-001	
Site	BEECHVILLE MS1				
Site Address	BEECHVILLE MS1				
Device Name	TRANSFORMER SECONDARY		Location BEE	CHVILLE TX	
Description	15kV FEEDER CABLE FROM TX	SECONDARY TO S	S&C ELECTRIC	C SWITCH BEA1F1	
Test Voltage	500 V 1000 V	2500 V 5	000 V	10000 V X	
AΦ - Gnd	105000	MΩ	ΑΦ - ΒΦ		MΩ
BΦ - Gnd	88000	MΩ	ΒΦ - CΦ		MΩ
CΦ - Gnd	93000	ΜΩ	CΦ - ΑΦ		MΩ
Comments					
Device Name	SWITCH FEEDER		Location BEE		
Description	15kV FEEDER CABLE FROM S8		CH BE42 SOL	ID DISCONNECT	
Test Voltage	500 V 1000 V	2500 V 5	000 V	10000 V X	
AΦ - Gnd	13000	MΩ	ΑΦ - ΒΦ		MΩ
BΦ - Gnd	17000	MΩ	ΒΦ - CΦ		MΩ
CΦ - Gnd	15400	MΩ	CΦ - ΑΦ		MΩ
Comments					
Device Name			Location		
Description					
Test Voltage	500 V 1000 V	2500 V 5	000 V	10000 V	
Test Voltage	500 V 1000 V	2500 V5	000 V	10000 V	МО
Test Voltage ΑΦ - Gnd ΒΦ - Gnd	500 V 1000 V	2500 ∨5 <u>ΜΩ</u> ΜΩ	000 V ΑΦ - ΒΦ ΒΦ - CΦ	10000 V	<u>ΜΩ</u>
Test Voltage ΑΦ - Gnd ΒΦ - Gnd CΦ - Gnd	500 V 1000 V	2500 V 5 <u>ΜΩ</u> <u>ΜΩ</u>	000 V ΑΦ - ΒΦ ΒΦ - CΦ CΦ - ΑΦ	10000 V	<u>ΜΩ</u> ΜΩ
Test Voltage ΑΦ - Gnd ΒΦ - Gnd CΦ - Gnd Comments	500 V 1000 V	2500 V 5 <u>ΜΩ</u> <u>ΜΩ</u>	000 V ΑΦ - ΒΦ ΒΦ - CΦ CΦ - ΑΦ	10000 V	ΜΩ ΜΩ ΜΩ
Test Voltage ΑΦ - Gnd ΒΦ - Gnd CΦ - Gnd Comments	500 V 1000 V	2500 V 5 <u>ΜΩ</u> <u>ΜΩ</u>	000 V ΑΦ - ΒΦ ΒΦ - CΦ CΦ - ΑΦ	10000 V	ΜΩ ΜΩ ΜΩ
Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd Comments Device Name Description	500 V 1000 V	2500 V 5 <u>ΜΩ</u> <u>ΜΩ</u>	000 V ΑΦ - ΒΦ ΒΦ - CΦ CΦ - ΑΦ Location	10000 V	ΜΩ ΜΩ
Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd Comments Device Name Description Test Voltage	500 V 1000 V	2500 V5	000 V AΦ - BΦ BΦ - CΦ CΦ - AΦ Location 000 V	10000 V	<u>ΜΩ</u> ΜΩ
Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd Comments Device Name Description Test Voltage AΦ - Gnd	500 V 1000 V	2500 V5 <u>MΩ</u> <u>MΩ</u> 2500 V5 <u>MΩ</u>	000 V AΦ - BΦ BΦ - CΦ CΦ - AΦ Location 000 V AΦ - BΦ	10000 V	<u>ΜΩ</u> <u>ΜΩ</u>
Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd Comments Device Name Description Test Voltage AΦ - Gnd BΦ - Gnd	500 V 1000 V	2500 V5 <u>MΩ</u> <u>MΩ</u> <u>MΩ</u> 2500 V5 <u>MΩ</u> <u>MΩ</u>	000 V AΦ - BΦ CΦ - AΦ Location 000 V AΦ - BΦ BΦ - CΦ	10000 V	<u>ΜΩ</u> ΜΩ
Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd Comments Device Name Description Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd	500 V 1000 V	2500 V MΩ MΩ MΩ 2500 V 2500 V 5 MΩ MΩ MΩ MΩ	$ \begin{array}{c c} A \Phi & - B \Phi \\ B \Phi & - C \Phi \\ C \Phi & - A \Phi \\ \end{array} $ Location $ \begin{array}{c} 000 \lor \\ A \Phi & - B \Phi \\ B \Phi & - C \Phi \\ C \Phi & - A \Phi \\ \end{array} $	10000 V	<u>ΜΩ</u> ΜΩ
Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd Comments Device Name Description Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd	500 V 1000 V	2500 V MΩ MΩ MΩ 2500 V 2500 V 5 MΩ MΩ MΩ MΩ	$ \begin{array}{c} A \Phi & - B \Phi \\ B \Phi & - C \Phi \\ C \Phi & - A \Phi \\ \end{array} $ $ \begin{array}{c} Location \\ 000 V \\ A \Phi & - B \Phi \\ B \Phi & - C \Phi \\ C \Phi & - A \Phi \\ \end{array} $	10000 V	<u>ΜΩ</u> ΜΩ ΜΩ ΜΩ ΜΩ
Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd Comments Device Name Description Test Voltage AΦ - Gnd BΦ - Gnd CΦ - Gnd CΦ - Gnd CΦ - Gnd	500 V	2500 V5 <u>MΩ</u> <u>MΩ</u> 2500 V5 <u>MΩ</u> <u>MΩ</u> <u>MΩ</u> <u>MΩ</u> <u>MΩ</u> <u>MΩ</u>	$ \begin{array}{c} A \Phi & - B \Phi \\ B \Phi & - C \Phi \\ C \Phi & - A \Phi \\ Location \\ 000 V \\ A \Phi & - B \Phi \\ B \Phi & - C \Phi \\ C \Phi & - A \Phi \\ \\ A \Phi & - A \Phi \\ \\ B \Phi & - A \Phi \\ \\ A \Phi & - A \Phi \\ \\ \\ A \Phi & - A \Phi \\ $	10000 V	<u>ΜΩ</u> ΜΩ ΜΩ ΜΩ ΜΩ ΜΩ


APPENDIX J. Infrared Inspection Report



www.boldstarinfrared.com



Infrared Thermographic Survey

- Electrical Distribution System -

ERTH Power

Date:

June 6th, 7th and 8th, 2023

Mitchell Dublin Clinton Goderich Tavistock Thamesford Embro





Infrared Report Summary

Purpose: Infrared inspection to identify thermal anomaly conditions on electrical distribution equipment that suggest an unwanted condition exists and repairs are required.
Method: Complete infrared inspection of selected ERTH Power distribution system. Save infrared images of all noted anomaly conditions. Detail the findings of the scanning in a report.
Conditions: Equipment operating under normal daytime loading conditions.
Inspection Equipment: FLIR model T460 thermal imaging systems, serial # 62113652.

Observations

Note: Boldstar Infrared Services Inc. is in no way responsible for any expenses resulting in actions or repair of reported anomalies. This report is not a warranty or guarantee of any equipment condition or reliability.

Please see report for details on all noted suspect conditions.

All of the report infrared images are classified as follows:

HIGH Priority: Component temperature over 50 Celsius rise over ambient.
Plan and execute repairs as soon as possible, within the next few days. Do not ignore.
MEDIUM Priority: Component temperature 25 to 50 Celsius rise over ambient.
Plan and execute repairs at the next opportunity, within the next few weeks. Do not ignore.
LOW Priority: Component temperature below 25 Celsius rise over ambient.
Plan and execute repairs at the next convenient opportunity. Do not ignore.
No Problems Noted (N/A): No anomaly conditions noted. Condition good.

All reported condition should be investigated further as soon as possible to verify the reported condition. Use all safety procedures. Electrical hazards exist.

CONTENTS OF REPORT

Priority: *H*= *High M*= *Medium L*= *Low N*/*A*= *Not Applicable*

Equipment	Condition	Max. Temp.	Priority	Page
Pole ET9235 (Clinton)	Heating switch	54.5°C	М	4
Pole 10815 (Goderich)	Heating connection	46.9°C	М	5
Pole ET8947 (Dublin)	No problem noted	-	N/A	6
MS1 (Clinton)	No problem noted	-	N/A	7
Pole ET9358, MS1 (Clinton)	No problem noted	-	N/A	8
Pole 11907, MS2 (Goderich)	No problem noted	-	N/A	9
31M4 (Goderich)	No problem noted	-	N/A	10
M3, Pole 11871 (Goderich)	No problem noted	-	N/A	11
MS3 (Goderich)	No problem noted	-	N/A	12
MS1 Sub-Station (Tavistock)	No problem noted	-	N/A	13
MS1 (Tavistock)	No problem noted	-	N/A	14
Pole ET11645 (Tavistock)	No problem noted	-	N/A	15
Pole ET2331 (Tavistock)	No problem noted	-	N/A	16
Pole ET2141, E620 (Embro)	No problem noted	-	N/A	17
Pole ET2649, E500 (Embro)	No problem noted	-	N/A	18
Pole ET4499 (Tavistock)	No problem noted	-	N/A	19



page 3 of 19



INFORMATION:

Infrared image of in-line switches (332). At pole ET9235.

Located at the intersection of Orange Street and Rattenbury Street in Clinton. Elevated heating was noted at the indicated location on the road-side switch (at arrow in photo). See IR information chart above for maximum temperature inside area box (AR01).

PRIORITY:

ANOMALY:

High

Heating switch

Medium

Low

Boldster

page 4 of 19

Identificatio	n:		DATE
Pole 10815 (Go	oderich)		2023-06-07
Description:	Riser Pole		
INFRARED	IMAGE	PHO	ОТО
AR01: 46.9°C		25.4°C	rature rise: 33.87 °C mbient)
IR information	Value		
Date of creation	2023-06-07	Status:	
Time of creation	7:50:19 AM	Deneined Detai	
Object parameter	Value	Repaired Date:	
Ambient temperature	13.0°C	Notes:	
Label	Value		
$\Delta R01 \cdot max$	46.9°C		

INFORMATION:

Infrared image of riser pole 10815 for the 259 switch feeder. Located at 396 Eldon Street in Goderich.

Elevated heating was noted at the indicated field-side ampact (at arrow in photo). See IR information chart above for maximum temperature inside area box (AR01).

PRIORITY:

High

Medium

Low

ANOMALY: Heating connection



Pole ET8947 (Dublin)

2023-06-06

DATE

Description: Metering Point

INFRARED IMAGE 48.5°C 40 20 0 -20 -40 -40.0°C IR information Value Date of creation 2023-06-06 Time of creation 9:14:17 AM **Object parameter** Value



INFORMATION:

Infrared image of a metering point. On pole ET8947. Located in Dublin.

18.0°C

No problem was noted.

Ambient temperature

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



MS1 (Clinton)

Description: Riser Pole

2023-06-06

ΡΗΟΤΟ

DATE



20.0°C



INFORMATION:

Infrared image of riser switches. Located at MS1 in Clinton.

No problem was noted.

Ambient temperature

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 7 of 19

Pole ET9358, MS1 (Clinton)

2023-06-06

DATE

Description: Switches

INFRARED IMAGE





INFORMATION:

Infrared image of riser switches 505 & 339. On pole ET9358. Located at MS1 in Clinton.

2023-06-06 10:52:44 AM

Value

20.0°C

No problem was noted.

IR information

Date of creation

Time of creation **Object parameter**

Ambient temperature

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		





INFORMATION:

Infrared image of riser pole 11907. Located at MS2 in Goderich.

No problem was noted.

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 9 of 19

Identification:	DATE
31M4 (Goderich)	2023-06-07

Description: Metering Point



INFORMATION:

Infrared image of metering point for the 31M4. Located at the Goderich TS.

No problem was noted.

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 10 of 19

Identificatior	1:			DATE
M3, Pole 11871	(Goderich)			2023-06-07
Description:	Switch			
INFRARED II	MAGE		PHOT	0
		31.6°C		
IR information	Value			
Date of creation	2023-06-07			
Time of creation	7:14:53 AM			
Object parameter	Value			
Ambient temperature	10.0°C			

INFORMATION:

Infrared image of the M3 switches. On pole 11871. Located at the Goderich TS.

No problem was noted.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



DATE

2023-06-07

Identification:

MS3 (Goderich)

Description: Sub-Station



INFORMATION:

Infrared image of the MS3 substation switches. Located in Goderich.

No problem was noted.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



MS1 Sub-Station (Tavistock)

2023-06-07

DATE

Description: Sub-Station



2023-06-07

Value 21.0°C

11:57:47 AM



INFORMATION:

Infrared image of the MS1 substation switches. Located at 17 Decew Street in Tavistock.

No problem was noted.

Date of creation

Time of creation

Object parameter

Ambient temperature

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



Identification:	DATE
MS1 (Tavistock)	2023-06-07

Description: Riser Pole





INFORMATION:

Infrared image of the MS1 riser pole.

Located at 17 Decew Street in Tavistock.

No problem was noted.

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 14 of 19



INFORMATION:

Infrared image of the PME 15170S metering point. Located on pole ET11645 in Tavistock.

No problem was noted.

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 15 of 19



40

20

0

-20

-35.4°C

INFORMATION:

Infrared image of the EZT68 metering point. Located on pole ET2331 in Tavistock.

Value

Value

21.0°C

2023-06-07

1:35:16 PM

No problem was noted.

IR information

Date of creation

Time of creation

Object parameter

Ambient temperature

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



Pole ET2141, E620 (Embro)

DATE 2023-06-08

Description: Transformer & Switch



INFORMATION:

Infrared image of the E620 transformer. Located on pole ET2141 in Embro.

No problem was noted.

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 17 of 19

Pole ET2649, E500 (Embro)

DATE 2023-06-08

Description: Transformer & Switch



INFORMATION:

Infrared image of the E500 transformer.

Located on pole ET2649 at 375745 37th Line in Embro.

9:52:00 AM

Value

22.0°C

No problem was noted.

Time of creation

Object parameter

Ambient temperature

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 18 of 19

Identification:	DATE
Pole ET4499 (Tavistock)	2023-06-08

Description: Metering Point





INFORMATION:

Infrared image of a metering point.

Located on pole ET4488 on Highway 2 in Thamesford.

No problem was noted.

This image is provided to show the typical thermal patterns that were noted on the inspected equipment that did not indicate any suspect conditions. Normal heating was noted only. No action is required.

PRIORITY:	High	Medium	Low
ANOMALY:	No problem noted		



page 19 of 19



APPENDIX K. 2025 Project Narratives



	2025 - Project Assessment Form									
ERTH Project Name ALL-SRVI			/RES-Residential Connections				Mun Cost Proje	icipality Category ect Type	All Capital New Res	idential
			G	eneral Inf	formatior	ı				
Dural and D		This are				- 		f		
Investme	escription nt Category	This project represents the cost associated with the connection of new residential customers. This includes modifications and/or expansions (subdivisions) to the existing distribution system to accommodate the connection of new customers. System Access								
Capital In	vestment									
					Historical	Expenditures			Average	
			2018	2019	2020	2021	2022	2023	(2018 to 2023)	
	Posidontial	Gross (\$)	\$406,776	\$798,932	\$753,124	\$663,717	\$1,144,173	\$339 <i>,</i> 858	\$684,430	
	Connections	Contributions (\$)	-\$23,382	\$79,463	\$57,670	\$81,477	\$120,389	\$209,472	\$87,515	
		Net (\$)	\$430,158	\$719,469	\$695,454	\$582,240	\$1,023,784	\$130,386	\$596,915	
					Forecast F	xpenditures				
			2024 (Bridge)	2025	2026	2027	2028	2029	Average (2025 to 2029)	
		Gross (\$)	\$266,770	\$600,232	\$612,237	\$624,481	\$636,971	\$649,710	\$624,726	
	Residential	Contributions (\$)	\$66,770	\$150,232	\$153,237	\$156,301	\$159,427	\$162,616	\$156,363	
	connections	Net (\$)	\$200,000	\$450,000	\$459,000	\$468,180	\$477,544	\$487,094	\$468,364	
Expected Expected Risks and	Customer Load (if available)Varies - Customer DrivenExpected Project TimingStart Date End DateQ1 Q4Expected Expenditure TimingQ1 Q2 Q3 Q425% 25% 25%Risks and MitigationResidential service connections are a common practice throughout any given year and FRTH					dERTH				
Comparat	Power has well developed standards and guidelines to guide all stages of design, construction and administration. Risks associated with residential connections are primarily a result of ensuring that all procedures and requirements are followed by the utility and the customers. These risks are mitigated through frequent communication between both parties.Comparative InformationSee Capital investment tables above for historical comparisons					truction t of tomers.				
REG Inves	EG Investment This project is not associated with a REG investment									
Leave to	Leave to Construct Approval This project does not require Leave to Construct approval under section 92 of the OEB Action				3 Act					
		Evalu	ation Crite	eria & Info	ormation	Requiren	nents			
Efficiency Project D	Efficiency, Customer Value & ReliabilityProject DriversResidential service connections are mandatory service requirements and are driven by customer requests and timelines.					у				
Investme	nt Priority	All custo	omer servic	e connecti	ons are to	p priority a	and are dep	pendent on	customer tim	elines.
1			ALL-SRVRI	ES-Residen	tial Conne	ctions				

Project Alternatives	Residential service connections follow a standardized process in line with ERTH Powers Conditions of Service. Depending on the situation there may or may not be alternative solutions with regards to the service connection. (i.e. overhead vs. underground, meter base location etc.) Each connection is evaluated by ERTH Power staff and a suitable connection is made with input from the customer in line with developed standards.
Operational Benefits	New customer service connections do not look to address specific operational issues however are constructed to current standards which will provide incremental operational benefits moving forward. (ex. accessible meter base location)
Reliability Benefits	New customer service connections do not look to address specific reliability issues however are constructed to current standards which will provide incremental reliability benefits moving forward. (ex. underground secondary installed in duct on customer property)
Customer Benefits	Not applicable
Safety	New customer service connections do not look to address specific safety issues however are constructed to current standards which will provide incremental safety benefits moving forward.
Cyber-Security, Privacy	Not applicable
Co-ordination, Interoperability	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	Not applicable
Environmental Benefits	Not applicable
	Category Specific Requirements
System Access Project	The factors affecting the timing of residential service connections are primarily driven by timelines set out by the customer and are a top priority.
	Customer preferences and input are always taken into consideration during the design of a new connection, however all connections are made ensuring that current standard practices are followed in a consistent manner.
	The final cost of the project as a whole is driven by customer requests and can vary year to year. On a more granular level each connection is evaluated and the cost of the connection can vary depending on the size & type of service along with existing conditions.
	The connection of new residential customers is completed through well established procedures that have continuously improved over time to provide cost efficiency to both ERTH Power and customers. Any material used by ERTH Power is purchased through a buying group of multiple local utilities that aims to standardize and minimize costs.
	On a project by project basis ERTH Power evaluates the connection requirements to see if other planning objectives can be accomplished. Examples of this include expansions to service new developments from the 28kV system or service requirements to leverage future conditions.
2	ALL-SRVRES-Residential Connections

Residential service connections follow a standardized process in line with ERTH Powers Conditions of Service. Depending on the situation there may or may not be alternative solutions with regards to the service connection. (i.e. overhead vs. underground, meter base location etc.) Each connection is evaluated by ERTH Power staff and a suitable connection is made with input from the customer in line with developed standards.

When a capital contribution is applicable it is calculated in accordance with the methodology included in the DSC and is completed on a project by project basis. These contributions vary on a year by year basis depending on demand and historical trends are used to budget.

Typically individual residential connections and subdivision developments have a very minimal impact to the distributions system. If a connection drives a substantial investment to the distribution system a separate project will be created and evaluated.



2025 - Project Assessment Form									
		<u></u>	10/00/10	<u>,56551116111</u>		N. de um in	te el te c	A 11	
EKIH						All			
Project Name	ALL-SRVC	I-Commer	cial & Indu	strial Conn	lections	Cost C	Lategory	Capital	
POWER						Projec	ct Type	New C&I	
		G	eneral In	formatior	า				
Project Description	This proje	ect renrese	nts the co	st associate	ed with the	e connectio	on of new c	ommercial an	Ч
	industria	l customer	s This inclu	ides modif	fications ar	nd/or expa	nsions to th	e existing dist	ribution
	system to		date the c	onnection	of new cur	stomers			
	eyeten t				0				
Investment Category	System A	ccess							
	- /								
Capital Investment									
				Historical I	Expenditures			Average	
		2018	2019	2020	2021	2022	2023	(2018 to 2023)	
	Gross (\$)	\$544,073	\$687,835	\$328,555	\$531,235	\$788,841	\$821,408	\$616,991	
C&I Connections	Contributions (\$)	\$260,383	\$539,664	\$225,952	\$418,314	\$591,287	\$602,876	\$439,746	
	Net (\$)	\$283,690	\$148,171	\$102,603	\$112,921	\$197 <i>,</i> 554	\$218,532	\$177,245	
				Forecast F	xpenditures				
		2024	2025	2020	2027	2029	2020	Average	
		(Bridge)	2025	2020	2027	2028	2029	(2023 (0 2023)	
	Gross (\$)	\$370,308	\$679,325	\$692,912	\$706,770	\$720,906	\$735,324	\$707,047	
C&I Connections	Net (\$)	\$270,308	\$495,877 \$183,449	\$505,794 \$187.118	\$515,910	\$526,228 \$194.677	\$530,753 \$198 571	\$516,112	
	Net (5)	\$100,000	J103,443	J107,110	\$190,800	\$194,077	Ş198,971	\$190,935	
Customer Information	Number	of Custome	er Attachm	ents V	Varies - Cu	stomer Dri	ven		
	Custome	r Load (if a	vailahle)	N N	Varies - Cu	stomer Dri	ven		
	custome		valiable)				ven -		
Expected Project Timing	Start Dat	ρ		(01				
	End Date	•		(∝- 04				
Expected Expenditure Timin	ng 01				25%				
	02				25%				
	03				25%				
	Q4				25%				
Risks and Mitigation	C&I servi	ce connect	ions are a	common p	ractice thr	oughout a	nv given ve	ar and ERTH P	ower has
	well deve	loped stan	dards and	guidelines	to guide a	II stages of	f design, co	nstruction and	4
	administ	ration. Risk	s associate	ed with C&	I connectio	ons are prij	marily a res	ult of ensuring	g that all
	procedur	es and reg	uirements	are follow	ed by the i	utility and	the custom	ers. These risk	s are
	mitigated	through f	requent co	mmunicat	ion betwee	en both pa	rties.		
	0		- 1						
Comparative Information	See Capit	al Investm	ent tables	above for l	historical c	omparisor	IS		
						- I			
REG Investment	This proie	ect is not as	ssociated v	with a REG	investmen	it			
Leave to Construct Approva	I This proje	ect does no	ot require L	eave to Co	onstruct ap	proval uno	der section	92 of the OEB	Act
··									

ALL-SRVCI-Commercial & Industrial Connections

	Evaluation Criteria & Information Requirements
Efficiency, Customer Value & Relia	ability
Project Drivers	C&I service connections are mandatory service requirements and are driven by customer requests and timelines.
Investment Priority	All customer service connections are top priority and are dependent on customer timelines.
Project Alternatives	C&I service connections follow a standardized process in line with ERTH Power Conditions of Service. Depending on the situation there may or may not be alternative solutions with regards to the service connection. (i.e. overhead vs. underground) Each connection is evaluated by ERTH Power staff and a suitable connection is made with input from the customer in line with developed standards.
Operational Benefits	New customer service connections do not look to address specific operational issues however are constructed to current standards which will provide incremental operational benefits moving forward. (ex. accessible metering)
Reliability Benefits	New customer service connections do not look to address specific reliability issues however are constructed to current standards which will provide incremental reliability benefits moving forward.
Customer Benefits	Not applicable
Safety	New customer service connections do not look to address specific safety issues however are constructed to current standards which will provide incremental safety benefits moving forward.
Cyber-Security, Privacy	Not applicable
Co-ordination, Interoperability	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	Not applicable
Environmental Benefits	Not applicable
	Category Specific Requirements
System Access Project	
Factors Affecting Project Timing/Priority	The factors affecting the timing of C&I service connections are primarily driven by timelines set out by the customer and are a top priority.
Factors Relating to Customer Preference	Customer preferences and input are always taken into consideration during the design of a new connection, however all connections are made ensuring that current standard practices are followed in a consistent manner.
Factors Affecting Project Cost	The final cost of the project as a whole is driven by customer requests and can vary year to year. On a more granular level each connection is evaluated and the cost of the connection can vary depending on the size & type of service along with existing conditions.
Controllable Cost Minimization	The connection of new C&I customers is completed through well established procedures that have continuously improved over time to provide cost efficiency to both ERTH Power and
2	ALL-SRVCI-Commercial & Industrial Connections

	customers. Any material used by ERTH Power is purchased through a buying group of multiple local utilities that aims to standardize and minimize costs.
Other Planning Objectives Met	On a project by project basis ERTH Power evaluates the connection requirements to see if other planning objectives can be accomplished. Examples of this include expansions to service new developments from the 28kV system or service requirements to leverage future conditions.
Technically Feasible Project Options	C&I service connections follow a standardized process in line with ERTH Powers Conditions of Service. Depending on the situation there may or may not be alternative solutions with regards to the service connection. (i.e. overhead vs. underground) Each connection is evaluated by ERTH Power staff and a suitable connection is made with input from the customer in line with developed standards.
Results of Economic Evaluation	When a capital contribution is applicable it is calculated in accordance with the methodology included in the DSC and is completed on a project by project basis. These contributions vary on a year by year basis depending on demand and historical trends are used to budget.
Nature and Magnitude of System Impacts, Costs & Cost Recovery	Typically individual C&I connections have a very minimal impact to the distributions system. If a connection drives a substantial investment to the distribution system a separate project will be created and evaluated.

2025 - Project Assessment Form									
POWER POWER	ALL-METERS-Meter Stock	Municipality Cost Category Project Type	All Capital Metering						
	General Information								
Project Description	This project represents the cost associated with replace includes single and three phase meters, associated has collector units) The replacement of these units is drive requirements, and also includes meter costs associate In addition, ERTH has included an additional \$1,250,000 begin our transition to AMI 2.0. This investment is det Assessment Form specific to AMI 2.0; however, the sp	cement of metering er rdware and AMI equip en by failures and regu d with new connectio 20 per year in 2027, 20 tailed further in a sep pend is included in the	quipment which oment (i.e. ulatory ins. 028, & 2029 to parate Project e totals below.						
Investment Category	System Access								

Capital Investment

			Historical Expenditures							
		2018	2019	2020	2021	2022	2023	(2018 to 2023)		
Meter Management -	Gross (\$)	\$172,527	\$203 <i>,</i> 982	\$187,291	\$453,318	\$220,494	\$216,502	\$242,352		
	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0		
	Net (\$)	\$172,527	\$203,982	\$187,291	\$453,318	\$220,494	\$216,502	\$242,352		

			Average						
		2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)	
Meter Management -	Gross (\$)	\$266,750	\$250,835	\$255,851	\$1,385,968	\$1,385,968	\$1,391,188	\$933,962	
	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	
	Net (\$)	\$266,750	\$250,835	\$255,851	\$1,385,968	\$1,385,968	\$1,391,188	\$933,962	

Customer Information	Number of Customer Attachments Customer Load (if available)	ALL ALL
Expected Project Timing	Start Date End Date	Q1 Q4
Expected Expenditure Timing	Q1 Q2 Q3 Q4	25% 25% 25% 25%

2023: \$215,502 2022: \$130,236 2021: \$453,318 2020: \$187,291 2019: \$203,982

Risks and Mitigation

There are minimal risks associated with the typical completion of this project as planned. With that being said a portion of the budget is dependent on meter failures which are unpredictable and based on historical failure rates.

Comparative Information

REG Investment

This project is not associated with a REG investment

ALL-METERS-Meter Stock

Leave to Construct Approval	This project does not require Leave to Construct approval under section 92 of the OEB Act
	Evaluation Criteria & Information Requirements
Efficiency, Customer Value & Reliab	ility
Project Drivers	Mandatory regulatory requirements. (DSC & Measurement Canada)
Investment Priority	New customer connections and upgrades are a top priority and typically organized by engineering staff in compliance with DSC requirements. Measurement Canada compliance is again a top priority and handled by metering staff.
Project Alternatives	Not applicable.
Operational Benefits	Not applicable.
Reliability Benefits	Not applicable.
Customer Benefits	Not applicable.
Safety	Not applicable.
Cyber-Security, Privacy	Not applicable
Co-ordination, Interoperability	Not applicable
Economic Development	Not applicable
Environmental Benefits	Not applicable
	Category Specific Requirements
System Access Project	
Factors Affecting Project Timing/Priority	The factors affecting the timing of metering replacements/upgrades are typically customer preferences, failures and regulatory requirements.
Factors Relating to Customer Preference	Meter replacements, especially for commercial/industrial customers are scheduled to best meet customer preferences.
Factors Affecting Project Cost	Meter failure rates are one of the largest factors affecting this project.
Controllable Cost Minimization	There a minimal controllable factors for cost mitigation.
Other Planning Objectives Met	Metering requirements typically do not meet any other planning objectives however; the use of smart meters will enable more informed decision making for both the customer and the LDC.
Technically Feasible Project Options	Not applicable
Results of Economic Evaluation	Not applicable
Nature and Magnitude of System Impacts, Costs & Cost Recovery	Not applicable

ALL-METERS-Meter Stock



		<u>2025 -</u>	Project As	sessment F	Form			
ERTH Power Power	ect Name ALL-r	METERS-Meter Stock - AMI 2.0				Municipality Cost Category Project Type		l apital letering
	General Information							
Project Descriptio	on This	project repre	esents the co	ost associate	ed with ERTH	s transition	to AMI 2.0 sta	arting in 2027.
Investment Categ	That being said, ERTH still requires a great deal of investigation to build a proper business to fully support this investment, which is estimated to cost upwards of \$5 million. ERTH is of the Grid Smart City Cooperative that has recently launched an RFP to choose a technica consultant who will be tasked with providing a report on AMI 2.0. It will include a compari of various vendors, their technological capabilities, costs & lead times. This report will for the basis of our AMI 2.0 strategy moving forward and is expected in 2025.						er business case on. ERTH is part e a technical e a comparison ort will form	
	5,517							
Capital Investmer	nt			Historical	Evnondituros			Average
		2018	2019	2020	2021	2022	2023	(2018 to 2023)
AMI 2.0 (included	Gross (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
in Meter	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Management)	Net (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
					- 1.			
		2024		Forecast E	xpenditures			Average
		2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)
AMI 2.0 (included	Gross (\$)	\$0	\$0	\$0	\$1,125,000	\$1,125,000	\$1,125,000	\$675,000
in Meter	Contributions (\$)	\$0	\$0	\$0 ¢0	\$0	\$0	\$0 ¢1.125.000	\$0
wanagement)	Net (\$)	ŞU	ŞU	ŞU	\$1,125,000	\$1,125,000	\$1,125,000	\$675,000
Customer Informa Expected Project	ation Num Custo Timing Start End I	ber of Custo omer Load (i Date Date	mer Attachn f available)	nents A A C C	ALL ALL Q1 Q4			
Expected Expendi	iture Timing Q1 Q2 Q3 Q4			2 2 2 2	25% 25% 25%			
Risks and Mitigation ERTH selec large resea		TH is still in the preliminary stages of evaluating AMI 2.0 options, which include vendor lection, timing, pace of investment, and technical capabilities. There are always risks with a rge investment in new technology, however ERTH plans to mitigate this through intensive search and industry collaboration with GSC and other groups over the next 2 years.						
Comparative Info	rmation Not a	applicable						
REG Investment This p		project is no	t associated	with a REG i	investment			
Leave to Construc	ct Approval This	project does	not require	Leave to Co	nstruct appr	oval under s	ection 92 of t	he OEB Act
1		ALL-ME	TERS-Meter	Stock - AMI	2.0			

Evaluation Criteria & Information Requirements

Efficiency, Customer Value & Reliabi	lity
Project Drivers	There are two drivers for this investment; firstly the AMI 1.0 system is approximately 15 years old and nearing or beyond its end of useful life. In comparison to the Kinetrics Report K-418033-RA-001-R000 completed in 2010 outlining Asset Depreciation for the OEB; the Typical Useful Life for a Smart Meter is 5-15 years. The secondary driver for this investment is the need for enhanced grid efficiency, reliability, and real-time data analytics to support advanced energy management, customer engagement, and the integration of renewable energy sources.
Investment Priority	To be determined through the development of a thorough business plan in 2025/2026.
Project Alternatives	To be determined through the development of a thorough business plan in 2025/2026.
Operational Benefits	To be determined through the development of a thorough business plan in 2025/2026.
Reliability Benefits	To be determined through the development of a thorough business plan in 2025/2026.
Customer Benefits	To be determined through the development of a thorough business plan in 2025/2026.
Safety	To be determined through the development of a thorough business plan in 2025/2026.
Cyber-Security, Privacy	To be determined through the development of a thorough business plan in 2025/2026.
Co-ordination, Interoperability	To be determined through the development of a thorough business plan in 2025/2026.
Economic Development	To be determined through the development of a thorough business plan in 2025/2026.
Environmental Benefits	To be determined through the development of a thorough business plan in 2025/2026.

Although ERTH is in the initial stages of evaluating AMI 2.0 options and values, which will be detailed in a formal business, plan in 2025/2026 the following are high-level expectations moving forward.

1. Operational Benefits:

- <u>Advanced Data Analytics</u>: AMI 2.0 goes beyond simple meter readings, providing utilities with deeper insights into consumption patterns, load forecasting, and grid optimization. This is an improvement over AMI 1.0's basic remote meter reading.
- <u>Faster Response Time</u>: While AMI 1.0 allows for remote meter reading, AMI 2.0 enables real-time data transmission, allowing for near-instant responses to grid issues and outages.
- <u>Advanced Demand-Side Management:</u> AMI 2.0 facilitates more effective demand response programs, allowing utilities to control loads in real time, as opposed to the limited load management in AMI 1.0.

2. Reliability Benefits:

- <u>Proactive Maintenance</u>: AMI 2.0 enhances predictive maintenance capabilities by identifying potential issues (like voltage fluctuations) before they lead to outages, surpassing AMI 1.0's reactive outage detection.
- <u>Grid Resilience</u>: Enhanced data collection and analysis in AMI 2.0 enable more efficient outage restoration and grid optimization compared to AMI 1.0.

3. Customer Benefits:

- <u>Deeper Usage Insights:</u> AMI 2.0 provides customers with more granular, real-time data and personalized energy-saving recommendations, improving on AMI 1.0's basic consumption reports.
- <u>Enhanced Engagement Tools</u>: Customers using AMI 2.0 have access to mobile apps and online platforms with interactive data visualization, while AMI 1.0 offers only basic usage information.

4. Safety Benefits:

- <u>Advanced Hazard Detection</u>: AMI 2.0 can detect grid anomalies, like overheating equipment or downed power lines, in realtime. AMI 1.0 lacks this level of detail and real-time hazard monitoring.
- <u>Remote Operation</u>: AMI 2.0 offers remote connection and disconnection capabilities with enhanced security and control, improving on the simpler, less secure remote actions of AMI 1.0.

5. Cybersecurity Benefits:

- <u>Stronger Encryption & Security Protocols:</u> AMI 2.0 improves upon the cybersecurity features of AMI 1.0 with stronger encryption, real-time threat detection, and multi-layered security protocols to defend against increasingly sophisticated cyberattacks.
- <u>Dynamic Security Updates</u>: Unlike AMI 1.0, AMI 2.0 systems can support more frequent and seamless updates to security protocols to combat emerging threats.

6. Interoperability:

- <u>Broader Integration:</u> AMI 2.0 is designed to work seamlessly with modern smart grid technologies like distributed energy resources (DERs), battery storage, and electric vehicle (EV) charging infrastructure, surpassing the limited interoperability of AMI 1.0.
- <u>Support for IoT Devices</u>: AMI 2.0 can integrate with IoT devices, sensors, and home energy management systems, offering a smarter, more connected ecosystem than AMI 1.0.

7. Economic Benefits:

- <u>Lower Operational Costs</u>: AMI 2.0 reduces costs more effectively by automating more processes and optimizing grid performance. AMI 1.0 mainly focuses on remote meter reading and basic data collection, offering limited cost savings.
- <u>Improved Energy Efficiency</u>: With better real-time data and predictive analytics, AMI 2.0 enables utilities and customers to optimize energy consumption, leading to greater long-term economic benefits compared to AMI 1.0.

8. Environmental Benefits:

- <u>Support for Clean Energy:</u> AMI 2.0 better integrates renewable energy sources like solar and wind, optimizing their use and allowing for greater adoption of green energy. AMI 1.0 has more limited capabilities for renewable integration.
- <u>Reduced Carbon Footprint:</u> AMI 2.0's advanced load management reduces the need for peak power plants and lowers overall emissions more effectively than AMI 1.0.

Category Specific Requirements

System Access Project

Factors Affecting Project Timing/Priority	To be determined through the development of a thorough business plan in 2025/2026.
Factors Relating to Customer Preference	To be determined through the development of a thorough business plan in 2025/2026.
Factors Affecting Project Cost	To be determined through the development of a thorough business plan in 2025/2026.
Controllable Cost Minimization	To be determined through the development of a thorough business plan in 2025/2026.
Other Planning Objectives Met	To be determined through the development of a thorough business plan in 2025/2026.
Technically Feasible Project Options	To be determined through the development of a thorough business plan in 2025/2026.
Results of Economic Evaluation	To be determined through the development of a thorough business plan in 2025/2026.
Nature and Magnitude of System Impacts, Costs & Cost Recovery	To be determined through the development of a thorough business plan in 2025/2026.

ERTH Project Name All-FACRL-Relocation of Plant Municipality Cost Category Project Type All Capital Enhancement Project Description This project represents the cost associated with the relocation of hydro infrastructure within the municipal road allowance to accommodate road widening and other modifications. ERTH Power

This project represents the cost associated with the relocation of hydro infrastructure within the municipal road allowance to accommodate road widening and other modifications. ERTH Power meets and communicates with our municipalities to have a better understanding of the facility relocations required for future years. When specific projects are known in advance, a dedicated project is created. This particular project is to accommodate facility relocation requests that arise throughout the year without prior knowledge.



Investment Category

System Access

ALL-FACRL-Relocation of Plant

Capital Ir	vestment									1
			2010	2010	Historical	Expenditures	2022	2022	Average	
		Groce (\$)	2018 \$429.220	2019 \$259.105	2020	2021	2022 \$7.014	\$2023	(2018 to 2023)	
	Facility	Contributions (\$)	\$438,339 \$194,326	\$258,195 \$1,216	\$38,264 \$10,454	\$68,235 \$9,941	۶7,014 \$0	\$393,802 \$110,645	\$203,975 \$54.430	
	Relocations	Net (\$)	\$244,013	\$258,195	\$38,264	\$88,235	\$7,014	\$393,802	\$171,587	
			,,010	,,200	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,,		,,002	,,507	
					Forecast	Expenditures	-		Average	
			2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)	
	F = 2111	Gross (\$)	\$105,796	\$177,593	\$181,145	\$184,767	\$188,463	\$192,232	\$184,840	
	Facility	Contributions (\$)	\$20,796	\$43,449	\$44,318	\$45,204	\$46,108	\$47,030	\$45,222	
	Relocations	Net (\$)	\$85,000	\$177,593	\$181,145	\$184,767	\$188,463	\$192,232	\$184,840	
Custome	r Information	Number of Cust Customer Load	tomer Atta (if availabl	chments e)	V V	′aries – Μι ′aries – Μι	unicipally D unicipally D	riven riven		
Expected	Project Timing	start Date			C)1				
Lycelea		Fnd Date				21)4				
						< ·				
Expected	Expenditure T	iming 01			1	.0%				
LAPCOLO		02			- 4	.0%				
		03			- 4	.0%				
		04			1	0%				
		~ _T			1					
Compara	tive Informatic	participates in r service areas. T alignment betw conflicts and en See Capital inve	utility's limited control over the project's timelines and design. To mitigate these risks, ERTH Power participates in regular coordination meetings with municipal authorities across the majority of our service areas. These meetings, along with maintaining open and continuous communication, ensure alignment between municipal and utility goals, helping to minimize potential delays or design conflicts and ensuring the project remains on track. See Capital investment tables above for historical comparisons							Power of our ensure n
REG Inve	stment	This project is n	ot associat	ted with a	REG invest	ment				
Leave to	Construct App	roval This project doe	es not requ	ire Leave t	to Constru	ct approva	l under sec	ction 92 of t	he OEB Act	
		Evaluat	tion Crite	ria & Info	rmation F	Requirem	ents			
Efficiency Project D	Efficiency, Customer Value & Reliability Project Drivers The primary driver for this project is to accommodate infrastructure upgrades driven by municipal requirements. ERTH Power maintains regular communication with municipal authorities to align municipal projects with areas that need upgrades, thereby minimizing unnecessary replacement of assets that are not yet at their end of life. However, full alignment is not always achievable, and son asset replacements may occur as part of these municipal-driven initiatives. This approach ensures that infrastructure improvements meet both municipal needs and asset management objectives.								nicipal lign ment of and some sures ives.	
Investme	ent Priority	These projects a	are manda	tory and a	re driven b	y municipa	al requests			
Project A	lternatives	ERTH Power wo however the re	ERTH Power works with local municipalities to explain the available options and associated costs nowever the relocation is dictated by the road modifications and often few alternatives exist.							
Operatio	nal Benefits	Facility relocation completed to concern be achieved	ons do not urrent stan d in conjun	look to ad dards whic ction with	dress spec ch will pro the reloca	ific operat vide increr tion ERTH	ional issue nental ben Power will	s however o efits. When incorporato	construction is additional be e these into th	s enefits ne design
2			Δ11-ΕΔ(RI-Reloca	tion of Pla	nt				

CRE-REIOCATION OF PIA
Reliability Benefits	Facility relocations do not look to address specific reliability issues however construction is completed to current standards, which will provide incremental benefits. When additional benefits can be achieved in conjunction with the relocation ERTH Power will incorporate these into the design.
Customer Benefits	Not applicable
Safety	Facility relocations do not look to address specific safety issues however construction is completed to current standards, which will provide incremental benefits. When additional safety benefits can be achieved in conjunction with the relocation ERTH Power will incorporate these into the design.
Cyber-Security, Privacy	Not applicable
Co-ordination,	This project does not apply to the regional infrastructure planning framework.
interoperability	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	Not applicable
Environmental Benefits	Not applicable
	Category Specific Requirements
<u>System Access Project</u> Factors Affecting Project Timing/Priority	The factors affecting the timing of facility relocations are primarily driven by timelines set out by the municipality and are a top priority.
Factors Relating to Customer Preference	Municipal preferences and input are always taken into consideration during the design and alternative options and costs are communicated to the municipality when applicable. Regular communication between the utility and the municipality often result in a solution that meets the requirements of the relocation while minimizing the financial impacts.
Factors Affecting Project Cost	The final cost of the project as a whole is driven by requirements of the municipality. Cost sharing between the municipality and ERTH Power is completed in accordance with the Public Service Works on Highways Act and results in the municipality contributing 50% to the cost of labour and labour saving devices.
Controllable Cost Minimization	Controllable costs are minimized through effective communication and standard design practices.
Other Planning Objectives Met	On a project by project basis ERTH Power evaluates the requirements to see if other planning objectives can be accomplished. Examples of this include the ability to complete voltage conversions or prepare for future plans.
Technically Feasible Project Options	ERTH Power works with local municipalities to explain the available options and associated costs however, the relocation is dictated by the road modifications and often few alternatives exist.
Results of Economic Evaluation	Not applicable
Nature and Magnitude of System Impacts, Costs & Cost Recovery	Typically, facility relocations have a minimal impact to the distributions system as a whole. If a specific relocation drives a substantial investment to the distribution system, a separate project will be created and evaluated.

	2025 - Project Assessment	Form	
POWER POWER	ALL-Fixed Dx Asset Replacement	Municipality Cost Category Project Type	ALL Capital Preventative
	General Information		
Project Description	System renewal projects are driven by the nee longer meet acceptable performance standar the public, and workers. These projects are p identified in the Asset Management Plan, and municipal substations, as outlined in the Distr expenditures under this program are shown b categories to maintain asset replacement lev labour costs. This project is a high-level investment that in sub-project spend is captured in the tables b created to show the level of spending for ea	ed to address distribution sy rds, aiming to minimize nega rioritized primarily based on d are aligned with goals such ribution System Plan. The his pelow. The goal is to increas els in light of increases in ma ncludes spending in the follo relow however separate pro ch and capture all necessary	stems or assets that no tive impacts on customers, asset condition, as as reducing load on storical and forecast e spending in these iterial, equipment and owing "sub-projects". The ject narratives have been or project drivers, etc.
	 Substation Upgrades Maps & Records Pole Replacements Progr Transformer Painting Pro Unplanned Capital Project Pole Line Rebuilds Underground System Rel 	am gram cts puilds	
Investment Category	System Renewal		

Capital Investment

			Historical Expenditures							
		2018	2019	2020	2021	2022	2023	(2018 to 2023)		
Sheed DV Asset	Gross (\$)	\$2,497,000	\$2,900,000	\$3,077,500	\$3,255,000	\$3,432,500	\$3,610,000	\$3,255,000		
Fixed DX Asset	Contributions (\$)	\$ 0	\$0	\$0	\$0	\$0	\$0	\$0		
Replacement	Net (\$)	\$2,497,000	\$2,900,000	\$3,077,500	\$3,255,000	\$3,432,500	\$3,610,000	\$3,255,000		

					Forecast E	xpenditures			A
			2024 (Bridge)	2025	2026	2027	2028	2029	Average (2025 to 2029)
Star Love L	G	ross (\$)	\$2,274,681	\$2,588,287	\$2,692,631	\$2,540,938	\$2,396,658	\$2,656,248	\$2,524,907
Fixed DX Asse	Contri	ibutions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Replacemen	N	let (\$)	\$2,274,681	\$2,588,287	\$2,692,631	\$2,540,938	\$2,396,658	\$2,656,248	\$2,524,907
Customer Informatio	Sustomer Information Number of Customer Attachments VARIES Customer Load (if available) VARIES								
Expected Project Till	iirig	Start Date							
		Enu Date			Q4				
Expected Expenditu	e Timing	Q1			20%	0			
		Q2			30%	/ D			
Q3		30%							
		Q4			20%	/ D			
				1					



Risks and Mitigation	System Renewal Projects, often centered on infrastructure upgrades or rebuilds, face a wide array of challenges. Risks include the current condition of underground infrastructure, potential public opposition to change, and disruptions to commercial or industrial operations. Coordination with municipal bodies, developers, and external contractors introduces schedule dependencies and limited control over timelines. Additionally, customer property and service modifications may cause dissatisfaction, especially when outages are required. By maintaining proactive communication, effective planning, and relying on trusted contractors and field assessments, these risks can be managed to minimize delays, control costs, and ensure smoother project execution.						
Comparative Information	ERTH Power completes various projects throughout a given year and possesses a great deal of expertise with regards to budgeting, design, planning and construction of OH and UG rebuilds and is continually improving its processes to ensure projects are completed as efficiently as possible. Pole replacements because of pole testing and reactive causes are tracked historically to ensure proper budgets and best practices are developed and improved as necessary.						
REG Investment	These projects are not associated with a REG investment						
Leave to Construct Approval	These projects do not require Leave to Construct approval under section 92 of the OEB Act						
Evaluation Criteria & Information Requirements							

Efficiency, Customer Value & Reliability

Project Drivers

These projects are primarily driven by the need to upgrade or replace critical infrastructure to ensure system safety, reliability, and efficiency, as identified in the Asset Management Plan. Aging underground cables, pole-mounted transformers, and copper conductors that have reached the end of their useful life or are experiencing increased failures, make upgrades essential. Additionally, aging poles and padmount transformers are highlighted in the Asset Condition Assessment as requiring the most significant investment as shown in the figure below. Upgrades such as voltage conversion and overhead infrastructure replacements are crucial for modernizing the grid and improving overall system performance. By focusing on proactive replacements, these projects address key safety concerns, reduce operational risks, and align with long-term asset management goals.

2





System-wide Health-Index

To maintain asset conditions, the Asset Management Plan, guided by the Asset Condition Assessment, has established specific asset replacement targets, as outlined in the table below. However, rising material, equipment, and labor costs due to inflation have made asset replacement more difficult to budget, supporting the need for an increase.

Asset	Target	2018	2019	2020	2021	2022	2023	Average
Wood Poles	145	185	167	144	146	79	106	138
Concrete Poles	4	2	1	10	0	2	2	3
Steel Poles	4	1	1	0	0	1	1	1
UG Cable	2.8	0.31	0.91	0.15	0.51	0	2	1
Polemount Transformers	30	31	94	62	38	42	38	51
Padmount Transformers	19	14	23	7	23	15	35	20

Investment Priority

Project Alternatives

ERTH Power implements a software based Investment Optimizer, which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.

Alternative designs were not considered for this program as a whole; instead, alternatives are evaluated on a project-by-project basis. Typically, the main alternative to asset replacement is a run-to-failure approach, which leads to increased risks for customer service, safety, and system reliability, and makes budgeting and planning more difficult.

For each project, alternatives are measured against the project constraints and criteria to determine the most appropriate solution.



	ALL-Fixed Dx Asset Replacement	
	4	
Quantitative Customer Impacts	Outages related to defective equipment are regularly one of the largest causes of s Robust capital programs that address aging assets in a considered, strategic and da approach will have the largest impact on outages related to defective equipment.	ystem outages. ta-driven
Number of Customers in Each Class Potentially Affected	ERTH Power supplies power to approximately 25,000 customers, of which around 2 residential and 2800 are commercial & industrial.	22,000 are
Asset Condition Relative to Typical Life Cycle	The projects that are completed as part of this program have been identified throu. Management Plan as requiring expedient replacement. Therefore, nearly all assets this program are considered at the end of their useful life. The goal of the System R program is to minimize outage, financial and safety risks by proactively testing, insp assessing and replacing aging assets. The Health Index distribution of ERTH Power's shown in Figure 1 below.	gh the Asset replaced under enewal pecting, assets is
System Renewal Project	Category Specific Requirements	
<u>Environmental Benefits</u>	System Renewal projects implement the use of the most current equipment which much more stringent environmental requirements than existing infrastructure such transformer insulating fluids and pole treatment methods.	comply with as current
Economic Development	This project does not directly relate to any economic growth however with any syst ERTH Power considers any potential for customer connections or load growth and a with an appropriate design.	em renewal addresses these
<u>Co-ordination, Interoperability</u>	This project does not apply to the regional infrastructure-planning framework.	
Cyber-Security, Privacy	Not applicable to this project	
<u>Safety</u>	All system renewal projects result in an upgrade to the existing distribution assets of provide a greater deal of both customer and worker safety simply based on the red equipment failure and construction to current standards. The construction of a pro substation will prevent an instance where crews would need to improvise temporar restore power during a substation failure.	which will luced risk of per mobile ry solutions to
Customer Benefits	The benefits to customers resulting from the completion of a system renewal proje upgrade in distribution assets that align with the long-term plan for the system to c standards.	ect arise from the current design
Reliability Benefits	The completion of the project will upgrade the existing aged assets as required and more reliable system simply based on the installation of new upgraded distribution	in turn provide a assets.
Operational Benefits	The largest operational benefit of this project is related to the upgraded infrastruct constructed to current standards. This ensures that proper clearances, spacing, pro and other equipment are implemented which are more easily accessed and operate staff.	ure being tective devices ed by operations

uration (Customer hrs)										
	2016	2017	2018	2019	2020	2021	2022	2023	Total	%
0-Unknown	1011	57	537	231	486	5800	124	61	8307	1.51%
1-Scheduled Outage	4472	2691	5836	4832	8852	13531	1631	13594	55439	10.06%
2-Loss of Supply	39869	18594	39803	42636	31467	67975	26440	57129	323913	58.75%
3-Tree Contacts	9851	2134	4512	1457	4605	10925	13038	3054	49577	8.99%
4-Lightning	0	294	1	23	387	218	40	1022	1985	0.36%
5-Defective Equipment	2021	4870	5243	11843	2463	18232	3056	11865	59593	10.81%
6-Adverse Weather	18338	1639	5318	1049	114	1687	4128	0	32273	5.85%
7-Adverse Environment	0	0	0	0	0	2532	0	0	2532	0.46%
8-Human Element	0	0	0	0	0	0	3	0	3	0.00%
9-Foreign Interference	202	5809	478	3007	1950	169	661	5444	17721	3.21%
Total	75764	36088	61728	65078	50324	121069	49121	92170	551342	100.00%



This program is aimed at improving system reliability within a broad asset set, which overall will **Qualitative Customer Impacts** improve customer satisfaction. Fixed Distribution Asset Replacement projects can affect all customer classes depending on the scope of the projects. As mentioned, assets that are replaced under this program are at or near Value of Customer Impact end of life with a much higher risk of failure. As a result, this program can greatly reduce outage times for all customers. Unforeseen events and projects outside our control often require that we adjust the budget as the **Other Factors Affecting** year progresses, which can mean that some projects are pushed back due to cost or availability of **Project Timing** personnel. **Consequences for System** System O&M costs are not expected to be materially affected by this project. **O&M** Costs **Reliability and Safety Factors** Reliability indicators will be positively affected with the replacement of aging and failing assets. Analysis of Project Benefits & There are no alternatives that can be considered regarding the timing and completion of this program due to the nature of the end of life assets. Timing Like for Like Renewal Like for Like Renewal Analysis is project-specific and considered on a case-by-case basis. When it is Analysis determined that there is the opportunity to reconfigure the system or meet other planning objectives, alternatives are weighed against project constraints and criteria to determine the best possible solution. 5





		<u>202</u>	5 - Project A	Assessment	Form			
ERTH POWER POWER	oject Name	ALL-STNUPGD-	Substation L	Jpgrades		Municipa Cost Cate Project T	ility / egory (ype I	ALL Capital Preventative
			General I	nformation				
Project Descript	egory	This project consists of expenditures allocated to upgrades with our remaining ten (14 substations. Typically, this investment has been associated with smaller expenditures along the lines of replacing switches, or individual components with the substations. 2024 and the forecast period there are larger material investments into the construction of a mobile substation. This will allow ERTH Power to Provide reliable an flexible contingency for substation failures; 10 remain in service w/ average transformer age of 44. In addition it will allow station maintenances to be completed without customer outages; customers are more and more reliant on uninterrupted supply and planned outages for substation maintenance are a significant driver of SAI and SAIFI within our system reliability indices. The mobile substation is expected to be ready for service in late 2024, with connection point upgrades and engineering analys continuing into 2025, and 2026. The mobile substation accounts for the following spending: 2024: \$300,000 2025: \$150,000 2026: \$50,000 The existing substations step voltage down from 27,600Y/16,000V (28kV) to 4,160Y/2,400V (4kV). ERTH made the decision along with many other provincial LDC's to eliminate the lower 4kV voltage from its distribution system and convert it to the preferred 28kV system. This allows LDC's to standardize & reduce inventory level, eliminate substations, provide more capacity and less line losses. ERTH's capital expenditure program aim to convert entirely to 28kV where possible and eliminate th need for our 4kV substations however this will take approximately 10-20 years. Therefore, the existing substations must remain in good working order for at least the amount of time.						
				Historical I	Expenditures			Average
		2018	2019	2020	2021	2022	2023	(2018 to 2023
C hat at	Gross (\$)	\$34,900	\$93,311	\$10,609	\$10,705	\$44,818	\$18,694	\$35,506
Substation	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
opgraues	Net (\$)	\$34,900	\$93,311	\$10,609	\$10,705	\$44,818	\$18,694	\$35,506
				Forecast E	xpenditures			Average
		2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029
Substation	Gross (\$)	\$310,000	\$181,842	\$82,798	\$33,782	\$34,795	\$35,839	\$73,811
Upgrades -	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	Net (\$)	\$310,000	\$181,842	\$82,798	\$33,782	\$34,795	\$35,839	\$73,811
Customer Inforn	nation	Number of Cus Customer Load	tomer Attach (if available)	nments	VARIES VARIES			

ALL-STNUPGD-Substation Upgrades

Expected Project Timing	Start Date	01			
Expected Project mining	Fnd Date	04			
Expected Expenditure Timing	Q1	20%			
	Q2	30%			
	Q3	30%			
	Q4	20%			
Risks and Mitigation	The largest risk within this investment substation. There are very few standar connections that are required to succe operations. ERTH engaged multiple firm connecting multiple substations and an effectively.	is the unique nature of the construction of a mobile rds that apply to the construction or distribution system essfully integrate a mobile substation into our ms that have experience building mobile substations and re confident that the project will be completed			
Comparative Information	No comparative information exists. As competitive pricing on the constructio	noted earlier ERTH engaged multiple firms for n of the mobile substation.			
REG Investment	This project is not associated with a RE	G investment			
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act			
	Evaluation Criteria & Information	n Requirements			
Efficiency, Customer Value & Reliabi	lity				
Project Drivers	The primary driver of this project is to provide a reliable contingency plan in the ever one of our ten (10) substations has a failure. A secondary driver for the project is to a ERTH to complete regular substation maintenance to our substations without custon experiencing outages as a result; historically we have been completing substation maintenance utilizing an outage to our customers.				
Investment Priority	The priority for this investment is drive substation transformers. The transforr and the most costly to replace. As note transformers is 44 years old, and the for consultant in 2023 after reviewing all r results and yearly maintenance record	en by the deteriorating condition of ERTH's remaining ner is the most critical component within a substation ed earlier the average age of our substation ollowing executive summary was provided by a relevant transformer oil testing, transformer testing s for each of the remaining 10 substations.			

Location/ID	Transformer	Serial #	Year	Base	Rating
	Manufacturer		Built	kVA	2023
Aylmer MS2-TX2	Ferranti-Packard	2305405	1992	3000	3.1
Aylmer Forest MS1	Westinghouse	A3S6273	1974	5000	3.4
Aylmer-McBrein MS2-TX1	Federal Pioneer	T 2993-1	1967	3000	3.3
Beachville MS1	HK Porter	225151	1976	3000	3.0
Clinton MS1	Ferranti-Packard	301687	1971	5000	3.5
Goderich MS2-T1	Westinghouse	A3S6815	1985	5000	3.0
Goderich MS3-T1	Westinghouse	A3S6029	1968	5000	3.3
Goderich MS4-T1	Westinghouse	A3S6467	1979	5000	3.2
Ingersoll MS1	Ferranti-Packard	0265001001	1985	5000	2.9
Port Stanley MS1	Ferranti-Packard	307425	1979	5000	3.4
Tavistock	Pioneer	G13572-1	2005	5000	1

Rating System Summary

- 1 Suitable for continued use
- 2 Suitable for continued use with increased monitoring, investigation
- 3 Suitability of continued use in question, requires increased monitoring and evaluation
- 4 Suitability of continued use doubtful, immediate evaluation > removal from service

As you can see the 2023 Rating varies, however the majority of the substation transformers are scored as "3 - Suitability for continued use in questions, requires increased monitoring and evaluation"

The alternative to the large material investment in a mobile substation are the following:

Do-Nothing (Status Quo): Continue to operate and maintain the remaining ten (10) substations. ERTH continues to complete voltage conversion within its distribution system which will eventually eliminate the need for the substations, however this will take 10-20 years to accomplish, leaving our customers at risk of a prolonged outage as a result of a substation transformer failure.

Replace Existing Substations "Like-for-Like": ERTH indicated in our 2015 AMP that the costs associated with replacing a substation would be approximately \$780,000. Assuming an inflationary factor of 3% that equates to approximately \$1.05million per substation in 2025, which is though to be an extremely conservative figure considering the costs increases we have seen in transformers and associated equipment over the past 5 years. This would result in >\$10million in expenditure required to replace the existing substations. In addition, our 2015 AMP outlined that ERTH could reasonably expect \$10,000 per year in savings per substation related to O&M costs savings once the substations are removed.

As a result, of the alternatives above, ERTH believes the most prudent approach is to continue with its voltage conversion efforts, with an objective of eliminating our 4kV substations. While also creating a suitable contingency plan via a mobile substation in the event we have a substation failure.

The largest operational benefit of this project is related to the upgraded infrastructure being constructed to current standards. This ensures that proper clearances, spacing, protective devices and other equipment are implemented which are more easily accessed and operated by operations staff.

Project Alternatives

Operational Benefits



	In addition, the inclusion of a material spend on a mobile substation will provide operat benefits allowing substation maintenances being done more often, without outages to customers.	tional				
	The completion of the project will upgrade the existing aged assets as required and in t provide a more reliable system simply based on the installation of new upgraded distribassets.	urn oution				
Reliability Benefits	The mobile substation will provide a reliable contingency plan in the case of a substatio transformer failure. This will drastically reduce the amount of time that will be required restore customers resulting from a failure. It will also reduce the number of customer h outages (SAIDI) resulting from typical substation maintenance practices.	on d to nours of				
Customer Benefits	The benefits to customers resulting from the completion of a system renewal project as from the upgrade in distribution assets that align with the long term plan for the system current design standards.	rise n to				
Safety						
	All system renewal projects result in an upgrade to the existing distribution assets whic provide a greater deal of both customer and worker safety simply based on the reducer equipment failure and construction to current standards. The construction of a proper substation will prevent an instance where crews would need to improvise temporary so to restore power during a substation failure.	h will d risk of mobile olutions				
Cyber-Security, Privacy						
	Not applicable to this project					
<u>Co-ordination, interoperability</u>	This project does not apply to the regional infrastructure-planning framework.					
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH Power considers any future potential for customer connections or load g and addresses these with an appropriate design.	rowth				
Environmental Benefits	System Renewal projects implement the use of the most current equipment which com with much more stringent environmental requirements than existing infrastructure suc current transformer insulating fluids and pole treatment methods.	iply h as				
	Category Specific Requirements					
System Renewal Project						
Asset Condition Relative to Typical Life Cycle	As noted above, the average age for ERTH substation transformers are 44 years old. In comparison to the Kinetrics Report K-418033-RA-001-R000 completed in 2010 outlining Depreciation for the OEB; the Typical Useful Life for a Power Transformer is 45 years ar Maximum Useful Life is 60 years. This age related comparison along with analysis of ou testing and maintenance records indicate that overall our substation transformers are a nearing their useful life and at a higher risk of failure.	g Asset nd the ir oil at or				
Number of Customers in Each Class Potentially Affected	Approximately 7500 of ERTHs customer are supplied via our 4kV system which equates nearly 30% of our customer base. Of these customers, the vast majority are residential small commercial customers.	and				
Quantitative Customer Impacts	To date, unplanned substation outages have not caused major reliability concerns how they pose a large risk of a prolonged outages should a transformer fail. The following fi from our annual reliability report show that Scheduled Outages comprise a significant p of customer hours (SAIDI) in a give year. A mobile substation will reduce this drastically	vever igures portion /.				
	4					
	ALL-STNUPGD-Substation Upgrades					

Duration (Customer hrs)										
	2016	2017	2018	2019	2020	2021	2022	2023	Total	%
0-Unknown	1011	57	537	231	486	5800	124	61	8307	1.51%
1-Scheduled Outage	4472	2691	5836	4832	8852	13531	1631	13594	55439	10.06%
2-Loss of Supply	39869	18594	39803	42636	31467	67975	26440	57129	323913	58.75%
3-Tree Contacts	9851	2134	4512	1457	4605	10925	13038	3054	49577	8.99%
4-Lightning	0	294	1	23	387	218	40	1022	1985	0.36%
5-Defective Equipment	2021	4870	5243	11843	2463	18232	3056	11865	59593	10.81%
6-Adverse Weather	18338	1639	5318	1049	114	1687	4128	0	32273	5.85%
7-Adverse Environment	0	0	0	0	0	2532	0	0	2532	0.46%
8-Human Element	0	0	0	0	0	0	3	0	3	0.00%
9-Foreign Interference	202	5809	478	3007	1950	169	661	5444	17721	3.21%
Total	75764	36088	61728	65078	50324	121069	49121	92170	551342	100.009



Qualitative Customer Impacts	This program is aimed at maintaining system reliability, within a high risk asset class which will
Qualitative customer impacts	improve customer satisfaction.

Constructing a mobile substation offers significant value in minimizing customer outages during failure. By deploying such a unit, the utility can restore power to affected areas without prolonged interruptions. This proactive measure ensures that customers experience minimal disruption to their daily lives and operations. Additionally, the mobile substation enhances the utility's responsiveness to emergencies, demonstrating a commitment to reliability and customer satisfaction.

The non-standard nature of a mobile substation can result in delays and unexpected costs, as **Other Factors Affecting Project** detailed in previous sections ERTH consultant multiple reputable consultant to help construct, and design the project including connection to our system.

Consequences for System O&M System O&M costs are not expected to be materially affected by this project.

> Reliability indicators will be positively affected with the introduction of a mobile substation into our operations.

Like for Like renewal analysis is outlined in the "Project Alternatives" section above.

Analysis of Project Benefits & There are no alternatives that can be considered regarding the timing and completion of this program due to the nature of the end of life assets. Timing

Like for Like Renewal Analysis

Reliability and Safety Factors

Value of Customer Impact

Timing

Costs

5

ALL-STNUPGD-Substation Upgrades





		<u>202</u>	5 - Project	Assessment	t Form			
	Project Name	ALL-MAPS-Ma	ps & Records			Municipa Cost Cate Project T	ility A egory C ype E	ll Capital Inhancement
			General I	nformatior	า			
Project Desci	ription	This project represents the costs associated with updating maps and records with Powers Geographical Information System (GIS). This includes adding and modifyi upgraded services and updating maps based on system renewal type projects. Th simply tracked in a separate budget due to the timing of when updates are comp when the physical construction of projects is done. This project will also contain e from third party vendors for GIS/OMS functionality upgrades.				vithin ERTH lifying new and . These are mpleted and in expenditures		
Investment C	Category	System Renew	al					
Capital Inves	tment							
				Historical I	Expenditures			Average
		2018	2019	2020	2021	2022	2023	(2018 to 2023)
Mans &	Gross (\$)	\$87,403	\$123,362	\$99,284	\$82,606	\$108,207	\$103,889	\$100,792
Records	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	Net (\$)	\$87,403	\$123,362	\$99,284	\$82,606	\$108,207	\$103,889	\$100,792
		2024		FUIECASLE	xpenditures			Average
		(Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)
Maps &	Gross (\$)	\$85,000	\$104,320	\$106,406	\$108,534	\$110,705	\$112,919	\$108,577
Records	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
		COLINA	C10/270	¢106 /06	¢100 E21		S I I / U I U	
Customer Inf	formation	\$85,000 Number of Cu Customer Load	\$104,320 stomer Attac d (if available	\$106,406 hments)	\$108,534 Varies - Cust Varies - Cust	tomer Driver)) 2115'212	\$106,577
Customer Inf	formation vject Timing	S85,000 Number of Cus Customer Load Start Date End Date	\$104,320 stomer Attac d (if available	\$106,406 hments)	\$108,534 Varies - Cust Varies - Cust Q1 Q4	tomer Driver)) 2115'212	\$106,577
Customer Inf Expected Pro Expected Exp Risks and Mir	formation oject Timing benditure Timing	Start Date End Date Q1 Q2 Q3 Q4 None	\$104,320 stomer Attac d (if available	\$106,406 hments)	\$108,534 Varies - Cust Varies - Cust Q1 Q4 25% 25% 25% 25%	tomer Driver)	11,5'9015
Customer Inf Expected Pro Expected Exp Risks and Mir	formation oject Timing benditure Timing tigation	Start Date End Date Q1 Q2 Q3 Q4 None This project is	\$104,320 stomer Attac d (if available	\$106,406 hments) ed with a REG	\$108,534 Varies - Cust Varies - Cust Q1 Q4 25% 25% 25% 25%	tomer Driver	2115,212	,,,,,,,,
Customer Inf Expected Pro Expected Exp Risks and Mir REG Investm Leave to Con	Formation Opect Timing Denditure Timing tigation ent struct Approval	S85,000 Number of Cur Customer Load Start Date End Date Q1 Q2 Q3 Q4 None This project is This project do	\$104,320 stomer Attac d (if available not associate bes not requi	\$106,406 hments) ed with a REG re Leave to C	\$108,534 Varies - Cust Varies - Cust Q1 Q4 25% 25% 25% 25% 6 investment Construct app	tomer Driver tomer Driver	section 92 of	the OEB Act
Customer Inf Expected Pro Expected Exp Risks and Mir REG Investme Leave to Con	formation oject Timing benditure Timing tigation ent struct Approval	S85,000 Number of Cur Customer Load Start Date End Date Q1 Q2 Q3 Q4 None This project is This project do	\$104,320 stomer Attac d (if available not associate bes not requi Criteria & Ir	\$106,406 hments) ed with a REC re Leave to C	\$108,534 Varies - Cust Varies - Cust Q1 Q4 25% 25% 25% 25% 6 investment Construct app	tomer Driver tomer Driver	section 92 of	the OEB Act
Customer Inf Expected Pro Expected Exp Risks and Mir REG Investme Leave to Con Efficiency, Cu Project Drive	formation oject Timing benditure Timing tigation ent struct Approval ustomer Value & Reliabi	\$85,000 Number of Cur Customer Load Start Date End Date Q1 Q2 Q3 Q4 None This project is This project do Evaluation Iity Having up-to-co	\$104,320 stomer Attac d (if available not associate bes not requi Criteria & Ir late, accurate	\$106,406 hments) ed with a REG re Leave to C oformation e maps are a	\$108,534 Varies - Cust Varies - Cust Q1 Q4 25% 25% 25% 25% 6 investment Construct app Requireme In operationa	tomer Driver tomer Driver tomer Driver niver nts	section 92 of	the OEB Act
Customer Inf Expected Pro Expected Exp Risks and Mir REG Investme Leave to Con Efficiency, Cu Project Drive Investment P	formation oject Timing benditure Timing tigation ent struct Approval ustomer Value & Reliabi rs	\$85,000 Number of Cur Customer Load Start Date End Date Q1 Q2 Q3 Q4 None This project is This project do Evaluation lity Having up-to-co Due to the proc	\$104,320 stomer Attac d (if available not associate bes not requi Criteria & Ir late, accurate ject driver th	\$106,406 hments) ed with a REG re Leave to C oformation e maps are a is is a high p	\$108,534 Varies - Cust Varies - Cust Q1 Q4 25% 25% 25% 25% 35 6 investment Construct app Requireme In operational priority and co	tomer Driver tomer Driver tomer Driver niver nts ni requiremer ponsidered ma	section 92 of nt that must b andatory.	the OEB Act

Project Alternatives	None
Operational Benefits	Up-to-date and accurate maps allow staff to efficiently and safely execute all aspects of their daily work.
Reliability Benefits	Up-to-date and accurate maps allow staff to efficiently restore outages and complete switching to minimize outages during planned work.
Customer Benefits	Up-to-date and accurate maps allow staff to minimize outages and complete work as efficiently as possible.
Safety	Up-to-date and accurate maps allow staff to establish work protection in order to safely execute projects.
Cyber-Security, Privacy	Not applicable
Co-ordination, Interoperability	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	Not applicable
Environmental Benefits	Not applicable
	Category Specific Requirements
<u>System Renewal Project</u> Asset Condition Relative to Typical Life Cycle	Not applicable, however this project is tied to all other system renewal projects and is linked to their asset condition.
Number of Customers in Each Class Potentially Affected	All
Quantitative Customer Impacts	Up-to-date and accurate maps allow staff to efficiently restore outages and complete switching to minimize outages during planned work.
Qualitative Customer Impacts	Difficult to quantify however customer satisfaction is generally linked to the utilities ability to efficiently perform work and minimize outages.
Value of Customer Impact	Difficult to quantify
Other Factors Affecting Project Timing	None
Consequences for System O&M Costs	Exact consequences are difficult to quantify for this budget.
Reliability & Safety Factors	Exact impacts are difficult to quantify for this budget.
Analysis of Project Benefits & Timing	Not applicable
Like for Like Renewal Analysis	Not applicable
2	All-MAPS-Maps & Records

	<u> 2025 - Pro</u>	oject Assess	sment Form		
P O W E R	ALL-OHUPG-Planned	Pole Replace	ements	Municipality Cost Category Project Type	ALL Capital Preventative
	Gen	eral Inform	nation		
Project Description	The pole replacement end of life pole replac The current pole testi with "re-tests" based created to ensure a co center in any given ye based on poor condit	t project is a cements iden ing program remaining s onsistent lev ear. This pro- ion.	blanket project used ntified as part of the tests 1/9 of the ERTH trength estimates. The vel of pole replacement ject is also used to ac	d to account for the ERTH Power yearly H Power service area he pole testing sche ents are assigned to ccount for reactive p	typical number of pole testing program. a every year along dule has been each operations pole replacements
Preliminary Project Information	Age of Plant: Primary Voltage: Pole Type: Area Description:	>50 years VARIES Wood VARIES	Constru Pri Secor	action Standards: I mary Conductor: M ndary Conductor: M Traffic Volume: M	Legacy VARIES VARIES VARIES
Asset Condition Issues	<text></text>		PCB's Clearances Road Construction Submersible TX Grounding Access	 Ope Caj 5kV UG Pole Meter A Stru 	n Bus

Investment Category

System Renewal

Capital Investment

Gross Capital Customer Contribution Net Capital O&M Costs (if applicable) \$300,000 \$0 \$300,000 \$0

1

ALL-OHUPG-Pole Replacements

Customer Information	Number of Customer Attachments Customer Load (if available)	VARIES VARIES	
Expected Project Timing	Start Date End Date	Q1 Q4	
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 30% 30% 20%	
Risks and Mitigation	The vast majority of projects require distribution system, which can create great deal of experience and construc always minimized and communicated these requirements and budgeting ar	varying degrees of outages to complete upgrades to the e the risk of customer displeasure. ERTH Power staff has a ction practices are in place to ensure that outages are d with customers. In addition ERTH Power staff is aware of and planning is completed with this in mind.	
Comparative Information	2024: In Progress - \$300,000 budgete 2023: \$293,913 2022: \$224,782 2021: \$467,757 2020: \$357,124	:d	
REG Investment	This project is not associated with a R	REG investment	
Leave to Construct Approval	This project does not require Leave to	o Construct approval under section 92 of the OEB Act	
	Evaluation Criteria & Information	on Requirements	
Efficiency, Customer Value & Reli	iability		
Project Drivers	The primary driver for this project is t regular pole testing. This type of proje the distribution system while mitigati Management Plan.	the replacement of end of life poles as identified by ect is aimed at maintaining the safety and reliability of ing the cost impacts to customers as set out in the Asset	
	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.		
Investment Priority	projects based on weighted criteria ir This process is detailed in Section 5.4.	pased Investment Optimizer which evaluates multiple n order to identify, select, prioritize and pace investments. .2 of the DSP.	
Investment Priority Project Alternatives	No alternative designs were examined replacements are completed on a one system as a whole are made.	based Investment Optimizer which evaluates multiple n order to identify, select, prioritize and pace investments. .2 of the DSP. d as part of this program. The majority of pole e for one basis and only minor changes to the distribution	
Investment Priority Project Alternatives Operational Benefits	 ERTH Power implements a software to projects based on weighted criteria in This process is detailed in Section 5.4 No alternative designs were examined replacements are completed on a one system as a whole are made. The largest operational benefit of this constructed to current standards. Thi devices and other equipment are imply operations staff. 	based Investment Optimizer which evaluates multiple n order to identify, select, prioritize and pace investments. .2 of the DSP. d as part of this program. The majority of pole e for one basis and only minor changes to the distribution s project is related to the upgraded infrastructure being is ensures that proper clearances, spacing, protective plemented which are more easily accessed and operated	
Investment Priority Project Alternatives Operational Benefits Reliability Benefits	 ERTH Power implements a software to projects based on weighted criteria in This process is detailed in Section 5.4 No alternative designs were examined replacements are completed on a one system as a whole are made. The largest operational benefit of this constructed to current standards. Thi devices and other equipment are imply operations staff. The completion of the project will upprovide a more reliable system simply assets. 	based Investment Optimizer which evaluates multiple n order to identify, select, prioritize and pace investments. .2 of the DSP. d as part of this program. The majority of pole e for one basis and only minor changes to the distribution s project is related to the upgraded infrastructure being is ensures that proper clearances, spacing, protective olemented which are more easily accessed and operated grade the existing aged assets as required and in turn y based on the installation of new upgraded distribution	
Investment Priority Project Alternatives Operational Benefits Reliability Benefits Customer Benefits	 ERTH Power implements a software to projects based on weighted criteria in This process is detailed in Section 5.4 No alternative designs were examined replacements are completed on a one system as a whole are made. The largest operational benefit of this constructed to current standards. Thi devices and other equipment are imply operations staff. The completion of the project will upprovide a more reliable system simply assets. The benefits to customers resulting from the upgrade in distribution asset current design standards. This will provide a more reliable system simply assets. 	based Investment Optimizer which evaluates multiple in order to identify, select, prioritize and pace investments. .2 of the DSP. d as part of this program. The majority of pole e for one basis and only minor changes to the distribution is project is related to the upgraded infrastructure being is ensures that proper clearances, spacing, protective olemented which are more easily accessed and operated grade the existing aged assets as required and in turn y based on the installation of new upgraded distribution rom the completion of a system renewal project arise ts that align with the long term plan for the system to ovide an increase in safety to the public and more reliable	
Investment Priority Project Alternatives Operational Benefits Reliability Benefits Customer Benefits	 ERTH Power implements a software to projects based on weighted criteria in This process is detailed in Section 5.4 No alternative designs were examined replacements are completed on a one system as a whole are made. The largest operational benefit of this constructed to current standards. Thi devices and other equipment are imply operations staff. The completion of the project will upprovide a more reliable system simply assets. The benefits to customers resulting from the upgrade in distribution asset current design standards. This will provide a more reliable system simply assets. 	based Investment Optimizer which evaluates multiple in order to identify, select, prioritize and pace investments. .2 of the DSP. d as part of this program. The majority of pole e for one basis and only minor changes to the distribution is project is related to the upgraded infrastructure being is ensures that proper clearances, spacing, protective oblemented which are more easily accessed and operated grade the existing aged assets as required and in turn y based on the installation of new upgraded distribution rom the completion of a system renewal project arise ts that align with the long term plan for the system to ovide an increase in safety to the public and more reliable	

	system that is much more cost effective to operate due to improved equipment, access and a reduction in line losses.
<u>Safety</u> <u>Cyber-Security, Privacy</u> Co-ordination, Interoperability	All system renewal projects result in an upgrade to the existing distribution assets which will provide a greater deal of both customer and worker safety simply based on the reduced risk of equipment failure and construction to current standards. Not applicable to this project
	This project does not apply to the regional infrastructure planning framework. ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH Power considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
<u>Environmental Benefits</u>	System Renewal projects implement the use of the most current equipment which comply with much more stringent environmental requirements than existing infrastructure such as current transformer insulating fluids and pole treatment methods.

Category Specific Requirements

System Renewal Project

Asset Condition Relative to Typical Life Cycle

The pole replacements that are completed as part of this program have been identified through annual testing as requiring expedient replacement. Therefore all assets replaced under this program are considered at the end of their useful life. The goal of the pole replacement program is to minimize outage, financial and safety risks by proactively testing, assessing and replacing aging pole assets. The Health Index distribution of wood poles is shown in Figure 1 below.



Figure 1: Extrapolated Wood Pole HI Results

ALL-OHUPG-Pole Replacements

Number of Customers in Each Class Potentially Affected	Pole replacements as identified by pole testing and reactive replacements due to failure can affect a wide range of customers including residential, commercial and industrial. This can include hospitals, large manufacturing facilities and other important loads depending on the location of the required replacement. Pole failures can result in large outages affecting entire feeders depending on the severity. Since the poles replaced under this program have been identified through testing as end of life the probability of a failure is much more likely as compared to typical useful life approximations.
Quantitative Customer Impacts	If the poles identified through the testing program are not replaced it is likely that an afterhours unplanned replacement would be required at some point. Depending on the severity of the failure a large feeder outage could be expected with an extended duration. In contrast a planned pole replacement can typically be completed with minimal to no outages to customers.
Qualitative Customer Impacts	This program is aimed at maintaining system reliability and public safety by eliminating all poles reaching end of life. This will ensure that current customer satisfaction levels are maintained.
Value of Customer Impact	The pole replacement program can affect all customer classes depending on the poles that are identified as requiring replacement. As previously mentioned the risk of failure is much higher since the poles have been identified through testing as requiring replacement and an unplanned replacement due to failure can result in a larger outage with a greater duration. A planned pole replacement very rarely results in a loss of service to customers.
Other Factors Affecting Project Timing	Due to the nature of the project and condition of the assets identified this program must be completed on a yearly basis.
Consequences for System O&M Costs	The largest consequence for system O&M costs is the resulting unplanned pole replacements that are likely if the program is not completed. This results in larger outage for customers and higher costs.
Reliability and Safety Factors	The poles identified are at their end of life and require expedient replacement to avoid any reliability and safety concerns.
Analysis of Project Benefits & Timing	There are no alternatives that can be considered regarding the timing and completion of this program due to the nature of the end of life assets.
Like for Like Renewal Analysis	The majority of pole replacements are completed in a like-for-like manner aside from upgrades to the materials, and design standards that are implemented. If a pole identified for replacement can be leveraged to cost effectively improve the distribution system outside of a like-for-like replacement than it is considered on a pole by pole basis.



	2025 - Project Asses	sment Form		
P O W E R	ALL-UGUPG-Transformer Painting	5	Municipality Cost Category Project Type	ALL Capital Preventative
	General Inform	nation		
Project Description	The pad-mounted transformer pa transformers that have not reach environmental factors. Currently, transformers for resurfacing, focu order to extend their useful life a	inting project is a bl ed their end-of-life k the project will sele using on transformer nd improve their app	anket project used to out have deteriorated ct a small number of s deteriorating faster pearance.	identify and repair externally due to candidate than typical, in
Preliminary Project Information	Age of Plant: 10-20 year Primary Voltage: VARIES Pole Type: N/A Area Description: VARIES	rs Constru Pr Seco	uction Standards: Le imary Conductor: V ndary Conductor: V Traffic Volume: V	egacy ARIES ARIES ARIES
Asset Condition Issues	Rotten Poles□Broken Equipment□Revitalization⊠Direct Buried Cable□TX Base□Backyard□	PCB's Clearances Road Construction Submersible TX Grounding Access	 Oper Cap 5kV UG C Polet Meter Ac Struct 	acity acity cable crans ccess tural
	<image/>			
Investment Category	System Renewal			
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$20,000 \$0 \$20,000 \$0		

ALL-UGUPG-Padmount Transformer Painting

Customer Information	Number of Customer Attachments Customer Load (if available)	VARIES VARIES		
Expected Project Timing	Start Date End Date	Q1 Q4		
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 30% 30% 20%		
Risks and Mitigation	Most projects necessitate varying degr system, which can lead to customer dis implementing effective construction pr outages. Additionally, staff ensure that affected customers. Comprehensive bu considerations in mind, leveraging ERT the impact of outages on customers.	ees of outages to facilitate upgrades to the distribution ssatisfaction. ERTH Power mitigates this risk by ractices aimed at minimizing the duration and impact of coutages are communicated clearly and promptly to udgeting and planning are conducted with these H Power's extensive experience to manage and reduce		
Comparative Information	ERTH Power completes various project expertise with regards to budgeting, de and is continually improving its process possible. Transformer refurbishment a proper budgets and best practices are	is throughout a given year and possesses a great deal of esign, planning and construction of OH and UG rebuilds ses to ensure projects are completed as efficiently as nd reactive causes are tracked historically to ensure developed and improved as necessary.		
REG Investment	This project is not associated with a RE	G investment		
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act		
Evaluation Criteria & Information Requirements				
		inequilements		
Efficiency, Customer Value & Reliabi Project Drivers	lity The primary driver for this project is th transformers. Secondary drivers are th	e extension of the working life of pad-mounted e improvement in appearance of this equipment.		
Efficiency, Customer Value & Reliabi Project Drivers Investment Priority	lity The primary driver for this project is th transformers. Secondary drivers are th ERTH Power implements a software ba projects based on weighted criteria in This process is detailed in Section 5.4.2	e extension of the working life of pad-mounted e improvement in appearance of this equipment. used Investment Optimizer, which evaluates multiple order to identify, select, prioritize and pace investments.		
Efficiency, Customer Value & Reliabi Project Drivers Investment Priority Project Alternatives	lity The primary driver for this project is th transformers. Secondary drivers are th ERTH Power implements a software ba projects based on weighted criteria in This process is detailed in Section 5.4.2 The alternative to refurbishment is rep transformers are selected for refurbish majority of refurbishments are comple distribution system as a whole are mad	e extension of the working life of pad-mounted e improvement in appearance of this equipment. used Investment Optimizer, which evaluates multiple order to identify, select, prioritize and pace investments. e of the DSP. Alacement and run-to-failure. A small number of ment based on cost and expected remaining life. The sted on a one for one basis and no changes to the de.		
Efficiency, Customer Value & Reliabi Project Drivers Investment Priority Project Alternatives Operational Benefits	lity The primary driver for this project is th transformers. Secondary drivers are th ERTH Power implements a software ba projects based on weighted criteria in This process is detailed in Section 5.4.2 The alternative to refurbishment is rep transformers are selected for refurbish majority of refurbishments are comple distribution system as a whole are mad The largest operational benefit of this p constructed to current standards. This devices and other equipment are imple by operations staff.	e extension of the working life of pad-mounted e improvement in appearance of this equipment. used Investment Optimizer, which evaluates multiple order to identify, select, prioritize and pace investments. e of the DSP. Ulacement and run-to-failure. A small number of ment based on cost and expected remaining life. The ted on a one for one basis and no changes to the de. project is related to the upgraded infrastructure being ensures that proper clearances, spacing, protective emented which are more easily accessed and operated		
Efficiency, Customer Value & Reliabil Project Drivers Investment Priority Project Alternatives Operational Benefits Reliability Benefits	lity The primary driver for this project is th transformers. Secondary drivers are th ERTH Power implements a software ba projects based on weighted criteria in or This process is detailed in Section 5.4.2 The alternative to refurbishment is rep transformers are selected for refurbish majority of refurbishments are compled distribution system as a whole are made The largest operational benefit of this process and other equipment are impled by operations staff. The completion of the project will upge provide a more reliable system simply assets.	e extension of the working life of pad-mounted e improvement in appearance of this equipment. ased Investment Optimizer, which evaluates multiple order to identify, select, prioritize and pace investments. e of the DSP. alacement and run-to-failure. A small number of ment based on cost and expected remaining life. The ted on a one for one basis and no changes to the de. project is related to the upgraded infrastructure being ensures that proper clearances, spacing, protective emented which are more easily accessed and operated rade the existing aged assets as required and in turn based on the installation of upgraded distribution		
Efficiency, Customer Value & Reliabil Project Drivers Investment Priority Project Alternatives Operational Benefits Reliability Benefits Customer Benefits	lity The primary driver for this project is the transformers. Secondary drivers are the ERTH Power implements a software base projects based on weighted criteria in or This process is detailed in Section 5.4.2 The alternative to refurbishment is rep transformers are selected for refurbish majority of refurbishments are compled distribution system as a whole are made The largest operational benefit of this process and other equipment are impled by operations staff. The completion of the project will upgress provide a more reliable system simply assets. The benefits to customers resulting from from the upgrade in distribution assets current design standards. This will provise	e extension of the working life of pad-mounted e improvement in appearance of this equipment. ased Investment Optimizer, which evaluates multiple order to identify, select, prioritize and pace investments. e of the DSP. alacement and run-to-failure. A small number of ment based on cost and expected remaining life. The ted on a one for one basis and no changes to the de. project is related to the upgraded infrastructure being ensures that proper clearances, spacing, protective emented which are more easily accessed and operated rade the existing aged assets as required and in turn based on the installation of upgraded distribution		
Efficiency, Customer Value & Reliabil Project Drivers Investment Priority Project Alternatives Operational Benefits Reliability Benefits Customer Benefits	lity The primary driver for this project is the transformers. Secondary drivers are the ERTH Power implements a software bas projects based on weighted criteria in This process is detailed in Section 5.4.2 The alternative to refurbishment is reptransformers are selected for refurbish majority of refurbishments are compled distribution system as a whole are maded. The largest operational benefit of this process and other equipment are impleted by operations staff. The completion of the project will upgr provide a more reliable system simply assets. The benefits to customers resulting from the upgrade in distribution assets current design standards. This will provide a more reliable system simply assets.	e extension of the working life of pad-mounted e improvement in appearance of this equipment. ased Investment Optimizer, which evaluates multiple order to identify, select, prioritize and pace investments. e of the DSP. alacement and run-to-failure. A small number of iment based on cost and expected remaining life. The ted on a one for one basis and no changes to the de. project is related to the upgraded infrastructure being ensures that proper clearances, spacing, protective emented which are more easily accessed and operated rade the existing aged assets as required and in turn based on the installation of upgraded distribution om the completion of a system renewal project arise is that align with the long term plan for the system to yide an increase in safety to the public and more reliable		

.

	system that is much more cost effective to operate due to improved equipment, access and a reduction in line losses.
Safety	
	All system renewal projects result in an upgrade to the existing distribution assets which will provide a greater deal of both customer and worker safety simply based on the reduced risk of equipment failure and construction to current standards.
Cyber-Security, Privacy	Not applicable to this project
<u>Co-ordination, Interoperability</u>	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH Power considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
<u>Environmental Benefits</u>	System Renewal projects implement the use of the most current equipment which comply with much more stringent environmental requirements than existing infrastructure such as current transformer insulating fluids and pole treatment methods.
	Category Specific Requirements
	category specific requirements
<u>System Renewal Project</u> Asset Condition Relative to Typical Life Cycle	Assets refurbished under this project are not at their end of life. The goal of the program is to extend the useful life of pad-mounted equipment.
System Renewal Project Asset Condition Relative to Typical Life Cycle Number of Customers in Each Class Potentially Affected	Assets refurbished under this project are not at their end of life. The goal of the program is to extend the useful life of pad-mounted equipment. Transformer replacements as identified by inspection and reactive replacements due to failure can affect a wide range of customers including residential, commercial and industrial. This can include hospitals, large manufacturing facilities and other important loads depending on the location of the required replacement. Transformer failures can result in large outages affecting entire feeders depending on the severity. Since the transformers replaced under this program have been identified through inspection as not yet end of life but needing immediate attention, the probability of a failure is much more likely as compared to typical useful life approximations.
System Renewal Project Asset Condition Relative to Typical Life Cycle Number of Customers in Each Class Potentially Affected Quantitative Customer Impacts	Assets refurbished under this project are not at their end of life. The goal of the program is to extend the useful life of pad-mounted equipment. Transformer replacements as identified by inspection and reactive replacements due to failure can affect a wide range of customers including residential, commercial and industrial. This can include hospitals, large manufacturing facilities and other important loads depending on the location of the required replacement. Transformer failures can result in large outages affecting entire feeders depending on the severity. Since the transformers replaced under this program have been identified through inspection as not yet end of life but needing immediate attention, the probability of a failure is much more likely as compared to typical useful life approximations. If the transformers identified through the inspection program are not repaired, it is likely that an afterhours, unplanned replacement would be required at some point. Depending on the severity of the failure, a large feeder outage could be expected with an extended duration. In contrast, a planned refurbishment can typically be completed with minimal to no outages to customers.
System Renewal Project Asset Condition Relative to Typical Life Cycle Number of Customers in Each Class Potentially Affected Quantitative Customer Impacts Qualitative Customer Impacts	Assets refurbished under this project are not at their end of life. The goal of the program is to extend the useful life of pad-mounted equipment. Transformer replacements as identified by inspection and reactive replacements due to failure can affect a wide range of customers including residential, commercial and industrial. This can include hospitals, large manufacturing facilities and other important loads depending on the location of the required replacement. Transformer failures can result in large outages affecting entire feeders depending on the severity. Since the transformers replaced under this program have been identified through inspection as not yet end of life but needing immediate attention, the probability of a failure is much more likely as compared to typical useful life approximations. If the transformers identified through the inspection program are not repaired, it is likely that an afterhours, unplanned replacement would be required at some point. Depending on the severity of the failure, a large feeder outage could be expected with an extended duration. In contrast, a planned refurbishment can typically be completed with minimal to no outages to customers. This program is aimed at maintaining system reliability and public safety by refurbishing transformers that are reaching end of life at an accelerated rate. This will ensure that current customer satisfaction levels are maintained.
System Renewal Project Asset Condition Relative to Typical Life Cycle Number of Customers in Each Class Potentially Affected Quantitative Customer Impacts Qualitative Customer Impacts Value of Customer Impact	Assets refurbished under this project are not at their end of life. The goal of the program is to extend the useful life of pad-mounted equipment. Transformer replacements as identified by inspection and reactive replacements due to failure can affect a wide range of customers including residential, commercial and industrial. This can include hospitals, large manufacturing facilities and other important loads depending on the location of the required replacement. Transformer failures can result in large outages affecting entire feeders depending on the severity. Since the transformers replaced under this program have been identified through inspection as not yet end of life but needing immediate attention, the probability of a failure is much more likely as compared to typical useful life approximations. If the transformers identified through the inspection program are not repaired, it is likely that an afterhours, unplanned replacement would be required at some point. Depending on the severity of the failure, a large feeder outage could be expected with an extended duration. In contrast, a planned refurbishment can typically be completed with minimal to no outages to customers. This program is aimed at maintaining system reliability and public safety by refurbishing transformers that are reaching end of life at an accelerated rate. This will ensure that current customer satisfaction levels are maintained.
System Renewal Project Asset Condition Relative to Typical Life Cycle Number of Customers in Each Class Potentially Affected Quantitative Customer Impacts Qualitative Customer Impacts Value of Customer Impact	Assets refurbished under this project are not at their end of life. The goal of the program is to extend the useful life of pad-mounted equipment. Transformer replacements as identified by inspection and reactive replacements due to failure can affect a wide range of customers including residential, commercial and industrial. This can include hospitals, large manufacturing facilities and other important loads depending on the location of the required replacement. Transformer failures can result in large outages affecting entire feeders depending on the severity. Since the transformers replaced under this program have been identified through inspection as not yet end of life but needing immediate attention, the probability of a failure is much more likely as compared to typical useful life approximations. If the transformers identified through the inspection program are not repaired, it is likely that an afterhours, unplanned replacement would be required at some point. Depending on the severity of the failure, a large feeder outage could be expected with an extended duration. In contrast, a planned refurbishment can typically be completed with minimal to no outages to customers. This program is aimed at maintaining system reliability and public safety by refurbishing transformers that are reaching end of life at an accelerated rate. This will ensure that current customer satisfaction levels are maintained. The refurbishment program can affect all customer classes depending on the transformers that are identified as requiring refurbishment. As previously mentioned the risk of failure is much higher since the transformers have been identified through inspection as requiring

.

	attention and an unplanned replacement due to failure can result in a larger outage with a greater duration.
Other Factors Affecting Project Timing	Due to the nature of the project and condition of the assets identified, this program must be completed on a yearly basis.
Consequences for System O&M Costs	The largest consequence for system O&M costs is the resulting unplanned transformer replacements that are likely if the program is not completed. This results in larger outage for customers and higher costs.
Reliability and Safety Factors	The transformers identified are at not their end of life but would otherwise require expedient replacement to avoid any reliability and safety concerns.
Analysis of Project Benefits & Timing	The timing of the project is based on need as determined through inspections. Transformers are selected such that the repairs significantly increase the expected life of the unit with an aim of maximizing cost savings as compared to replacement.
Like for Like Renewal Analysis	Transformers are selected based on their compatibility with current standards.



	2025 - Project Assessme	ant Form		
ERTH Project Name	ALL-UNPLND-Unplanned Capital Projects		Municipality Cost Category Project Type	All Capital Enhancement
	General Informati	on		
Project Description	This project budget is allocated for unplanned capital expenditures that come up within a given year and have not been budgeted for. The majority of this spending includes items such as transformer/cable replacements, MVA's (motor vehicle accidents) and storm damage and are typically associated with asset replacement (System Renewal).			
Investment Category	System Renewal			
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$175,000 \$0 \$175,000 \$0		
Customer Information	Number of Customer Attachments Customer Load (if available)	Varies Varies		
Expected Project Timing	Start Date End Date	Q1 Q4		
Expected Expenditure Timing	Q1 Q2 Q3 Q4	25% 25% 25% 25%		
Risks and Mitigation	The risks and mitigations measures for this budget are difficult to predict based on the nature of the project.			
Comparative Information	2024: In Progress - \$175,000 Budgeted 2023: \$275,126 2022: \$295,195 2021: \$376,395 2020: \$275,126			
REG Investment	This project is not associated with a REG investment			
Leave to Construct Approval	This project does not require Leave to Construct approval under section 92 of the OEB Act			
Evaluation Criteria & Information Requirements				
Efficiency, Customer Value & Reliability Project Drivers The drivers for this budget are difficult to predict based on the nature of the project, however the majority are based on asset failure and external factors such as MVA's and weather.				
Investment Priority	The projects typically encompassed by this budget are high priority and usually considered mandatory.			
Project Alternatives	The majority of spending that falls within this budget does not have any alternatives. With that being said each situation is examined by engineering and operations staff to ensure the best decision is made.			
1	ALL-UNPLND-Unplanned Capit	al Projects		

Operational Benefits	Not applicable
Reliability Benefits	Not applicable
Customer Benefits	Not applicable
Safety	Not applicable
Cyber-Security, Privacy	Not applicable
Co-ordination, Interoperability	Not applicable
Economic Development	Not applicable
Environmental Benefits	Not applicable
	Category Specific Requirements
System Renewal Project	
Asset Condition Relative to Typical Life Cycle	Typically the condition of the assets replaced under this budget will be at their end of life, since they are replaced based on a failure. Other investments under this budget such as storm damage and MVA's can vary and are difficult to predict.
Number of Customers in Each Class Potentially Affected	Varies
Quantitative Customer Impacts	Not applicable
Qualitative Customer Impacts	Not applicable
Value of Customer Impact	Not applicable
Other Factors Affecting Project Timing	Not applicable
Consequences for System O&M Costs	Not applicable
Reliability & Safety Factors	Not applicable
Analysis of Project Benefits & Timing	Not applicable
Like for Like Renewal Analysis	Not applicable



AYL-OHCONV-Parkview Heights

Investment Category	System Renewal		
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$470,000 \$0 \$470,000 \$0	
Customer Information	Number of Customer Attachments	Approx. 100 Residential	
Expected Project Timing	Start Date End Date	Q1 Q3	
Expected Expenditure Timing	Q1 Q2 Q3 Q4	10% 50% 40% 0%	
Risks and Mitigation	This project involves the installation of infrastructure components such as poles, transformers, and junctions, which will alter the visual landscape of the area. These changes may raise concerns among local residents. To mitigate this risk, ERTH Power will leverage its extensive experience in customer communication, proactively engaging with the community to explain the necessity of the installations. This approach helps to address concerns and fosters a clearer understanding of the project's objectives, minimizing potential resistance and ensuring smoother project execution.		
Comparative Information	ERTH Power completes various projects throughout a given year and possesses a great deal of expertise with regards to budgeting, design, planning and construction of OH and UG rebuilds and is continually improving its processes to ensure projects are completed as efficiently as possible.		
REG Investment	This project is not associated with a REG investment		
Leave to Construct Approval	This project does not require Leave to Construct approval under section 92 of the OEB Act		
	Evaluation Criteria & Information Requirements		
Efficiency, Customer Value & Reliab	<u>ility</u>		
Project Drivers	The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system and enhancing overall service quality.		
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.		
Project Alternatives	N/A		
Operational Benefits	The completion of the voltage conversion project to 28kV will enhance system flexibility by improving switching operations during outages and facilitating load shifting. This conversion aligns with current infrastructure standards, ensuring the installation of appropriate		
2	AYL-OHCONV-Parkview He	ights	

3	AYL-OHCONV-Parkview Heights
Environmental Benefits	
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
	This project does not apply to the regional infrastructure planning framework.
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the GSC Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
<u>Cyber-Security, Privacy</u>	Not applicable to this project
<u>Safety</u>	All system renewal projects involve upgrading existing distribution assets, which significantly enhances safety for both customers and workers. By replacing outdated infrastructure with modern equipment constructed to current standards, the risk of equipment failure is greatly reduced. These upgrades not only mitigate potential safety hazards but also ensure that the system adheres to the latest clearance and material standards. This leads to a safer system, reducing the likelihood of accidents and enhancing overall public safety.
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.
	clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost- effectiveness by modernizing infrastructure and optimizing operational practices.

Voltage conversion projects reduce distribution line losses, lowering overall power consumption. They also upgrade infrastructure by incorporating modern equipment that meets stricter environmental standards, such as advanced transformer insulating fluids and improved pole treatment methods.

Category Specific Requirements

<u>System Renewal Project</u> Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 100 residential
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.



	<u> 2025 - Pro</u>	oject Assessme	nt Form		
ERIH Project Name	AYL-OHCONV-South S	St E		Municipality Cost Category Project Type	Aylmer Capital Enhancement
	Gen	eral Information	on		
Project Description	This project will conv driver for this project replacement of aging	ert the area of So is voltage conve assets and oper	outh St E from 4k rsion. The secon bus secondary,	<pre><v dary="" driver="" for="" improving="" pre="" preferred="" system<="" the="" this="" to=""></v></pre>	27.6kV. The primary project is the reliability in the area.
Preliminary Project Information	Age of Plant: Primary Voltage: Pole Type: Area Description:	>50 years 4kV Wood Residential	Constru Pri Secor	action Standards: mary Conductor: ndary Conductor: Volume:	Legacy 1/0 ACSR Open Bus Low
Asset Condition Issues	Rotten Poles Broken Equipment Revitalization Direct Buried Cable TX Base Backyard	⊠ □ Road □ Si □	PCB's Clearances Construction ubmersible TX Grounding Access	□ Op □ C □ 5kV U(□ Po □ Meter ⊠ Str	een Bus ⊠ apacity ⊠ 6 Cable □ letrans □ Access □ uctural □
4 28 38 42 44 27 33 37 41 43	48 86 49 49 49 49 49 40 40 40 40 40 40 40 40 40 40	64 68 63 65 67	72 78 69 71 79	82 88 92 83 81 91	96 100 104 10 95 102 105 10
50 10 ⁸³	South Street I	East	A093	A092	
4 50 3	1434 50 50 60 AO510 2257 109 55 55	64 66 68 70 61 63	72 76 78 80 69 75 81 83	50 84 88 92 8 85 87 89	96 100 104 106 95 101 103
Investment Category	System Renewal				
Capital Investment Customer Information	Gross Capital Customer Contributic Net Capital O&M Costs (if applica Number of Customer	on able) Attachments	\$220,000 \$0 \$220,000 \$0 Approx. 50 Re	sidential	
1	AYL-OI	HCONV-South St	E		

Expected Project Timing	Start Date End Date	Q1 Q3	
Expected Expenditure Timing	Q1 Q2 Q3 Q4	10% 50% 40% 0%	
Risks and Mitigation	This project involves the installation of infrastructure components such as poles, transformers, and junctions, which will alter the visual landscape of the area. These changes may raise concerns among local residents. To mitigate this risk, ERTH Power will leverage its extensive experience in customer communication, proactively engaging with the community to explain the necessity of the installations. This approach helps to address concerns and fosters a clearer understanding of the project's objectives, minimizing potential resistance and ensuring smoother project execution.		
Comparative Information	ERTH Power completes various projects throughout a given year and possesses a great deal of expertise with regards to budgeting, design, planning and construction of OH and UG rebuilds and is continually improving its processes to ensure projects are completed as efficiently as possible.		
REG Investment	This project is not associated with a RE	EG investment	
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act	
	Evaluation Criteria & Information	n Requirements	
Efficiency, Customer Value & Reliabi	lity		
Project Drivers	The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system and enhancing overall service quality.		
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.		
Project Alternatives	N/A		
Operational Benefits	The completion of the voltage conversion project to 28kV will enhance system flexibility by improving switching operations during outages and facilitating load shifting. This conversion aligns with current infrastructure standards, ensuring the installation of appropriate clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost-effectiveness by modernizing infrastructure and optimizing operational practices.		
Reliability Benefits	This project's conversion of the area to reliability by providing greater flexibilit outage durations, as operators will be	o a 28kV distribution system will significantly enhance ty for switching operations. This flexibility will reduce able to more efficiently isolate faults and reroute	

AYL-OHCONV-South St E

	power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	
	All system renewal projects involve upgrading existing distribution assets, which significantly enhances safety for both customers and workers. By replacing outdated infrastructure with modern equipment constructed to current standards, the risk of equipment failure is greatly reduced. These upgrades not only mitigate potential safety hazards but also ensure that the system adheres to the latest clearance and material standards. This leads to a safer system, reducing the likelihood of accidents and enhancing overall public safety.
Cyber-Security, Privacy	Not applicable to this project
Co-ordination, Interoperability	
	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the GSC Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
Environmental Benefits	
	Voltage conversion projects reduce distribution line losses, lowering overall power consumption. They also upgrade infrastructure by incorporating modern equipment that meets stricter environmental standards, such as advanced transformer insulating fluids and improved pole treatment methods.
	Category Specific Requirements
System Renewal Project	
3	AYL-OHCONV-South St E

Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 50 residential
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M	
Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Costs Reliability & Safety Factors	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify. This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Costs Reliability & Safety Factors Analysis of Project Benefits & Timing	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify. This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS. ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.



Investment Category	System Renewal			
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$100,000 \$0 \$100,000 \$0		
Customer Information	Number of Customer Attachments	Approx. 15 Residential, 5 Commercial		
Expected Project Timing	Start Date End Date	Q2 Q3		
Expected Expenditure Timing	Q1 Q2 Q3 Q4	90% 10% 0% 0%		
Risks and Mitigation	This project involves the installation of infrastructure components such as poles, transformers, and junctions, which will alter the visual landscape of the area. These changes may raise concerns among local residents. To mitigate this risk, ERTH Power will leverage its extensive experience in customer communication, proactively engaging with the community to explain the necessity of the installations. This approach helps to address concerns and fosters a clearer understanding of the project's objectives, minimizing potential resistance and ensuring smoother project execution.			
Comparative Information	ERTH Power completes various projects throughout a given year and possesses a great deal of expertise with regards to budgeting, design, planning and construction of OH and UG rebuilds and is continually improving its processes to ensure projects are completed as efficiently as possible.			
REG Investment	This project is not associated with a RI	EG investment		
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act		
Evaluation Criteria & Information Requirements				
Efficiency, Customer Value & Reliab	Dility The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system and enhancing overall service quality.			
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.			
Project Alternatives	N/A			
Operational Benefits	The completion of the voltage conversimproving switching operations during aligns with current infrastructure stan	sion project to 28kV will enhance system flexibility by goutages and facilitating load shifting. This conversion dards, ensuring the installation of appropriate		
2	CLI-OHCONV-Albert St Al	ley		
	clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost- effectiveness by modernizing infrastructure and optimizing operational practices.			
--	---			
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.			
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.			
<u>Safety</u>	This project will improve health and safety by removing aging copper primary conductors, which have become brittle and prone to failure. The replacement of these conductors will reduce the risk of downed hydro lines, particularly during adverse weather conditions, thereby enhancing the safety of both the public and utility workers. Upgrading to materials that are more durable will not only improve system reliability but also significantly mitigate potential safety hazards associated with failing infrastructure.			
Cyber-Security, Privacy	Not applicable to this project			
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the Grid Smart City Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.			
	This project does not apply to the regional infrastructure planning framework.			
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.			
<u>Economic Development</u>	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.			

CLI-OHCONV-Albert St Alley

Environmental Benefits	
	consumption. They also upgrade infrastructure by incorporating modern equipment that meets stricter environmental standards, such as advanced transformer insulating fluids and improved pole treatment methods.
	Category Specific Requirements
<u>System Renewal Project</u> Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 15 residential and 5 Commercial
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.



GDE-OHCONV-Blake & Gibbons

Investment Category	System Renewal	
Capital Investment	Gross Capital	\$160,000
	Customer Contribution	\$0
	Net Capital	\$160,000
	O&M Costs (if applicable)	\$0
Customer Information	Number of Customer Attachments	Approx. 20 Residential, 2 C&I
Expected Project Timing	Start Date	Q1
	End Date	Q2
Expected Expenditure Timing	Q1	70%
	Q2	30%
	Q3	0%
	Q4	0%
Risks and Mitigation	This project is driven by a third-party limited control over project timelines developer's part can affect the utility maintains proactive and frequent cor changes or delays. However, despite control, which may result in timeline	development, which presents a risk due to the utility's b. Delays or extended periods of inactivity on the 's schedule. To mitigate these risks, ERTH Power nmunication with developers to stay informed of any these efforts, certain factors remain outside the utility's adjustments.
Comparative Information	ERTH Power completes various proje expertise with regards to budgeting, and is continually improving its proce possible.	cts throughout a given year and possesses a great deal of design, planning and construction of OH and UG rebuilds esses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a F	REG investment
Leave to Construct Approval	This project does not require Leave to	o Construct approval under section 92 of the OEB Act
	Evaluation Criteria & Information	on Requirements
Efficiency, Customer Value & Relia	ability	
Project Drivers	The primary driver for this project is to development activities. In most cases of-life assets as justified in the Asset needs and asset management object improvements are made in line with sustainability goals.	to accommodate servicing requirements dictated by s, this initiative also aligns with the replacement of end- Management Plan. By addressing both development ives, the project ensures that infrastructure both immediate servicing demands and long-term asset
Investment Priority	ERTH Power implements a software b projects based on weighted criteria ir This process is detailed in Section 5.4	pased Investment Optimizer which evaluates multiple n order to identify, select, prioritize and pace investments. .2 of the DSP.
Project Alternatives	N/A	
Operational Benefits	The completion of the voltage conve improving switching operations durin aligns with current infrastructure star clearances, spacing, protective device manageable for operations staff. Add elimination of ERTH Power municipal	rsion project to 28kV will enhance system flexibility by g outages and facilitating load shifting. This conversion ndards, ensuring the installation of appropriate es, and other equipment that are more accessible and litionally, the voltage conversion will lead to the substations, which will streamline operations and reduce
2	GDE-OHCONV-Blake & Gil	obons

GDE-OHCONV-Blake & Gibbons

	maintenance costs. Overall, the project enhances system efficiency, reliability, and cost- effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.
Customer Benefits	The completion of this project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	
	All system renewal projects involve upgrading existing distribution assets, which significantly enhances safety for both customers and workers. By replacing outdated infrastructure with modern equipment constructed to current standards, the risk of equipment failure is greatly reduced. These upgrades not only mitigate potential safety hazards but also ensure that the system adheres to the latest clearance and material standards. This leads to a safer system, reducing the likelihood of accidents and enhancing overall public safety.
Cyber-Security, Privacy	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the SWBG (Southwest Buying Group) which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project has been driven by the need to connect a new development. This will create a positive impact to Ontario economic growth and job creation; the exact measure of this impact is outside the expertise of ERTH Power.
<u>Environmental Benefits</u>	Voltage Conversion projects help to reduce the distribution line losses and in turn aid in the reduction of power consumption and at the same time implement the use of the most current equipment which comply with much more stringent environmental requirements than existing infrastructure such as transformer insulating fluids and pole treatment methods.

GDE-OHCONV-Blake & Gibbons

Category Specific Requirements

System Renewal Project

Potentially Affected

Asset Condition Relative to Typical Life Cycle

The condition of the assets encompassed by this project are nearing end of life but not at risk of immediate failure. The replacement is being driven by voltage conversion and the need to connect a new apartment complex in the area.

Number of Customers in Each Class 2 C&I and approx. 20 residential

Quantitative Customer Impacts Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed. By diverting this new service from the 4kV system to the more robust 28kV system, improvements in system reliability and power quality are expected for the 4kV customers in the area.

Qualitative Customer ImpactsMore frequent and extended outages will result in reduced customer satisfaction. The
completion of the project will divert load from the station.

Value of Customer ImpactThis particular project indirectly affects a large number of customers connected to the 4kV
system, which is nearing its end of life and needs to have load removed from it.

Other Factors Affecting ProjectSince this project is primarily to accommodate connection of a new customer, their progress
can affect project timelines. This is mitigated through good communication with the
developer. In this case, we have been assured that we will have ample time to complete the
project as planned.

Consequences for System O&MIf this project and other system renewal projects are not completed O&M will drasticallyCostsincrease over time as asset failure will result in costly unplanned repairs. At this time specific
O&M consequences are difficult to quantify.

affects a large number of customers by reducing load on the DS.

investments. This process is detailed in Section 5.4.2 of the DSP.

This project does not directly address any reliability or safety factors however indirectly

ERTH Power implements a software based Investment Optimizer which evaluates multiple

This project will be a like-for-like replacement aside from the voltage conversion aspects.

projects based on weighted criteria in order to identify, select, prioritize and pace

Reliability & Safety Factors

Analysis of Project Benefits & Timing

Like for Like Renewal Analysis



Investment Category	System Renewal	
Capital Investment	Gross Capital Customer Contribution	\$125,000 \$0
	Net Capital	\$125,000
	O&M Costs (if applicable)	\$0
Customer Information	Number of Customer Attachments	Various commercial (park lights, amenities)
Expected Project Timing	Start Date	Q2
	End Date	Q3
Expected Expenditure Timing	Q1	0%
	03	40%
	Q4	0%
Risks and Mitigation	This project involves the installation of and junctions, which will alter the visu concerns among local residents. To m experience in customer communication the necessity of the installations. This understanding of the project's objection smoother project execution.	of infrastructure components such as poles, transformers, ual landscape of the area. These changes may raise itigate this risk, ERTH Power will leverage its extensive on, proactively engaging with the community to explain approach helps to address concerns and fosters a clearer ives, minimizing potential resistance and ensuring
Comparative Information	ERTH completes various projects thro expertise with regards to budgeting, o and is continually improving its proce possible.	ughout a given year and possesses a great deal of design, planning and construction of OH and UG rebuilds sses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a R	EG investment
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act
	Evaluation Criteria & Informatio	n Requirements
Efficiency, Customer Value & Reliab	Dility The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system	
	and enhancing overall service quality.	
Investment Priority	ERTH Power implements a software b projects based on weighted criteria in This process is detailed in Section 5.4.	ased Investment Optimizer which evaluates multiple order to identify, select, prioritize and pace investments. 2 of the DSP.
Project Alternatives	No other alternative have been consid	dered
Operational Benefits	The completion of the voltage conversion project to 28kV will enhance system flexibility by improving switching operations during outages and facilitating load shifting. This conversion aligns with current infrastructure standards, ensuring the installation of appropriate clearances, spacing, protective devices, and other equipment that are more accessible and	
2	ING-OHCONV-Victoria	Park 🔳 🔲 💻

	manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost-effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	
	All system renewal projects involve upgrading existing distribution assets, which significantly enhances safety for both customers and workers. By replacing outdated infrastructure with modern equipment constructed to current standards, the risk of equipment failure is greatly reduced. These upgrades not only mitigate potential safety hazards but also ensure that the system adheres to the latest clearance and material standards. This leads to a safer system, reducing the likelihood of accidents and enhancing overall public safety.
<u>Cyber-Security, Privacy</u>	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participates in the GSCC (Grid Smart City Cooperative) which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	This project does not apply to the regional infrastructure planning framework.
	ERTH communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future customer connections or load growth and addresses these with an appropriate design. System renewal projects, especially voltage conversion, will provide a distribution system more capable of connecting future customers with higher reliability.
Environmental Benefits	

ING-OHCONV-Victoria Park

System Renewal projects implement the use of the most current equipment which comply with much more stringent environmental requirements than existing infrastructure such as current transformer insulating fluids and pole treatment methods.

Category Specific Requirements

System Renewal Project Asset Condition Relative to Typical Life Cycle	The condition of the assets encompassed by this project are nearing end of life. The replacement is being driven by voltage conversion and the need to remove overhead primary from the park.
Number of Customers in Each Class Potentially Affected	Various commercial (park lights, amenities)
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed. The Mill St MS is nearing its end of life and voltage conversion is needed to extend the life of the station transformer and ensure a failure does not occur, as it would affect a large number of customers.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	This particular project indirectly affects a large number of customers connected to the Clinton DS which is nearing its end of life and need to have load removed from it.
Other Factors Affecting Project Timing	The primary factor affecting the timing of this project is the requirement to remove load from the Mill St MS.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability or safety factors however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will not be a like-for-like replacement. New infrastructure will be constructed underground. There is no practical alternative that would eliminate the safety concern from overhead primary in the park.



Investment Category	System Renewal	
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$230,000 \$0 \$230,000 \$0
Customer Information	Number of Customer Attachments	Approx. 15 Commercial
Expected Project Timing	Start Date End Date	Q2 Q3
Expected Expenditure Timing	Q1 Q2 Q3 Q4	0% 80% 20% 0%
Risks and Mitigation	This project involves the installation or and junctions, which will alter the visu concerns among local residents. To mi experience in customer communication the necessity of the installations. This understanding of the project's objective smoother project execution.	f infrastructure components such as poles, transformers, al landscape of the area. These changes may raise tigate this risk, ERTH Power will leverage its extensive on, proactively engaging with the community to explain approach helps to address concerns and fosters a clearer ves, minimizing potential resistance and ensuring
Comparative Information	ERTH Power completes various projec expertise with regards to budgeting, d and is continually improving its proces possible.	ts throughout a given year and possesses a great deal of esign, planning and construction of OH and UG rebuilds ses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a RI	EG investment
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act
Evaluation Criteria & Information Requirements		
Efficiency, Customer Value & Reliab	ility	
Project Drivers	The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system and enhancing overall service quality.	
Investment Priority	ERTH Power implements a software bar projects based on weighted criteria in This process is detailed in Section 5.4.2	ased Investment Optimizer which evaluates multiple order to identify, select, prioritize and pace investments. 2 of the DSP.
Project Alternatives	N/A	
Operational Benefits	The completion of the voltage convers improving switching operations during aligns with current infrastructure stan	sion project to 28kV will enhance system flexibility by goutages and facilitating load shifting. This conversion dards, ensuring the installation of appropriate
2	ING-UGCONV-Oxford La	ne 📕 📕 📕

	clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost- effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	This project will improve health and safety by removing aging copper primary conductors, which have become brittle and prone to failure. The replacement of these conductors will reduce the risk of downed hydro lines, particularly during adverse weather conditions, thereby enhancing the safety of both the public and utility workers. Upgrading to materials that are more durable will not only improve system reliability but also significantly mitigate potential safety hazards associated with failing infrastructure.
Cyber-Security, Privacy	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the Grid Smart City Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.

ING-UGCONV-Oxford Lane

<u>Environmental Benefits</u>	Voltage conversion projects reduce distribution line losses, lowering overall power consumption. They also upgrade infrastructure by incorporating modern equipment that meets stricter environmental standards, such as advanced transformer insulating fluids and improved pole treatment methods.
	Category Specific Requirements
<u>System Renewal Project</u> Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 15 Commercial
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.



MIT-UGCONV-Maple & St Andrews

Investment Category	System Renewal	
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$150,000 \$0 \$150,000 \$0
Customer Information	Number of Customer Attachments	Approx. 30 Residential
Expected Project Timing	Start Date End Date	Q1 Q4
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 40% 30% 10%
Risks and Mitigation	This project involves the installation of and junctions, which will alter the visu concerns among local residents. To mexperience in customer communication the necessity of the installations. This understanding of the project's object smoother project execution. The use of external contractors to inst dependence on their timelines, availa ERTH Power engages in thorough plan Additionally, relationships are establiss ERTH Power's construction standards, and within the project's schedule. This compliance with utility expectations.	f infrastructure components such as poles, transformers, ial landscape of the area. These changes may raise itigate this risk, ERTH Power will leverage its extensive on, proactively engaging with the community to explain approach helps to address concerns and fosters a clearer ves, minimizing potential resistance and ensuring call civil infrastructure introduces risks related to bility, and quality of workmanship. To mitigate this risk, ming to secure contractors early in the project timeline. shed with trusted contractors who are well versed in ensuring that work is completed to the required quality s proactive approach minimizes delays and ensures
Comparative Information	ERTH Power completes various project expertise with regards to budgeting, or and is continually improving its procest possible.	ts throughout a given year and possesses a great deal of lesign, planning and construction of OH and UG rebuilds sses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a R	EG investment
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act
	Evaluation Criteria & Informatio	n Requirements
Efficiency, Customer Value & Reliab	ility	
Project Drivers	The primary driver for this project is to preferred 28kV distribution system. Th assets as outlined in the Asset Manag replaced to meet 28kV design require distribution system's design. In the low benefits to customers, including impro- supports ERTH Power's asset manager and enhancing overall service quality.	o convert existing infrastructure to be supplied from the his conversion aligns with the replacement of end-of-life ement Plan. While some newer assets may need to be ments (such as pole heights), this is necessary due to the ng term, voltage conversion will deliver significant oved system efficiency and reliability. This project ment objectives by modernizing the distribution system

MIT-UGCONV-Maple & St Andrews

Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Project Alternatives	N/A
Operational Benefits	The completion of the voltage conversion project to 28kV will enhance system flexibility by improving switching operations during outages and facilitating load shifting. This conversion aligns with current infrastructure standards, ensuring the installation of appropriate clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost-effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	All system renewal projects involve upgrading existing distribution assets, which significantly enhances safety for both customers and workers. By replacing outdated infrastructure with modern equipment constructed to current standards, the risk of equipment failure is greatly reduced. These upgrades not only mitigate potential safety hazards but also ensure that the system adheres to the latest clearance and material standards. This leads to a safer system, reducing the likelihood of accidents and enhancing overall public safety.
Cyber-Security, Privacy	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the GSC Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power. This project does not apply to the regional infrastructure planning framework. ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.

MIT-UGCONV-Maple & St Andrews

<u>Economic Development</u>	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
<u>Environmental Benefits</u>	Voltage Conversion projects help to reduce the distribution line losses and in turn aid in the reduction of power consumption and at the same time implement the use of the most current equipment which comply with much more stringent environmental requirements than existing infrastructure such as transformer insulating fluids and pole treatment methods.
	Category Specific Requirements
System Renewal Project Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 30 residential
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.



Investment Category	System Renewal	
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$115,000 \$0 \$115,000 \$0
Customer Information	Number of Customer Attachments	Approx. 40 Residential, 2 C&I
Expected Project Timing	Start Date End Date	Q1 Q3
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 40% 40% 0%
Risks and Mitigation	This project involves the installation of and junctions, which will alter the visc concerns among local residents. To mexperience in customer communication the necessity of the installations. This understanding of the project's object smoother project execution. The use of external contractors to inside pendence on their timelines, availated ERTH Power engages in thorough plan Additionally, relationships are establisted ERTH Power's construction standards and within the project's schedule. This compliance with utility expectations.	of infrastructure components such as poles, transformers, ual landscape of the area. These changes may raise nitigate this risk, ERTH Power will leverage its extensive on, proactively engaging with the community to explain approach helps to address concerns and fosters a clearer ives, minimizing potential resistance and ensuring tall civil infrastructure introduces risks related to ability, and quality of workmanship. To mitigate this risk, nning to secure contractors early in the project timeline. shed with trusted contractors who are well versed in a ensuring that work is completed to the required quality is proactive approach minimizes delays and ensures
Comparative Information	ERTH Power completes various project expertise with regards to budgeting, of and is continually improving its procet possible.	cts throughout a given year and possesses a great deal of design, planning and construction of OH and UG rebuilds sses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a R	EG investment
Leave to Construct Approval	This project does not require Leave to	o Construct approval under section 92 of the OEB Act
	Evaluation Criteria & Informatio	on Requirements
Efficiency, Customer Value & Relia	bility The primary driver for this project is t	a convert existing infrastructure to be supplied from the
Project Drivers	preferred 28kV distribution system. T assets as outlined in the Asset Manag replaced to meet 28kV design require distribution system's design. In the lo benefits to customers, including impr supports ERTH Power's asset manage and enhancing overall service quality.	this conversion aligns with the replacement of end-of-life gement Plan. While some newer assets may need to be ements (such as pole heights), this is necessary due to the ng term, voltage conversion will deliver significant oved system efficiency and reliability. This project ment objectives by modernizing the distribution system

CLI-UGCONV-Rattenbury St E

Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Project Alternatives	N/A
Operational Benefits	The completion of the voltage conversion project to 28kV will enhance system flexibility by improving switching operations during outages and facilitating load shifting. This conversion aligns with current infrastructure standards, ensuring the installation of appropriate clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost-effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	All system renewal projects involve upgrading existing distribution assets, which significantly enhances safety for both customers and workers. By replacing outdated infrastructure with modern equipment constructed to current standards, the risk of equipment failure is greatly reduced. These upgrades not only mitigate potential safety hazards but also ensure that the system adheres to the latest clearance and material standards. This leads to a safer system, reducing the likelihood of accidents and enhancing overall public safety.
Cyber-Security, Privacy	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the GSC Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power. This project does not apply to the regional infrastructure planning framework. ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.

CLI-UGCONV-Rattenbury St E

Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
<u>Environmental Benefits</u>	Voltage Conversion projects help to reduce the distribution line losses and in turn aid in the reduction of power consumption and at the same time implement the use of the most current equipment which comply with much more stringent environmental requirements than existing infrastructure such as transformer insulating fluids and pole treatment methods.
	Category Specific Requirements
System Renewal Project Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 40 Residential, 2 C&I
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.



Investment Category	System Renewal	
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$185,000 \$0 \$185,000 \$0
Customer Information	Number of Customer Attachments	Approx. 30 Residential
Expected Project Timing	Start Date End Date	Q1 Q4
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 40% 30% 10%
Risks and Mitigation	This project involves the installation of infrastructure components such as poles, transformers, and junctions, which will alter the visual landscape of the area. These changes may raise concerns among local residents. To mitigate this risk, ERTH Power will leverage its extensive experience in customer communication, proactively engaging with the community to explain the necessity of the installations. This approach helps to address concerns and fosters a clearer understanding of the project's objectives, minimizing potential resistance and ensuring smoother project execution.	
Comparative Information	ERTH Power completes various projec expertise with regards to budgeting, d and is continually improving its proces possible.	ts throughout a given year and possesses a great deal of lesign, planning and construction of OH and UG rebuilds sses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a RI	EG investment
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act
Evaluation Criteria & Information Requirements		
Efficiency, Customer Value & Reliab	Dility The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system and enhancing overall service quality.	
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.	
Project Alternatives	N/A	
Operational Benefits	The completion of the voltage converse improving switching operations during aligns with current infrastructure stan	sion project to 28kV will enhance system flexibility by g outages and facilitating load shifting. This conversion dards, ensuring the installation of appropriate
2	MIT-UGCONV-St David	St St

	clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost- effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	All system renewal projects involve upgrading existing distribution assets, which significantly enhances safety for both customers and workers. By replacing outdated infrastructure with modern equipment constructed to current standards, the risk of equipment failure is greatly reduced. These upgrades not only mitigate potential safety hazards but also ensure that the system adheres to the latest clearance and material standards. This leads to a safer system, reducing the likelihood of accidents and enhancing overall public safety.
Cyber-Security, Privacy	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the GSC Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	
	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
Environmental Benefits	

MIT-UGCONV-St David St

Voltage Conversion projects help to reduce the distribution line losses and in turn aid in the reduction of power consumption and at the same time implement the use of the most current equipment which comply with much more stringent environmental requirements than existing infrastructure such as transformer insulating fluids and pole treatment methods.

Category Specific Requirements

System Renewal Project Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 30 residential
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.



PTS-OHCONV-Walnut St

Investment Category	System Renewal	
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$150,000 \$0 \$150,000 \$0
Customer Information	Number of Customer Attachments	Approx. 45 Residential
Expected Project Timing	Start Date End Date	Q2 Q3
Expected Expenditure Timing	Q1 Q2 Q3 Q4	0% 90% 10% 0%
Risks and Mitigation	This project involves the installation of and junctions, which will alter the visu concerns among local residents. To mi experience in customer communicatio the necessity of the installations. This understanding of the project's objective smoother project execution.	f infrastructure components such as poles, transformers, al landscape of the area. These changes may raise tigate this risk, ERTH Power will leverage its extensive on, proactively engaging with the community to explain approach helps to address concerns and fosters a clearer ves, minimizing potential resistance and ensuring
Comparative Information	ERTH Power completes various project expertise with regards to budgeting, d and is continually improving its proces possible.	ts throughout a given year and possesses a great deal of esign, planning and construction of OH and UG rebuilds ses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a RI	EG investment
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act
Evaluation Criteria & Information Requirements		
Efficiency, Customer Value & Reliabi Project Drivers	<u>Ility</u> The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system and enhancing overall service quality.	
Investment Priority	ERTH Power implements a software ba projects based on weighted criteria in This process is detailed in Section 5.4.2	ased Investment Optimizer which evaluates multiple order to identify, select, prioritize and pace investments. 2 of the DSP.
Project Alternatives	N/A	
Operational Benefits	The completion of the voltage conversion project to 28kV will enhance system flexibility by improving switching operations during outages and facilitating load shifting. This conversion aligns with current infrastructure standards, ensuring the installation of appropriate clearances, spacing, protective devices, and other equipment that are more accessible and	
2	PTS-OHCONV-Walnut S	t 🗾 📕 📕

	manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost-effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	
	This project will improve health and safety by removing aging copper primary conductors, which have become brittle and prone to failure. The replacement of these conductors will reduce the risk of downed hydro lines, particularly during adverse weather conditions, thereby enhancing the safety of both the public and utility workers. Upgrading to materials that are more durable will not only improve system reliability but also significantly mitigate potential safety hazards associated with failing infrastructure.
Cyber-Security, Privacy	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the Grid Smart City Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.
Environmental Benefits	

PTS-OHCONV-Walnut St

Voltage conversion projects reduce distribution line losses, lowering overall power consumption. They also upgrade infrastructure by incorporating modern equipment that meets stricter environmental standards, such as advanced transformer insulating fluids and improved pole treatment methods.

Category Specific Requirements

<u>System Renewal Project</u> Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.
Number of Customers in Each Class Potentially Affected	Approx. 45 residential
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.
Other Factors Affecting Project Timing	Not applicable.
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.



Investment Category	System Renewal	
Capital Investment	Gross Capital Customer Contribution Net Capital O&M Costs (if applicable)	\$300,000 \$0 \$300,000 \$0
Customer Information	Number of Customer Attachments	Approx. 65 Residential
Expected Project Timing	Start Date End Date	Q2 Q4
Expected Expenditure Timing	Q1 Q2 Q3 Q4	0% 30% 50% 20%
Risks and Mitigation	This project involves the installation of infrastructure components such as poles, transformers, and junctions, which will alter the visual landscape of the area. These changes may raise concerns among local residents. To mitigate this risk, ERTH Power will leverage its extensive experience in customer communication, proactively engaging with the community to explain the necessity of the installations. This approach helps to address concerns and fosters a clearer understanding of the project's objectives, minimizing potential resistance and ensuring smoother project execution.	
Comparative Information	ERTH Power completes various projec expertise with regards to budgeting, d and is continually improving its proces possible.	ts throughout a given year and possesses a great deal of esign, planning and construction of OH and UG rebuilds ses to ensure projects are completed as efficiently as
REG Investment	This project is not associated with a R	EG investment
Leave to Construct Approval	This project does not require Leave to	Construct approval under section 92 of the OEB Act
Evaluation Criteria & Information Requirements		
Efficiency, Customer Value & Reliability		
Project Drivers	The primary driver for this project is to convert existing infrastructure to be supplied from the preferred 28kV distribution system. This conversion aligns with the replacement of end-of-life assets as outlined in the Asset Management Plan. While some newer assets may need to be replaced to meet 28kV design requirements (such as pole heights), this is necessary due to the distribution system's design. In the long term, voltage conversion will deliver significant benefits to customers, including improved system efficiency and reliability. This project supports ERTH Power's asset management objectives by modernizing the distribution system and enhancing overall service quality.	
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.	
Project Alternatives	N/A	
Operational Benefits	The completion of the voltage conversion project to 28kV will enhance system flexibility by improving switching operations during outages and facilitating load shifting. This conversion aligns with current infrastructure standards, ensuring the installation of appropriate	
2	TAV-OHCONV-Wellingtor	st 🔳 🔳 📕

	clearances, spacing, protective devices, and other equipment that are more accessible and manageable for operations staff. Additionally, the voltage conversion will lead to the elimination of ERTH Power municipal substations, which will streamline operations and reduce maintenance costs. Overall, the project enhances system efficiency, reliability, and cost- effectiveness by modernizing infrastructure and optimizing operational practices.
Reliability Benefits	This project's conversion of the area to a 28kV distribution system will significantly enhance reliability by providing greater flexibility for switching operations. This flexibility will reduce outage durations, as operators will be able to more efficiently isolate faults and reroute power. Once the system is standardized to a single distribution voltage, overall reliability will improve, resulting in fewer and shorter outages. This modernization reduces complexity in operations and maintenance, further enhancing the system's performance and ensuring more consistent and reliable service to customers.
Customer Benefits	The completion of this system renewal project will provide significant benefits to customers by upgrading distribution assets in line with the long-term plan and current design standards. These upgrades will enhance public safety, reduce the risk of equipment failure, and increase system reliability. The modernization of infrastructure will also lead to more cost-effective operations through improved equipment, easier access for maintenance, and a reduction in line losses. Collectively, these improvements will result in lower operational costs and fewer service interruptions, delivering both immediate and long-term benefits to customers.
<u>Safety</u>	This project will improve health and safety by removing aging copper primary conductors, which have become brittle and prone to failure. The replacement of these conductors will reduce the risk of downed hydro lines, particularly during adverse weather conditions, thereby enhancing the safety of both the public and utility workers. Upgrading to materials that are more durable will not only improve system reliability but also significantly mitigate potential safety hazards associated with failing infrastructure.
<u>Cyber-Security, Privacy</u>	Not applicable to this project
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participate in the Grid Smart City Buying Group which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	This project does not apply to the regional infrastructure planning framework.
	ERTH Power communicates its projects with the required third parties to properly coordinate all work and gain efficiencies if possible.
Economic Development	This project does not directly relate to any economic growth however with any system renewal ERTH considers any future potential for customer connections or load growth and addresses these with an appropriate design. System renewal projects especially voltage conversion will provide a distribution system more capable of connecting future customers with higher reliability.

TAV-OHCONV-Wellington St

<u>Environmental Benefits</u>	Voltage conversion projects reduce distribution line losses, lowering overall power consumption. They also upgrade infrastructure by incorporating modern equipment that meets stricter environmental standards, such as advanced transformer insulating fluids and improved pole treatment methods.						
Category Specific Requirements							
<u>System Renewal Project</u> Asset Condition Relative to Typical Life Cycle	The conditions of the assets encompassed by this project are at their end of life.						
Number of Customers in Each Class Potentially Affected	Approx. 65 residential						
Quantitative Customer Impacts	Exact frequency and duration statistics are not currently known for the area; however the further deterioration of end of life assets will increase the probability that customers will experience more frequent outages if not addressed.						
Qualitative Customer Impacts	More frequent and extended outages will result in reduced customer satisfaction. The completion of the project will remove load from the station.						
Value of Customer Impact	The value of the project is difficult to isolate and quantify however achieves multiple strategic objectives including voltage conversion, enabling development etc. which overall provide a great benefit to all ERTH Power customers.						
Other Factors Affecting Project Timing	Not applicable.						
Consequences for System O&M Costs	If this project and other system renewal projects are not completed O&M will drastically increase over time as asset failure will result in costly unplanned repairs. At this time specific O&M consequences are difficult to quantify.						
Reliability & Safety Factors	This project does not directly address any reliability however indirectly affects a large number of customers by reducing load on the DS.						
Analysis of Project Benefits & Timing	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2 of the DSP.						
Like for Like Renewal Analysis	This project will be a like-for-like replacement aside from the voltage conversion aspects.						

	2025 - Project Assessment Form						
Project Name	ALL-AUTOMATION-System Automation	Municipality Cost Category Project Type	ALL Capital Enhancement				
	General Information						
Project Description	 General Information This project covers the costs associated with enhancing the performance of the distribut advanced technology-enabled devices to act an quickly detect faults and isolate outages and minimizing downtime. Faster Restoration: Utilities can rest rerouting electricity through alternatoutages. Achieved utilizing "self-heat operator functions. Increased Operational Flexibility: a about grid conditions, allowing operespond to issues proactively. Reduced Operational Costs: by aut switching, utilities save on labor, equivalent function at strategic location be dispatched or not; saving hours In addition to the objectives detailed above to support future technologies, reduced empublic safety. Over the forecast period ERTH plans to focus Smart Switches, namely G&W Viper Reclose enabled fault indicators throughout our systemation. 	automation initiatives a fon system through the i hieve the following obje tage Response: grid auto affected sections, reduc tore power more quickly ative pathways, avoiding aling" configurations or r utomated devices provid rators to make better de omating tasks like fault d uipment, and vehicle de is allows us to determine System Automation, inv vironmental impacts, inc s on the installation of R rs with SEL Relays for co tem in strategic locations	aimed at mplementation of ctives. Dmation devices cing the impact of by automatically prolonged remote controlled de real-time data cisions and letection and ployment costs. e if trucks need to restments will help rease worker, and emotely Operable ontrol and SCADA s. Due to the dis-				
	 contiguous nature of our service territory, and being embedded to Hydro One in many communities a large focus will be at our demarcation points with Hydro One. This will allow us to have real time data and determine if outages are caused by upstream Loss of Supply or within our system. This will allow us to make more informed, efficient decisions to dispatch crews, to restore outages quicker or avoid costly responses when the issue is not within our system. System Automation spending will comprise approximately 1.9% of our yearly expenditures, and plan to install on average one (1) smart switch, and 2-3 sets of fault indicators over the forecast period. 						
Investment Category	System Service						

ALL-AUTOMATION-System Automation

Capital Investment

-		Historical Expenditures						Average
		2018	2019	2020	2021	2022	2023	(2018 to 2023)
System Automation	Gross (\$)	\$58,179	\$26,011	\$0	\$6,108	\$114,378	\$95,720	\$50,066
	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	Net (\$)	\$58,179	\$26,011	\$0	\$6,108	\$114,378	\$95,720	\$50,066

		Forecast Expenditures						Average
		2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)
System Automation	Gross (\$)	\$34,800	\$120,000	\$122,400	\$124,848	\$127,345	\$129,892	\$124,897
	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	Net (\$)	\$34,800	\$120,000	\$122,400	\$124,848	\$127,345	\$129,892	\$124,897

Customer Information	Number of Customer Attachments Customer Load (if available)	ALL ALL
Expected Project Timing	Start Date End Date	Q1 Q4
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 30% 30% 20%

Risks and Mitigation

When implementing distribution system automation projects, various risks can arise, ranging from technical challenges to operational and financial concerns.

1. New Technology

- **Risk:** Integration issues with existing systems and infrastructure, such as compatibility problems between legacy equipment and new automation technologies, not all locations within our unique service territory will be able to equally utilize smart grid enabled technology. (i.e. upstream protective devices are incompatible)
- **Mitigation:** ERTH has installed five (5) automated switches and multiple SCADA enable fault indicators over the historical period and as such has developed knowledge and experience to efficiently implement new devices into the forecast period. In addition, we have paced our investment in a relatively modest fashion to ensure we are not at the "bleeding-edge" of the new technology, but in a way that allows us to learn from others and implement more known solutions.

2. Supply Chain and Vendor Risks

- **Risk**: Delays in equipment delivery or supply chain disruptions that can affect project timelines.
- **Mitigation**: work with industry groups, primarily Grid Smart City (GSC) to create standardized installations and secure group-purchasing benefits. Ensure via proper longer term planning that equipment is ordered well in advance of the project to avoid delays.

3. Cybersecurity Risks

- **Risk**: Increased exposure to cyberattacks due to the integration of communication technologies and remote access capabilities.
- Mitigation: Implement robust cybersecurity measures, and regular security audits.
| Comparative Information | As noted above, ERTH has installed five (5) automated switches and multiple SCADA enabled fault indicators. These are reflected in historical spending, however thee (3) of the switches were purchased and installed prior to the historical period. |
|-------------------------------------|---|
| REG Investment | This project is not associated with a REG investment |
| Leave to Construct Approval | This project does not require Leave to Construct approval under section 92 of the OEB Act |
| | Evaluation Criteria & Information Requirements |
| Efficiency, Customer Value & Reliab | bility |
| Project Drivers | The primary driver for all system automation type projects is to maximize operational and reliability benefits leveraging advances in distribution technology. Ultimately it will lead to reduced outage frequency and duration and will drive operational efficiency allowing the system to be monitored and controlled remotely. ERTH Power operates the distribution system spanning a large geographical area; implementation of system automation will provide real time feedback and control of the system to utilize resources more efficiently. |
| Investment Priority | ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2c) of the DSP. |
| | On a high level the alternative to investing in system automation is to do nothing and maintain the status quo. |
| Project Alternatives | Do-Nothing (Status Quo): Continue operating the current system without any upgrades or automation. The benefits of this approach would be reduced upfront costs and the avoidance of risks associated with new technology. This would however result in missed opportunities for efficiency, reliability and cost savings, that new technology can provide. ERTH evaluates each project to determine if an automated switch is suitable for the application and continues to install some manually operated devices in certain situations to balance the cost/benefit throughout our system. |
| | On a more granular level, each type of system automation solution has an alternative
manufacturer, varying capabilities and varying costs. Each solution is evaluated based on these
criteria and implemented to maximize the benefits to the distribution system in line with
customer preferences. |
| Operational Benefits | System automation enables remote operation of critical switching points, allowing staff to respond quickly to system issues rather than manually performing switching procedures. Remote monitoring devices provide real-time data, allowing ERTH Power to promptly identify and address problems. This reduces the time spent patrolling lines to locate faults and enables staff to allocate resources more efficiently to the exact location of the issue, resulting in faster restoration and enhanced operational efficiency. |
| Reliability Benefits | Automating the distribution system leads to significant improvements in reliability. It reduces outage durations by enabling quicker load transfers and better sectionalizing capabilities. In the event of faults, automation allows for more precise isolation of affected sections, limiting the number of customers impacted and improving overall system resilience. This increased reliability directly translates into better service quality and customer satisfaction. |
| Customer Benefits | Automation enhances the customer experience by minimizing both the duration and frequency of outages. The system's ability to "self-heal" through automatic fault detection and sectionalization reduces the impact on customers, ensuring fewer interruptions in service. In addition, the real-time data collected from automated systems improves communication with |

	customers, providing more accurate and timely updates during outages or system disturbances, resulting in greater transparency.
<u>Safety</u>	While system automation projects do not directly address specific safety issues, they significantly improve safety for field personnel. Remotely operated switches reduce the need for manual operations in hazardous conditions, such as during storms or fault scenarios. This limits the exposure of staff to dangerous environments, enhancing overall worker safety and reducing the likelihood of accidents or injuries.
<u>Cyber-Security, Privacy</u>	Various security and privacy measure will be implemented; ERTH Power is involved in industry working groups and will look to implement and maintain cyber security measures as they evolve within the industry.
<u>Co-ordination, Interoperability</u>	ERTH Power is a member of the USF (Utilities Standard Forum) which provides recognized construction standards to a large number of utilities throughout Ontario that have been created to maintain consistency and consider future development. ERTH Power also actively participates in the GSCC (Grid Smart City Cooperative) which is a group of utilities who come together to standardize on materials and purchasing practices to take advantage of improved purchasing power.
	System automation projects typically require very little coordination with third parties and distribution infrastructure changes (poles, lines etc.) are minimal.
Economic Development	While the project is not directly tied to economic growth, the improved reliability and efficiency of the distribution system can indirectly support the economic development of the community. With automation in place, ERTH Power will be better equipped to accommodate the growing population and business demands by ensuring consistent, high-quality power delivery to new customers. This reliability makes the area more attractive for future residential, commercial, and industrial development.
<u>Environmental Benefits</u>	Though the project's primary focus is not on environmental improvements, automation can lead to minor environmental benefits. By optimizing power distribution and reducing the need for manual field interventions, the project can decrease the use of utility vehicles, thereby slightly lowering the carbon footprint associated with system maintenance and operation. Additionally, a more reliable grid with faster restoration times reduces energy waste during outages.
	Category Specific Requirements
System Service Project Assessment of the Benefits to Customers	See Customer Benefits section above
Information Related to Regional Planning	Not applicable
Integration of Advanced Technology	All system automation projects will include the implementation of more advanced technology including switches, reclosers & fault indicators capable of remote monitoring and control through the SCADA system, as well as other software systems that will promote efficiency.
4	ALL-AUTOMATION-System Automation

System Benefits to Reliability, Efficiency and Safety	System automation will result in reduced outage duration through quicker load transfers and the ability to better sectionalize the system.
	Automating the distribution system will allow for remote operation of strategic switching points allowing staff to be directed quickly to system issues rather than switching procedures. The installation of remote monitoring equipment will provide data to ERTH Power to help identify issues and provide the ability to focus resources directly to the issue; resulting in less time patrolling lines to find issues.
	System automation type projects do not look to address specific safety issues however remotely operated switches will result in less exposure to manual switching operations which is most often done in less than favourable outage scenarios (i.e. storm & fault conditions)
Factors Affecting Implementation Timing & Priority	See Risks & Mitigation section detailed above
Alternative Solution Analysis	See Project Alternatives section detailed above

	2025 - Project Assessment Form							
P O W E R	ALL-DEVICES-IT Hardware & Software	Municipality ALL Cost Category Capital Project Type Enhancement						
	General Information							
Project Description	This project represents costs associated with upgr devices such as desktops, laptops, printers, firewa a proactive basis based on current requirements, spending related to SCADA, workstation firewall a cyber-security requirements. ERTH Power has recently created a "Digital Roadm technologies to create an interconnected and sust empower customers, optimize operations, and pa more efficient future. This involves items like digit digitized inspections, OMS system upgrades, and H be exploring options to modernize our customer s system enhancements, and improved communica still being evaluated for capabilities, options availa year-to-year.	ades and replacements of various IT related Ils & servers. These are typically replaced on berformance etc. In 2025, there is additional nd switches to maintain functionality and hap" with a vision to harness the potential of ainable digital ecosystem. Our vision is to rticipate in a transition towards a greener, ized work order and service order packages, hardware for field staff. In addition, we will ervice experience through chat bots, phone tion options. Many of these initiatives are able etc. and will be thoroughly evaluated						
	In addition, ERTH has included an additional \$1,75 ERP System (Enterprise Resource Planning). This la Project Assessment form; however, the costs are	In addition, ERTH has included an additional \$1,750,000 in 2026 & 2027 for an upgrade to its ERP System (Enterprise Resource Planning). This large investment is detailed in a separate Project Assessment form; however, the costs are included below.						
Investment Category	General Plant							
Capital Investment								

			Historical Expenditures					Average
		2018	2019	2020	2021	2022	2023	(2018 to 2023)
IT Hardwara 9	Gross (\$)	\$112,621	\$34,983	\$49,150	\$85,160	\$92,683	\$33,669	\$68,044
Software &	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Software	Net (\$)	\$112,621	\$34,983	\$49,150	\$85,160	\$92,683	\$33,669	\$68,044

	Forecast Expenditures						Average	
		2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)
IT Hardwara 9	Gross (\$)	\$164,000	\$344,550	\$1,188,254	\$514,135	\$470,093	\$472,795	\$597,965
Software &	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Jontware	Net (\$)	\$164,000	\$344,550	\$1,188,254	\$514,135	\$470,093	\$472,795	\$597,965

Customer Information	Number of Customer Attachments Customer Load (if available)	ALL ALL
Expected Project Timing	Start Date End Date	Q1 Q4
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 30% 30% 20%

Risks and Mitigation	There are minimal risks associated with the standard hardware replacement program (i.e. laptops, servers, firewalls, etc.) as these types of projects generally follow a predictable schedule. The implementation of additional Digital Roadmap objectives come with risks associated with new technology and software platforms. ERTH has a highly skilled and knowledgeable IT department and will utilize consultants, industry professionals and collaboration groups to help mitigate these risks.
Comparative Information	Each year these types of replacements occur and there is not a great deal of comparative information that is used to adjust or modify the budget from year to year.
REG Investment	This project is not associated with a REG investment
Leave to Construct Approval	This project does not require Leave to Construct approval under section 92 of the OEB Act
	Evaluation Criteria & Information Requirements
<u>Efficiency, Customer Value & Relia</u> Project Drivers	bility The primary driver for IT related purchases is to ensure that the proper systems are in place for staff to be efficient and enable them to perform their job. Other items such as firewalls, servers etc. also take into consideration regulatory requirements and industry best practices with regards to security and data handling. Digital Roadmap initiatives are driven by the need to not only modernize our operations but also improve the way we interact with our customers, partners, employees, and the environment.
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2c) of the DSP.
Project Alternatives	On a high level the alternative to investing in IT is to do nothing or scale back spending and only reactively replace equipment as it fails. This would result in increased O&M costs based on inefficiencies with staff not being able to effectively accomplish their required tasks. ERTH is confident that it will need to digitize its system to meet our customers expectations with regards to improved communication and reliability, energy management, the ability to connect EVs and DERs.
Operational Benefits	Maintaining sufficient IT infrastructure ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Reliability Benefits	Maintaining sufficient IT infrastructure ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Customer Benefits	Maintaining sufficient IT infrastructure ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
<u>Safety</u> Cyber-Security Privacy	IT infrastructure does not directly relate to safety for either the public or employees however it indirectly enables the ability to efficiently provide training to employees, allow customers to report outages and safety concerns, enable effective planning to reduce safety concerns etc.
<u>cyber-secunty, rilvacy</u>	Various security and privacy measure are implemented; ERTH Power is involved in industry working groups and will look to implement and maintain cyber security measures as they evolve within the industry.
2	ALL-DEVICES-IT

<u>Co-ordination, Interoperability</u>	IT projects typically require very little coordination with third parties and distribution infrastructure changes (poles, lines etc.) are minimal. As ERTH evaluates options for software it will ensure that they are coordinated and interoperable as possible with other systems and work flows.
Economic Development	This project does not directly relate to any economic growth, however moving towards a digital utility will enable connections of EVs & DERs.
Environmental Benefits	Minimal environmental benefits are expected, as a direct result of this project however moving towards a digital utility will enable connections of EVs & DERs.
	Category Specific Requirements
<u>System Service Project</u> Assessment of the Benefits to Customers	Maintaining sufficient IT infrastructure ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits. Moving to ESRI GIS will allow ERTH to better prepare for the changing utility environment that will include digital systems, driving many improvements in operations that will ultimately benefit the customer.
Information Related to Regional Planning	Planned IT spending will not be applicable to the regional planning process.
Integration of Advanced Technology	All IT spending will include the implementation of more advanced technology from simple components like upgrade computers to more substantial improvements such as firewalls to maintain security requirements.
System Benefits to Reliability, Efficiency and Safety	Maintaining sufficient IT infrastructure ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Factors Affecting Implementation Timing & Priority	There are minimal risks associated with the timing of these types of projects.
Alternative Solution Analysis	On a high level the alternative to investing in IT is to do nothing or scale back spending and only reactively replace equipment as it fails. This would result in increased O&M costs based on inefficiencies with staff not being able to effectively accomplish their required tasks.

2025 - Project Assessment Form Municipality ALL FRTH **Project Name** Financial/ERP System Upgrade Cost Category Capital Enhancement Project Type **General Information Project Description** This project represents costs associated with an upgrade to our ERP System (Enterprise Resource Planning) System. This investment is included within our IT Hardware & Software Plan however; an assessment form has been completed specifically for it due to the materiality of the project. ERTH Power's current Financial System is outdated and approaching end of support by Microsoft and its associated VARs. The system is not a comprehensive Enterprise Resource Planning solution, thereby causing inefficiencies in operations, data management, and decision-making. Upgrading the ERP system will streamline business processes, improve

ntegration Challenges: Ensuring that the r
nfrastructure and third-party systems may
nitigated with careful planning and testing

		2018	2019	2020	2021	2022	2023	(2018 to 2023)
ERP System	Gross (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
(included in IT	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Plan	Net (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
				Eorocast E	vnondituros			

savings while delivering better service to customers.

		Forecast Expenditures						
		2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)
ERP System	Gross (\$)	\$0	\$0	\$1,166,666	\$583,333	\$0	\$0	\$350,000
(included in IT	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Plan	Net (\$)	\$0	\$0	\$1,166,666	\$583,333	\$0	\$0	\$350,000

Customer Information	Number of Customer Attachments Customer Load (if available)	ALL ALL
Expected Project Timing	Start Date End Date	Q1 Q4
Expected Expenditure Timing	Q1 Q2 Q3 Q4	20% 30% 30% 20%

General Plant

Risks and Mitigation

Investment Category

Capital Investment

Training and Change Management: Upgrading an ERP system will require significant employee training and adjustment to new processes. Proper change management strategies must be in place to minimize disruption.

reliability, and enhance the company's ability to adapt to future challenges. The proposed investment will modernize infrastructure, improve integration, and drive long-term cost

Historical Expenditures

Average

new ERP system integrates smoothly with existing In pose technical challenges, but these can be ir n ξ.

Comparative Information	ERTH is in contact with other Ontario LDCs to understand their experiences with ERP System upgrades.
REG Investment	This project is not associated with a REG investment
Leave to Construct Approval	This project does not require Leave to Construct approval under section 92 of the OEB Act
	Evaluation Criteria & Information Requirements
Efficiency, Customer Value & Reliab	bility
	With the added risk of mental health and burnout of staff in recent years and to mitigate enterprise risk across the organization, ERTH requires the implementation of solutions that will create efficiencies in the organization. An updated ERP system will streamline processes for the organization, leading to reduced manual effort and improved decision making.
Project Drivers	ERTH Power's current Enterprise Resource Planning (ERP) system is outdated, and approaching end of life and product support causing risk along with inefficiencies in operations, data management, and decision-making. Upgrading the ERP system will streamline business processes, improve reliability, and enhance the company's ability to adapt to future challenges. The proposed investment will modernize infrastructure, improve integration, and drive long-term cost savings while delivering better service to customers.
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2c) of the DSP.
Project Alternatives	As product support will no longer be available, maintaining the status quo will present a risk to the organization. As part of the implementation of the ERP, a tender process will be used whereby alternatives will be reviewed and alternate solutions and vendors will be evaluated. At this time, the selected solution is unknown until the evaluation is conducted. Based on cost/benefit analysis, the full scope of the ERP solution will be evaluated thereby contributing to a final prize of the solution and implementation.
Operational Benefits	The current ERP system lacks modern features that streamline operations, such as advanced automation, real-time data processing, human resource management, inventory barcoding, and budgeting analytics. Upgrading will reduce manual processes and improve workflows across departments, from supply chain management to human resources.
Reliability Benefits	ERTHs upgrade of its ERP system aims primarily to enhance operational efficiency, leading to indirect reliability benefits.
Customer Benefits	ERTHs upgrade of its ERP system aims primarily to enhance operational efficiency, leading to indirect benefits for customers through improved back end processes. A modern ERP can offer enhanced customer management tools, leading to improved service levels, faster response times, and better overall customer satisfaction, which is crucial in a highly competitive market.
<u>Safety</u>	ERTHs upgrade of its ERP system aims primarily to enhance operational efficiency, this may lead to improved safety programs, tracking and data however is not a primary objective.
<u>Cyber-Security, Privacy</u>	A new ERP system will comply with all necessary cybersecurity requirements and have more up-to-date security systems in place as compared to our legacy solution.
Co-ordination, Interoperability	
2	ALL-DEVICES-IT

	The implementation of a new ERP system can create interoperability benefits by improving how different software systems, departments, and business processes communicate and work together. This is accomplished with a centralized database, standardized processes, real-time data access, scalability and cross-department collaboration.
Economic Development	Again, ERTHs upgrade of its ERP system aims primarily to enhance operational efficiency, and is not directly linked to economic development however increased efficiency will allow the LDC to better handle economic development.
<u>Environmental Benefits</u>	Implementing a new ERP system can bring environmental benefits by reducing paper usage through digital processes, optimizing resource management, and lowering energy consumption. It improves supply chain efficiency, reduces overproduction and waste, and enables better tracking of sustainability metrics. Additionally, ERP systems help businesses comply with environmental regulations and can support greener supply chain choices.
	Category Specific Requirements
<u>System Service Project</u> Assessment of the Benefits to Customers	See Customer Benefits Section above
System Service Project Assessment of the Benefits to Customers Information Related to Regional Planning	See Customer Benefits Section above Not applicable
System Service Project Assessment of the Benefits to Customers Information Related to Regional Planning Integration of Advanced Technology	See Customer Benefits Section above Not applicable The new ERP system itself will be a new technology with advanced capabilities, offering significant improvements over our current legacy system. We will assess various vendors and compare their features to select the most suitable solution.
System Service ProjectAssessment of the Benefits to CustomersInformation Related to Regional PlanningIntegration of Advanced TechnologySystem Benefits to Reliability, Efficiency and Safety	See Customer Benefits Section above Not applicable The new ERP system itself will be a new technology with advanced capabilities, offering significant improvements over our current legacy system. We will assess various vendors and compare their features to select the most suitable solution. See applicable sections above.
System Service ProjectAssessment of the Benefits to CustomersInformation Related to Regional PlanningIntegration of Advanced TechnologySystem Benefits to Reliability, Efficiency and SafetyFactors Affecting Implementation Timing & Priority	See Customer Benefits Section above Not applicable The new ERP system itself will be a new technology with advanced capabilities, offering significant improvements over our current legacy system. We will assess various vendors and compare their features to select the most suitable solution. See applicable sections above. See Risks & Mitigation section above.

2025 - Project Assessment Form									
ERTH Municipality ALL Project Name ALL-LEASEHOLD-Leasehold Improvements Cost Category Capital Project Type Enhancement									
	Constal Information								
			· .	General I					
Project Description This project represents costs associated with upgrades at the ERTH Aylmer and Goderich Operating Centers. This line item does NOT include any costs associated with the new Ingersoll Operations Center.									
		Gen							
Capital Investr	nent					- 11			
			2010	2010	Historical		2022	2022	Average
	Gross (\$)		\$96,396	\$33,722	\$50.037	\$67,178	\$52.847	\$22.911	\$53.849
Leasehol	d Contributions	(\$)	\$0 \$0	\$33,722	\$0 \$0	\$07,178 \$0	\$52,847 \$0	\$22,511 \$0	\$0
Improveme	Net (\$)	(17	\$96,396	\$33,722	\$50,037	\$67,178	\$52,847	\$22,911	\$53,849
								.	·
					Forecast E	xpenditures	-		Average
			2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)
Less the	Gross (\$)		\$45,000	\$15,000	\$15,300	\$15,606	\$15,918	\$16,236	\$15,612
Leaseno	d Contributions	(\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Improveni	Net (\$)		\$45,000	\$15,000	\$15,300	\$15,606	\$15,918	\$16,236	\$15,612
Expected Proje	rmation ect Timing	Start	omer Load (t Date	omer Attaci (if available))	ALL ALL Q2 Q4			
Expected Expe	End Date Q4 Expected Expenditure Timing Q1 20% Q2 30% Q3 30% Q4 20%								
Risks and Miti	Risks and Mitigation There are minimal risks associated with these types of projects.								
Comparative I	omparative Information Each year these types of replacements occur and there is not a great deal of comparative information that is used to adjust or modify the budget from year to year.								
REG Investmer	nt	This	project is no	ot associate	d with a RE	G investmei	nt		
Leave to Const	Leave to Construct Approval This project does not require Leave to Construct approval under section 92 of the OEB Act								
		Eva	aluation C	riteria & In	formation	Requirem	ents		
Efficiency, Cus	tomer Value & Relia	<u>bility</u>							
Project Drivers	The primary driver for Leasehold Improvement spending is to ensure that the proper facilities are in place for staff to be efficient and enable them to perform their job.								
Investment Pri	ERTH Power implements a software based Investment Optimizer which evaluates multipleInvestment Priorityprojects based on weighted criteria in order to identify, select, prioritize and pace investmentsThis process is detailed in Section 5.4.2c) of the DSP.								
1			ALL-LEASI	EHOLD-Leas	ehold Impr	ovements			

Project Alternatives	The most obvious alternative to yearly leasehold improvements would be constructing new operations centers which do not financially make sense at this point as our current facilities are able to be maintained at a suitable level without too much investment year over year.
Operational Benefits	Maintaining proper facilities ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Reliability Benefits	Maintaining proper facilities ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Customer Benefits	Maintaining proper facilities ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
<u>Safety</u>	Maintaining proper facilities ensures that day-to-day operations are able to be completed as safely as possible.
Cyber-Security, Privacy	Not applicable
<u>Co-ordination, Interoperability</u>	Not applicable
Economic Development	Not applicable
Environmental Benefits	Minimal environmental benefits are expected as a result of spending within this budget.
	Category Specific Requirements
<u>General Plant Project</u> Qualitative & Quantitative Analyses including Assessment of Options	The most obvious alternative to yearly leasehold improvements would be constructing new operations centers which do not financially make sense at this point as our current facilities are able to be maintained at a suitable level without too much investment year over year.
Business Case for projects that substantially exceed the materiality threshold.	Not applicable

		<u>2</u>	<u>025 - Proje</u>	ct Assessm	ent Form			
ERIH Power	Project Name	ALL-VEHICLE	-Fleet Repla	acement		Mu Cos Pro	nicipality st Category ject Type	All Capital Vehicle
			General Information					
Project Descr	intion	This project hudget covers the yearly replacement of rolling stock including large & small						
	iption	vehicles, for Sustainment	vehicles, forklifts, and trailers. The replacement schedule is outlined in the 5-Year Fleet Sustainment Plan.					
Investment C	Category	General Plar	nt					
Capital Inves	tment							
		2010	2010	Historical I	Expenditures	2022	2022	Average
	Groce (\$)	2018	¢107.147	2020	2021	2022	¢240.421	(2018 to 2023)
Fleet	Contributions (\$)	\$03,400 \$0	\$107,147 \$0	\$288,850 \$0	\$200,957 \$0	\$455,952 \$0	\$340,431 \$0	\$255,797 \$0
Replacements	Net (\$)	\$63,466	\$107,147	\$288,850	\$266,957	\$455,932	\$340,431	\$253,797
				<u> </u>	<u> </u>	<u> </u>		
				Forecast E	xpenditures	1	•	Average
		2024 (Bridge)	2025	2026	2027	2028	2029	(2025 to 2029)
Fleet	Gross (\$)	\$882,701	\$697,701	\$445,000	\$445,000	\$350,000	\$575,000	\$502,540
Replacements	Contributions (\$)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
	Net (\$)	\$882,701	\$697,701	\$445,000	\$445,000	\$350,000	\$575,000	\$502,540
Expected Pro	ject Timing	Customer Lo Start Date End Date	oad (if availa	ble)	ALL Q1 Q4			
Expected Exp	enditure Timing	Details Prov	ide in Fleet	Plan				
Risks and Mit	tigation	There are very minimal risks associated with the completion of this project as planned. The primary risk is associated with the timing of the planned expenditures. Since 2020, both large and small vehicle lead times have drastically increased and become more unpredictable. This seems to have stabilized with small vehicles but continues to be an issue with large trucks that currently have an unstable lead time of nearly 3 years.						
Comparative	Information	AVERAGE: \$291,863 2023: \$340,431 2022: \$455,932 2021: \$266,957 2020: \$288,850 2019: \$107,147						
REG Investme	ent	This project	is not assoc	iated with a	REG investi	ment		
Leave to Con	struct Approval	This project	does not re	quire Leave	to Construc	t approval ι	under section	92 of the OEB Ac
		Evaluatio	n Criteria 8	& Informat	ion Requir	ements		
Efficiency, Cu	istomer Value & Relial	pility						

ALL-VEHICLE-Fleet Replacement

Project Drivers	The primary driver for this project is to maintain a fleet that enables staff to be safe and efficient when completing required activities.
Investment Priority	ERTH Power implements a software based Investment Optimizer which evaluates multiple projects based on weighted criteria in order to identify, select, prioritize and pace investments. This process is detailed in Section 5.4.2c) of the DSP. On a more granular level individual vehicles are prioritized based a number of factors outlined in the Fleet Sustainment Plan.
Project Alternatives	There are not really any alternatives to maintaining a fleet capable of safely constructing, maintaining and operating the system. There are however numerous variations of the pace of replacement, type of vehicle etc. ERTH Power looks at its requirements each time a vehicle is scheduled for replacement to see if a smaller/larger version is required, or whether the fleet can be reconfigured to reduce financial requirements.
Operational Benefits	Maintaining proper fleet vehicles ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Reliability Benefits	Maintaining proper fleet vehicles ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Customer Benefits	Maintaining proper fleet vehicles ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Safety	Maintaining proper fleet vehicles ensures that day-to-day operations are as efficient as possible; this relates to almost every aspect of the utility operation and provides operations, reliability and customer benefits.
Cyber-Security, Privacy	Not applicable
Co-ordination, Interoperability	Not applicable
Economic Development	Not applicable
Environmental Benefits	Not applicable
	Category Specific Requirements
<u>General Plant Project</u> Qualitative & Quantitative Analyses including Assessment of Options	There are numerous variations of the pace of replacement, type of vehicle etc. when scheduling fleet replacements. ERTH Powers looks at its requirements each time a vehicle is scheduled for replacement to see if a smaller/larger version is required, or whether the fleet can be reconfigured to reduce financial requirements.
Business Case for projects that substantially exceed the materiality threshold.	Not applicable.



APPENDIX L. Fleet Sustainment Plan





updated: 2024

Contents

xecutive Summary	3
Background	4
Dptimal Fleet	4
Existing Fleet	5
ong Term Fleet Plan	6
inancial Projections	9



Executive Summary

ERTH currently has 10 large vehicles consisting of 7 bucket trucks and 3 RBD's, 17 small vehicles consisting of engineering, operations and metering vans, SUV's and pickup trucks along with multiple trailers and 2 forklifts.

ERTH uses vehicle age as the primary method for creating long term spending projections and then prioritizes replacements on a yearly basis based on condition, maintenance costs, failure risks, and utilization. The following illustrates the guidelines used to project replacements and is compared to the planned replacement age over the next 15 years.

	ERTH Replacement Guidelines	Planned Average Replacement Age
Large Vehicles:	12-15 years	17.25
Small Vehicles:	8-12 years	10.75

Over the next 5 years, ERTH plans to replace four (4) large vehicles and six (6) small vehicles. This will result in an average fleet spend of approximately \$502,540 and does not include trailers or forklift upgrades. This is an increase from the previous 5 year average from 2019-2023 was \$291,863.

ERTH is satisfied with the current performance of our fleet however will need to increase fleet spending over the next five (5) years to ensure our fleet remains reliable and efficient.



Background

In 2010 the Ontario Energy Board (OEB) commissioned Kinetrics to analyze and study the useful life of Local Distribution Companies' assets. Findings from this report revealed that the useful life range for large utility trucks/bucket trucks are 5-15 years and pickups/vans are 5-10 years taking into account utilization and daily conditions under which the equipment operates.

ERTH Power first created a fleet sustainment plan in 2010, which created a road map for long term planning ensuring that we are able to provide safe, reliable hydro service to our customers. ERTH Power service territory creates unique challenges concerning fleet management due to the large geographic area that our communities span. Due to this fact, we operate three (3) operations centers, which makes sharing of fleet resources challenging, and ERTH must own and maintain additional vehicles as compared to a contiguous LDC with a similar customer base. In addition, ERTH vehicles typically experience an increased number of kilometers, again due to the physical separation of each of our communities.

Optimal Fleet

The following is what ERTH has determined to be our optimal fleet as of 2024; any vehicle denoted with an (*) indicates that ERTH will evaluate options of **EV or Hybrid** replacements to align with our environmental goals and corporate mission & vision.

LARGE VEHICLES

INGERSOLL	AYLMER	Goderich
65' Bucket	47' Bucket Truck (Hybrid)	55' Bucket Truck
50' Bucket	Single Axle RBD	47' Bucket Truck
42' Bucket		Tandem Axle RBD
Tandem Axle RBD		
37' Service Truck		

SMALL VEHICLES

INGERSOLL	AYLMER	Goderich
Crew Pickup (2500)	Crew/Foreperson Pickup (2500)	Crew Pickup (2500)
Crew Pickup (2500)		Foreperson Pickup (2500)
Foreperson Pickup (2500)		**Supervisor Pickup (1500)
**Supervisor Pickup (1500)		**Field Services Vehicle (Small Pickup)
Inventory/Dump Truck (F550)		
** Metering Vehicle (Small Van)		
** Metering Vehicle (Small Van)		
** Engineering Vehicle (Small Truck)		
** Engineering Vehicle (XUV)		
** Events Vehicle (EV Bolt)		
**Manager of Ops Vehicle (XUV or Truck)		



Existing Fleet

The existing fleet is detailed below, with any differences between the optimal fleet highlighted in red. In general ERTH is nearing our optimal fleet with a few notable changes that will occur in the future.

- 1. EV or Hybrid options for most small vehicles. ERTH currently has 2/9 vehicles replaced with EV alternatives.
- 2. 50' Bucket Truck in Aylmer to be replaced with a 37' Bucket Truck in Ingersoll. ERTH has determined that a smaller service truck will be less costly to replace, operate and maintain, without compromising our operational abilities.
- 3. 50' Bucket Truck in Goderich replaced with a 47' Bucket Truck. We have again determined that a 47' truck will be less costly to replace, operate and maintain without compromising our operation abilities at the Goderich Ops Center.

LARGE VEHICLES

INGERSOLL	AYLMER	Goderich
65' Bucket	47' Bucket Truck (Hybrid)	55' Bucket Truck
50' Bucket	Single Axle RBD	50' Bucket Truck
42' Bucket	50' Bucket Truck	Tandem Axle RBD
Tandem Axle RBD		
37' Service Truck		

SMALL VEHICLES

INGERSOLL	AYLMER	Goderich
Crew Pickup (2500)	Crew/Foreperson Pickup (2500)	Crew Pickup (2500)
Crew Pickup (2500)		Foreperson Pickup (2500)
Foreperson Pickup (2500)		**Supervisor Pickup (1500)
**Supervisor Pickup (1500)		**Field Services Vehicle (Small Pickup)
Inventory/Dump Truck (F550)		
** Metering Vehicle (Small Van)		
** Metering Vehicle (Small Van)		
** Engineering Vehicle (Small Truck)		
** Engineering Vehicle (XUV)		
** Events Vehicle (EV Bolt)		
**Manager of Ops Vehicle (XUV or Truck)		



Long Term Fleet Plan

The small & large vehicles that are currently in service primarily align with the optimal fleet for each operations center and therefore both small and large vehicles are simply in "maintenance" mode and will be scheduled for replacement based on their end of life.

In order to complete long term planning, vehicle age is used as the primary indicator of replacement requirements. This allows ERTH to determine suitable spending requirements over a long period ensuring that we are able to create a relatively level investment schedule and avoid large increases and decreases year over year. With that being said, when prioritizing vehicles for replacement on a yearly basis we consider condition, maintenance costs, failure risks, and utilization (i.e. the oldest vehicles are not always replaced solely based on vehicle age.)

A snapshot of our fleet age in 2025 vehicle age is shown below:

	Average Age
Large Vehicles:	10.4
Small Vehicles:	6.4

The following indicates ERTH's current guidelines for vehicle useful life and indicates the average replacement age based on the long-term replacement schedule. The guidelines used are within the range provided by Kinetrics in the Asset Depreciation Study for the Ontario Energy Board. ERTH's planned replacement age will typically be older than the guideline in an attempt to keep spending as low as possible while still maintaining a fleet capable of efficiently managing the distribution system.

	ERTH Replacement Guidelines	Planned Average Replacement Age
Large Vehicles:	12-15 years	17.25
Small Vehicles:	8-12 years	10.75



ES
2
Ш
<u>></u>
B
4

Area	Vehicle #	Description	Year	Age	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034
	28-14	65' DBL BUCKET ING	2014	10	10	11	12	13	14	15	16	17	18	19	1
	21-16	50' DBL BUCKET ING (move to GDE)	2016	00	8	6									
Ingersoll	23-20	42' POSI BUCKET ING	2020	4	4	5	9	7	8	6	10	11	12	13	14
	TBD	550 - 40' SERVICE TRUCK	TBD	TBD			1	2	ŝ	4	ß	9	7	80	6
	08-23	900-52 RBD ING	2023	1	1	2	3	4	5	9	7	8	6	10	11
	09-16	50' DBL BUCKET AYL	2016	∞	∞	6	10	11	12	13	14	15	16	17	1
Andrea	05-07	47' POSI BUCKET AYL	2007	17	17	18	1	2	ŝ	4	ß	9	7	∞	6
Aymen	22-06	50-48 RBD ING	2006	18	18	19	20	21	1	2	ŝ	4	5	9	7
	08-07	40-47 RBD AYL	2007	17											
	103-09	55' DBL BUCKET GDE	2009	15	15	16	17								
Codorich	21-16	50' DBL BUCKET ING (from ING)	2016	00			10	11	12	13	1	2	ŝ	4	5
douellell	15-09	50' DOUBLE BUCKET POSI GDE	2010	14	e	4	ß	9	7	8	6	10	11	12	13
	102-14	50-48 RBD Terex GDCH	2014	10	10	11	12	13	14	15	16	17	1	2	3
				Average Age	9.4	10.4	8.8	6	7.9	8.9	8.6	9.6	8.9	6.9	7.3
SMALL V	'EHICLES														
	Webble #					1000			0.00	0000	0000				

Area	Vehicle #	Description	Year	Age	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034
	12-14	CHEV SILVERADO - ING - SUPV (1500)	2014	10	10	11	12	1	2	e	4	5	9	7	8
	10-22	DODGE RAM - ING - FOREMAN (2500)	2022	2	e	4	ъ	9	7	6	10	1	2	ŝ	4
Ingersoll	29-23	GMC SIERRA - ING - CREW (2500)	2023	1	1	2	ю	4	Ŋ	9	7	∞	6	10	11
	101-11	GMC SIERRA - AYL - CREW (2500)	2011	13	13	13	14	15	15	16	17	17	18	19	19
	35-19	FORD 550 - ING - OPS/STORES Dump	2019	5	9	7	8	6	10	11	12	13	14	1	2
Aylmer	06-20	CHEV SILVERADO - AYL - FOREMAN 3/4	2020	4	4	5	9	7	8	6	10	11	1	2	3
	27-17	CHEV SILVERADO - GDE - SUPV (1500)	2017	7	∞	6	10	11	1	2	m	4	2	9	7
Codevich	14-22	DODGE RAM - GDE - FOREMAN (2500)	2022	2	e	4	Ŋ	9	7	8	6	10	11	1	2
סמפוומו	110-23	GMC SIERRA - GDE - CREW (2500)	2012	12	2	ŝ	4	ß	9	7	8	6	10	11	12
	30-16	CHEV COLORADO - GDE - FIELD SERVICES	2016	8	8	6	10	11	12	1	2	3	4	5	9
	24-17	NISSAN VAN - ING - METERING	2017	7	7	1	2	æ	2	'n	4	с	4	ъ	4
	34-20	NISSAN VAN - ING - METERING	2020	4	4	5	9	7	1	2	ŝ	1	2	ŝ	4
lood	TBD	EQUINOX EV	2024	0	1	2	ŝ	4	ß	9	7	∞	6	10	11
Vehicles	43-18	CHEV BOLT EV - ING - COMMS/REL	2018	9	9	7	∞	6	10	11	12	13	1	2	ŝ
	TBD	F150 LIGHTNING	TBD	TBD		1	2	ŝ	4	ъ	9	7	∞	6	10
	106-14	TOYOTA TACOMA - GDCH - FIELD SERV.	2014	10	10	11	12	13	14	15	1	2	ŝ	4	S
	N/A	CHEVY EQUINOX - ING -OPS MNGR	2018	9	9	7	8	6	10	11	1	2	3	4	5
				Average Age	6.7	6.4	6.9	7.2	7.0	7.4	6.8	6.9	6.5	6.0	6.8
				[2]											

Fleet Sustainment Plan



>	/ehicle #	Description	Replacement \$	2024	2025	2026	2027	2028	2029
	05-07	47' POSI BUCKET AYL	\$592,701		\$462,701				
	TBD	550 - 40' SERVICE TRUCK	\$300,000			\$300,000			
•	22-06	50-48 RBD ING	\$450,000			\$125,000	\$325,000		
s	21-16	50' DBL BUCKET ING	\$625,000					\$150,000	\$475,000
	102-14	50-48 RBD Terex GDCH	\$450,000						
			SUB TOTAL	\$0	\$462,701	\$425,000	\$325,000	\$150,000	\$475,000
	TBD	EQUINOX EV	\$60,000	\$60,000					
	TBD	F150 LIGHTNING	\$100,000		\$100,000				
	24-17	NISSAN VAN - ING - METERING	\$80,000		\$80,000				
	12-14	CHEV SILVERADO - ING - SUPV (1500)	\$100,000				\$100,000		
	27-17	CHEV SILVERADO - GDE - SUPV (1500)						\$100,000	
	34-20	NISSAN VAN - ING - METERING						\$80,000	
n	30-16	CHEV COLORADO - GDE - FIELD SERVICES							\$80,000
	N/A	CHEVY EQUINOX - ING -OPS MNGR							
	106-14	TOYOTA TACOMA - GDCH - FIELD SERV.							
	10-22	DODGE RAM - ING - FOREMAN (2500)							
			SUB TOTAL	\$60,000	\$180,000	¢0	\$100,000	\$180,000	\$80,000
	TBD	ING - Job/Reel Trailer w/ Brake	\$30,000	\$30,000					
c	T-52	AYL - Job/Reel Trailer w/ Brake	\$35,000		\$35,000				
y N B	All	Paint & Refurbishment	\$20,000		\$20,000	\$20,000	\$20,000	\$20,000	\$20,000
;		Forklift Replacement							
			SUBTOTAL	\$30,000	\$55,000	\$20,000	\$20,000	\$20,000	\$20,000
			TOTAL	\$90,000	\$697,701	\$445,000	\$445,000	\$350,000	\$575,000
				\$419,088	\$419,088	\$419,088	\$419,088	\$419,088	\$419,088

The fleet replacement plan is balanced with small & large vehicles purchases to create a relatively level capital spend from year-to-year.

Financial Projections

[9] Fleet Sustainment Plan



